

Cover code

```
% \usepackage{incgraph}
% \usetikzlibrary{backgrounds}
\begin{inctext}%
\gtrSymbolsSetCreateSelected{blue}{Male}\gtrSymbolsSetCreateSelected{red}{Female}%
\gtrSymbolsSetCreateSelected{black}{Neuter}%
\begin{tikzpicture}
\genealogytree[template=symbol nodes,level size=8mm,level distance=6.5mm,
box={title={\gtrnodenumber},height=5mm,attach boxed title to bottom center,
fonttitle=\fontsize{3mm}{3mm}\sffamily,
boxed title style={size=tight,height=3mm,valign=center,left=0.2mm,right=0.2mm}},
tcbset={mytext/.style={notitle,interior style={top color=gtr_Yellow_Frame!50!gtr_Yellow_Back,
bottom color=gtr_Yellow_Frame!50!gtr_Yellow_Back,middle color=gtr_Yellow_Back}}},
add parent=a to fam_a,add parent=b to fam_b,add parent=c to fam_c]
{ child{ gm pf
  child{ pm gf cm child{ gm pf cf child{ gm pf cf cm cm child{ gm pf
    child{ gm pf cf child{ gm pf cf child{ gm pf child{ gm pf cf cm cm } cf cm c[id=a]m } cm
      } cm } cm cm } } cm } cf cf cf
    child{ gm pf cf cm cm child{ gm pf cf cm cm child{ gm pf child{ gm pf cf
      child{ g[box={width=6.5cm,notitle},phantom*]m
        child{g[box={width=6.5cm,height=23mm,enlarge top initially by=-15mm,mytext},
          no content interpreter]{\Huge\bfseries genealogytree}
        child[id=fam_a] {gf cm cf cm
          child{ gm pf cf cm child{ gm pf cf child{ gm pf cf cm
            child[id=fam_b]{ gm cf cf child{ gm pf cf
              child{ gm pf cm cf cf cm cm
                child{ gm pf cm child{ gm pf cm cf child{ gm pf child{ gm pf cm cf cm cf }
                  cm cf cm cf } cm cf } cf cm cf }
                child{ gm pf cm cf cm cf }
                child[id=fam_c,pivot shift=2cm]{ g[distance=1cm]m cm child { gm pf cm
                  child{ gm pf cm cm cf cf cf cm cm cf } cm
                  child{ gm pf cf cm child{ gm pf cm cm cf cf cf cm cm cf } cm cf }
                  cf } } }
                cm cm } cm cm } } cm cm } cm } cm cf cm
              } cm cf cf cm cm cm cf }
            } cm } cf cm cm } }
          }
        } cm cm
        child{ gm pf cm cf cm cm cf }
        child{ gm pf child{ pm gf child{ gm pf cm cf cm } } cf cm cf cm }
        union{ pf cm cm cf
          child{ gm pf child{ gm pf cf cm child{ gm pf child{ gm pf
            child{ gm pf cf child{ gm pf cf child{ gm pf child{ gm pf
              child{ gm pf cf child{ gm pf child{ gm pf c[id=b]f cm cm } cf cm cm
              child{ g[box={width=4cm,notitle},phantom*]m
                child{g[box={width=4cm,height=23mm,enlarge top initially by=-15mm,
                  mytext,capture=minipage,halign=center},no content interpreter]
                  {\large\bfseries Manual for\ version\ \ version\(\datum)}
                  cm cf cm cm child{ gm cf cm cf cm
                    child{ g[box={width=4cm,mytext},no content interpreter]{Thomas F.-Sturm} }
                    c[id=c]f cm } cf cm }
                  } } cm cm } cf cm cm } cf cm cm } cm cm }
                  cm child{ gm pf cf cm cm } cm cm cm } cf cm cm } cf cm cm } cm
                } cf cm cm
              }
            }
          } }
        }
      }
    }
  }
}
\begin{scope}[on background layer]
\node (bg) [fill tile image*={width=4cm}{crinklepaper.png},minimum width=21cm,
minimum height=29.7cm,inner sep=0pt,outer sep=0pt] at (current bounding box) {};
\path[top color=white,bottom color=red,fill opacity=0.25]
(bg.south west) rectangle (bg.north east);
\end{scope}
\end{tikzpicture}
\end{inctext}
```

The genealogytree package

Manual for version 2.4.0 (2026/05/06)

Thomas F. Sturm¹

<https://www.ctan.org/pkg/genealogytree>

<https://github.com/T-F-S/genealogytree>

Abstract

Pedigree and genealogy tree diagrams are proven tools to visualize genetic and relational connections between individuals. The naming for mathematical tree structures with parent nodes and child nodes is traded from historical family diagrams. However, even the smallest family entity consisting of two parents and several children is no mathematical tree but a more general graph.

The **genealogytree** package provides a set of tools to typeset such genealogy trees or, more precisely, to typeset a set of special graphs for the description of family-like structures. The package uses an auto-layout algorithm which can be customized to e.g. prioritize certain paths.

Contents

1	Introduction	9
1.1	Genealogy Trees	9
1.2	Package Design Principles and Philosophy	10
1.3	Comparison with Other Packages	11
1.4	Installation	12
1.5	Loading the Package	12
1.6	Libraries	13
1.7	How to Get Started	13
2	Tutorials	15
2.1	Tutorial: First Steps (Ancestor Tree)	15
2.1.1	Document Setup	15
2.1.2	Creation of a Basic Ancestor Diagram	16
2.1.3	Applying options	18
2.1.4	Growing the Tree	19
2.1.5	Prioritize and Colorize a Path	22
2.1.6	Changing the Timeflow	24
2.2	Tutorial: Diagram Manipulation by ID values (Descendant Tree)	25
2.2.1	Creation of a Basic Descendant Diagram	25
2.2.2	Growing the Tree	26
2.2.3	Separating Diagram Data and Diagram Drawing	29
2.2.4	Emphasizing a Relationship Path	30
2.2.5	Coloring Subtrees	32
2.3	Tutorial: A Database Family Diagram (Sand Clock)	34
2.3.1	Creation of a Basic Sand Clock Diagram	34
2.3.2	Node Content in Database Format	35

¹Prof. Dr. Dr. Thomas F. Sturm, Institut für Mathematik und Informatik, University of the Bundeswehr Munich, D-85577 Neubiberg, Germany; email: thomas.sturm@unibw.de

2.3.3	Formatting the Node Content	36
2.3.4	Adding Images	38
2.3.5	Full Example with Frame	39
2.4	Tutorial: Descendants of the Grandparents (Connecting Trees)	43
2.4.1	Descendants of the Two Grandparents	43
2.4.2	Connected Diagram	44
2.5	Tutorial: Multi-Ancestors	46
2.5.1	Triple Ancestor Example	46
2.5.2	Adding Edges Manually	47
2.5.3	Manual Position Adjustments	48
2.6	Tutorial: Externalization	49
2.6.1	Externalization Process	49
2.6.2	Document Setup	49
2.6.3	Marking Diagrams for Externalization	50
2.7	Tutorial: Conversion to Pixel Images	52
2.7.1	Command Line Conversion with MuPDF	52
2.7.2	Command Line Conversion with Ghostscript	52
2.7.3	Command Line Conversion with ImageMagick	53
2.7.4	Conversion with the 'standalone' Package	53
2.7.5	Conversion during Externalization	54
3	Genealogy Tree Macros	55
3.1	Creating a Genealogy Tree	55
3.2	Using Tree Options	58
3.3	Accessing Information inside Nodes	59
3.4	Auxiliary Tools	61
4	Graph Grammar	63
4.1	Graph Structure	63
4.2	Subgraph 'parent'	65
4.3	Subgraph 'child'	67
4.4	Subgraph 'union'	69
4.5	Subgraph 'sandclock'	71
4.6	Node 'c'	73
4.7	Node 'p'	73
4.8	Node 'g'	73
4.9	Data 'input'	74
4.10	Control Sequence 'insert'	75
5	Option Setting	77
5.1	Option Priorities	77
5.1.1	Option Priorities for Nodes	78
5.1.2	Option Priorities for Families	79
5.2	Graph Growth Setting (Time Flow)	80
5.3	Graph Geometry	83
5.4	Identifiers	92
5.5	Node Options	95
5.6	Family Options	104
5.7	Subtree Options	107
5.8	Level Options	109
5.9	Tree Positioning Options	111
5.10	TikZ and Tcolorbox Options	114

5.11	Ignoring Input	117
5.12	Inserting Input	121
5.13	Phantom Nodes and Subtrees	125
5.14	Childless Families	128
5.15	Autofill Parent Graphs (Ancestors)	132
5.16	Special and Auxiliary Options	136
6	Node Data (Content) Processing	137
6.1	Setting a Node Data Processing and Processor	138
6.2	Predefined Non-Interpreting Processings	139
6.2.1	fit	139
6.2.2	tcolorbox	143
6.2.3	tcbox	146
6.2.4	tcbox*	149
6.2.5	tikznode	152
6.3	Creating a Customized Non-Interpreting Processor	154
6.4	Content Interpreters	155
7	Database Processing	161
7.1	Database Concept	162
7.2	Example Settings	163
7.3	Data Keys	165
7.4	Input Format for Dates	172
7.5	Formatting the Node Data	174
7.6	Formatting Names	184
7.7	Formatting Dates	186
7.8	Formatting Places	190
7.9	Formatting Events	191
7.10	Formatting Lists of Events	194
7.11	Formatting Comments	196
7.12	Formatting Professions	197
7.13	Formatting Lists of Information	198
7.14	Formatting Sex	199
7.15	Formatting Images	200
7.16	Formatting Ages	202
8	Edges	203
8.1	Edge Settings	204
8.2	Edge Types	208
8.3	Edge Parameters	213
8.4	Edge Labels	217
8.5	Edge Labels Database	219
8.6	Adding and Removing Nodes from Edge Drawing	221
8.7	Extra Edges	226
8.8	Edge Shifting	231
9	Genealogy Symbols	237
9.1	Symbol Color Settings	237
9.1.1	Global Color Settings	237
9.1.2	Local Color Settings	238
9.2	List of Symbols	239
9.3	Legend to Symbols	243

9.3.1	Printing a Legend	243
9.3.2	Description Texts and Language Settings	244
10	Language and Text Settings	247
10.1	Preamble Settings	247
10.2	Document Settings	248
11	Debugging: Library  debug	249
11.1	Parser Debugging	249
11.2	Processor Debugging	252
11.3	Graphical Debugging	261
11.4	Show Information	265
12	Templates: Library  templates	269
12.1	Using Templates	269
12.2	Template 'formal graph'	269
12.3	Template 'signpost'	270
12.4	Template 'symbol nodes'	270
12.5	Template 'tiny boxes'	271
12.6	Template 'tiny circles'	271
12.7	Template 'medical'	272
12.8	Template 'directory'	274
12.9	Template 'database pole'	275
12.10	Template 'database pole reduced'	277
12.11	Template 'database poleportrait'	278
12.12	Template 'database poleportrait reduced'	280
12.13	Template 'database portrait'	281
12.14	Template 'database portrait reduced'	283
12.15	Template 'database traditional'	284
12.16	Template 'database traditional reduced'	285
12.17	Template 'database sideways'	286
12.18	Template 'database sideways reduced'	288
12.19	Template 'database sidewaysportrait'	289
12.20	Template 'database sidewaysportrait reduced'	290
12.21	Template 'database relationship'	291
12.22	Template 'ahnentafel 3'	292
12.23	Template 'ahnentafel 4'	294
12.24	Template 'ahnentafel 5'	296
12.25	Template 'a4paper 3'	298
12.26	Template 'a4paper 4'	299
12.27	Template 'a3paper 5'	300
12.28	Template 'letterpaper 3'	301
12.29	Template 'letterpaper 4'	301
12.30	Template 'display 16:9 3'	302
12.31	Template 'display 16:9 4'	303
12.32	Template 'display 16:9 5'	304
12.33	Template 'display 16:10 3'	305
12.34	Template 'display 16:10 4'	305
12.35	Template 'display 16:10 5'	305
12.36	Border Size Options	306
12.37	Predefined Colors of the Library	308
12.38	Auxiliary Control Sequences	309

13 Fancharts: Library	311
13.1 Fan Chart Diagrams	311
13.2 Geometry Options	314
13.3 Segment Text Options	320
13.4 Color and Style Options	322
13.5 Templates	335
13.5.1 Template 'spartan'	335
13.5.2 Template 'malefemale sober'	336
13.5.3 Template 'malefemale relation'	336
13.5.4 Template 'colorwheel sober'	337
13.5.5 Template 'colorwheel serious'	337
13.5.6 Template 'colorwheel malefemale'	338
13.5.7 Template 'colorwheel rich'	338
13.5.8 Template 'colorwheel opulent'	339
13.5.9 Template 'wave sober'	339
13.5.10 Template 'wave serious'	340
13.5.11 Template 'wave malefemale'	340
13.5.12 Template 'wave rich'	341
13.5.13 Template 'wave opulent'	341
13.5.14 Template 'radial sober'	342
13.5.15 Template 'radial serious'	342
13.5.16 Template 'radial malefemale'	343
13.5.17 Template 'radial rich'	343
13.5.18 Template 'radial opulent'	344
13.6 Advanced Customization	345
14 Auto-Layout Algorithm	349
14.1 Preliminaries	349
14.1.1 Aesthetic Properties	349
14.1.2 Genealogy Trees	350
14.1.3 Graph Grammar	350
14.2 Requirements	351
14.2.1 Parent and Child Alignment	351
14.2.2 Patchwork Families	352
14.2.3 Graph Growing Direction	353
14.3 Algorithmic Steps	354
14.3.1 Recursive Family and Node Placement	354
14.3.2 Contours	354
14.3.3 Combining Subtrees	355
14.4 Known Problems	356
15 Example Graph Files	359
15.1 example.option.graph	359
15.2 example.database.graph	360
15.3 example.formal.graph	361
15.4 example.neumann.graph	362
16 Stack Macros	367
16.1 Creating a Stack	367
16.2 Push to a Stack	367
16.3 Pop from a Stack	368
16.4 Peek into a Stack	368


16.5 Creating Stack Shortcuts	369
Bibliography	371
Index	373

1


Introduction

1.1 Genealogy Trees


The naming for mathematical tree structures with parent nodes and child nodes is traded from historical family diagrams. But, creating a family diagram for medical and sociological studies or family research can become surprisingly difficult with existing tools for tree visualization. The simple reason is, that a mathematical tree has only *one* parent node for its direct children nodes.



With reverse logic, this can be used to visualize ancestor diagrams starting from an individual to its predecessors:




However, even the smallest *family* entity consisting of two parents and several children is no mathematical tree but a more general graph:




The `genealogytree` package aims to support such graphs which will be denoted *genealogy trees* in the following. The graphs to be processed cannot become arbitrarily complex. A set of special graphs for the description of family-like structures is supported by the package algorithms. From at theoretical point of view, these graphs can be seen as a sort of annotated mathematical trees.

1.2 Package Design Principles and Philosophy

The emphasis of a *genealogy tree* is not the node or individual, but the *family*. A family is a set of arbitrarily many parents and children. From an algorithmic point of view, there could be more than two parents in a family.



A node is either a parent or a child to a specific family. A node can also be child to one family and parent to another (or many) families. Such a node is called a **g-node** (genealogy node) in the following.



The main restriction of the graph grammar is that there is exactly *one* **g-node** which connects its enclosing family to another one. In the example above, the father node is the **g-node** in the grandparents family. It is linked to the family with mother and children.

A strong driving force for elaborating and creating this package was to balance two contradictory goals for diagram generation: **automatism** and **customization**. In the ideal case, a diagram would be constructed automatically by data provided from an external data source and would also be freely customizable in any thinkable way starting changing colors, lines, shapes, node positioning, etc. In the real world, a trade-off between these goals has to be found.

Automatism:

- For a set of *genealogy trees* described by a grammar, see Chapter 4 on page 63, an auto-layout algorithms computes the node positioning.
- The graph grammar is family-centric and supports ancestors and descendants diagrams. For the later, multiple marriages can be used to a certain degree.
- The graph data can be written manually, but the package design is adjusted to process automatically generated data. There are many genealogy programs which manage family related data. The general idea is that such programs export selected diagram data in a text file using the provided grammar. Processing GEDCOM¹ files directly by the package is not possible.
- While manipulations like coloring a single node can be done directly at node definition, the package design makes a lot of efforts to allow manipulations *aside* from the actual place of data definition, see Section 5.1.1 on page 78 and Section 5.1.2 on page 79. The idea is that automatically generated data has not to be edited, but can be manipulated from outside. Also, an automatically or manually generated data set can be used for several distinct diagrams; e.g. the graph data in Section 15.1 on page 359 is used numerous times inside this document for different diagrams.

¹GEDCOM (GEnealogical Data COMMunication) is a widely used data exchange format.

- The auto-layout algorithm is implemented in pure T_EX/L^AT_EX (without Lua). This imposes all programming restrictions of this macro language on the implementation, but makes the package independent of external tools and fosters L^AT_EX customization.

Customization:

- The auto-layout algorithm can be customized to e.g. prioritize certain paths or exclude selected subtrees. Also, several node dimensions and distances can be changed globally or locally.
- The appearance of a node can be customized with all capabilities of TikZ [5] and tcolorbox [4]. Also, the node text can be processed.
- For the node content, a database concept can be used, see Chapter 7 on page 161. This gives a high degree of customizing the data visualization inside the node.
- The geometry of edges between nodes is not considered by the auto-layout algorithm, but edges can also be customized in many ways, see Chapter 8 on page 203.
- Several *genealogy tree* diagrams can be interconnected manually to form a more complex total diagram.

On the technical side, the package is based on *The TikZ and PGF Packages* [5] and uses *The tcolorbox package* [4] for the nodes. Since all processing is done in T_EX/L^AT_EX without Lua and external tools, one should expect a lot of processing time for complex diagrams. Therefore, using an externalization of the diagrams is recommended.


1.3 Comparison with Other Packages

This is not really a comparison, but more a hinting to other possibilities for graph drawing. I am not aware of another package with focus on *genealogy trees* as defined here, but surely there are excellent other graph drawing packages. The first to name is TikZ itself. There, one will find a bunch of graph drawing tools with different algorithms, partly implemented in Lua. The second one is the `forest` package which is also very powerful and does not need Lua.

1.4 Installation

Typically, `genealogytree` will be installed as part of a major L^AT_EX distribution and there is nothing special to do for a user.

If you intend to make a local installation *manually*, you have to install not only `genealogytree.sty`, but also all `*.code.tex` files in the local `texmf` tree.



1.5 Loading the Package

The base package `genealogytree` loads the package `tcolorbox` [4] with its `skins`, `fitting`, and `external` libraries. This also loads several other packages are loaded, especially `tikz` [5] with its `arrows.meta` and `fit` libraries.

`genealogytree` itself is loaded in the usual manner in the preamble:

```
\usepackage{genealogytree}
```

The package takes option keys in the key-value syntax. Alternatively, you may use these keys later in the preamble with `\gtruselibrary`^{→P.13} (see there). For example, the key to use debug code is:

```
\usepackage[debug]{genealogytree}
```

1.6 Libraries

The base package `genealogytree` is extendable by program libraries. This is done by using option keys while loading the package or inside the preamble by applying the following macro with the same set of keys.

U 2017-01-20

```
\gtruselibrary{<key list>}
```

Loads the libraries given by the `<key list>`.

```
\gtruselibrary{all}
```

The following keys are used inside `\gtruselibrary` respectively `\usepackage` without the key tree path `/gtr/library/`.

`/gtr/library/debug`

(LIB debug)

Loads additional code for debugging a *genealogy tree*. This is also useful for displaying additional informations during editing a graph; see Chapter 11 on page 249.

`/gtr/library/templates`

(LIB templates)

Loads additional code for templates. These are styles to set various options by one key; see Chapter 12 on page 269.

`/gtr/library/fanchart`

(LIB fanchart)

Loads additional code to draw ancestor fancharts. Therefor, the auto-layout algorithm is replaced by a specialized other algorithm; see Chapter 13 on page 311.

`/gtr/library/all`

(style, no value)

Loads all libraries listed above.

For the curious readers: There are additional *core* libraries which are loaded automatically and which are not mentioned here. Also, languages are special libraries which are loaded by `\gtrloadlanguage` ^{→ P. 248}.

Third party libraries (denoted external libraries) can also be loaded using `\gtruselibrary`, if they follow the file naming scheme `gtrlib.<key>.code.tex`

```
% Loading 'gtrlib.foofoo.code.tex'
\gtruselibrary{foofoo}
```

Note that such external libraries are not version-checked as internal libraries are.

1.7 How to Get Started

You don't have to read this long document to start creating your first *genealogy tree*. A good starting point is to browse through the tutorials in Chapter 2 on page 15 and simply try some of them on your computer. The package provides a lot of options and allows many adjustments to node setting, but you do not need to know them in advance to create the first examples.

You should also take a look at Chapter 12 on page 269, where template examples are shown which could be useful instantly.

For using advanced features, it is not harmful to know at least the basics of `TikZ` [5] and `tcolorbox` [4], since `genealogytree` is based on both.

2

Tutorials

2.1 Tutorial: First Steps (Ancestor Tree)

2.1.1 Document Setup

Most examples in this documentation will display some *code snippets* which one can use in a document with proper set-up. This very basic tutorial will create a tiny full document. If this does not work on your system, there is probably some installation problem. Typically, this can be solved by just updating the T_EX distribution.

The very first document just tests, if the package is installed:

```
\documentclass{article}
\usepackage[all]{genealogytree}
\begin{document}
  \section{First Test}
  Package loaded but not used yet.
\end{document}
```


1 First Test
Package loaded but not used yet.

2.1.2 Creation of a Basic Ancestor Diagram

Now, we start with the very first *genealogy tree*. Such trees are *family-centric*. So, let us begin with a family consisting of mother and father and three children. Chapter 4 on page 63 tells us, that there are different kinds of families; the two main ones are **parent** and **child**. For a single family, the choice is quite irrelevant. Here, we think about extending the example to grandparents. Therefore, we take the **parent** construct.

Before the details are discussed, let us try a full example:

```
\documentclass{article}
\usepackage[all]{genealogytree}
\begin{document}
\section{First Test}
\begin{tikzpicture}
\genealogytree{
  parent{
    g{first child}
    c{second child}
    c{third child}
    p{father}
    p{mother}
  }
}
\end{tikzpicture}
\end{document}
```




The environment `tikzpicture` is the main picture environment from the TikZ [5] package. `\genealogytree`^{→P. 55} can only be used inside such an environment.

When testing this example, be very sure about setting all braces properly. The internal parser will react very sensitive on input errors. Of course, this is nothing new for a \TeX user, but larger trees will have a lot of hierarchical braces and error messages will likely not be very talkative about *where* the error is.

The `genealogytree` package uses `{}` pairs for structuring and `[]` pairs for options like *typical* \LaTeX does.

In the following, we will not see full documents but *code snippets* and their output. Note that the full example used the `all` option to load all libraries of `genealogytree`, see Section 1.6 on page 13. You should also add all libraries for testing the examples. Later, you may choose to reduce the libraries.

Let us look at our example again with focus on the relevant part:




Our **parent** family has two parents denoted by **p** and three children, two of them denoted by **c** as expected. But one child, not necessarily the first one, is denoted by **g**. This is the **g**-node which connects a family *uplink* to another family. Here, we have a single family which is the root family where no *uplink* exists. Nevertheless, a **g**-node has to be present.

2.1.3 Applying options


Certainly, the size and distance of the nodes can be changed. A quick way to adapt the graph is to use preset values from a given `/gtr/template`^{→P. 269}. We put this to the option list of `\genealogytree`^{→P. 55}.

```
\begin{tikzpicture}
  \genealogytree[template=signpost]{
    parent{
      g{first child}
      c{second child}
      c{third child}
      p{father}
      p{mother}
    }
  }
\end{tikzpicture}
```



Options can also be set for families and nodes. We enhance our *genealogy tree* by giving `/gtr/male`^{→P. 101} and `/gtr/female`^{→P. 101} settings to the nodes:


```
\begin{tikzpicture}
  \genealogytree[template=signpost]{
    parent{
      g[female]{first child}
      c[male]{second child}
      c[female]{third child}
      p[male]{father}
      p[female]{mother}
    }
  }
\end{tikzpicture}
```



2.1.4 Growing the Tree


As next step, the father node shall get a grandfather and a grandmother. For this, the father node has to become a **g**-node which links the grandparents family to the root family:

```
\begin{tikzpicture}
\genealogytree[template=signpost]{
  parent{
    g[female]{first child}
    c[male]{second child}
    c[female]{third child}
    parent{
      g[male]{father}
    }
    p[female]{mother}
  }
}
\end{tikzpicture}
```



Visually, nothing happened. But, the father node is now **g**-node of a new family. As in our root family, we can add parents **p** and even other children **c**. Of course, these other children are the siblings of the father node:

```
\begin{tikzpicture}
\genealogytree[template=signpost]{
  parent{
    g[female]{first child}
    c[male]{second child}
    c[female]{third child}
    parent{
      c[female]{aunt}
      g[male]{father}
      c[male]{uncle}
      p[male]{grandfather}
      p[female]{grandmother}
    }
    p[female]{mother}
  }
}
\end{tikzpicture}
```




One could replace all parents **p** by **parent** families with a single **g**-node. This would increase the expense, but can be a good thing when editing and compiling a tree step by step.

We now prepare our tree for expansion and replace mother, grandfather, and grandmother with


appropriate **parent** families.

```
\begin{tikzpicture}
\genealogytree[template=signpost]{
  parent{
    g[female]{first child}
    c[male]{second child}
    c[female]{third child}
    parent{
      c[female]{aunt}
      g[male]{father}
      c[male]{uncle}
      parent
      {
        % former 'p' node
        g[male]{grandfather}
      }
      parent{
        % former 'p' node
        g[female]{grandmother}
      }
    }
  }
  parent
  {
    % former 'p' node
    g[female]{mother}
  }
}
\end{tikzpicture}
```



Again, we populate the three added families with parents **p** and children **c**.

```
\begin{tikzpicture}
\genealogytree[template=signpost]{
  parent{
    g[female]{first child}
    c[male]{second child}
    c[female]{third child}
    parent{
      c[female]{aunt}
      g[male]{father}
      c[male]{uncle}
      parent
      {
        g[male]{grandfather}
        p[male]{great-grandfather}
        p[female]{great-grandmother}
      }
      parent{
        g[female]{grandmother}
        p[male]{great-grandfather 2}
        p[female]{great-grandmother 2}
        c[male]{granduncle}
      }
    }
  }
  parent
  {
    c[male]{uncle 2}
    g[female]{mother}
    p[male]{grandfather 2}
    p[female]{grandmother 2}
  }
}
\end{tikzpicture}
```



2.1.5 Prioritize and Colorize a Path

After the tree has been grown to its final size, we want to influence the node positions. Let us assume that the lineage from *first child* to *great-grandmother 2* has to be especially emphasized.

To prioritize a node, the `/gtr/pivot`^{→P.97} option can be used. This will place a node centered in relation to its ancestors and/or descendants. If this option is used for several connected nodes, a straight lineage is generated. All other nodes are placed automatically to respect this lineage.

```
%...  
    g[pivot,female]{first child}  
%...
```

To emphasize this lineage further, the respective nodes should be colorized differently. With standard settings, every node is drawn as a `tcolorbox`. Box options are given by `/gtr/box`^{→P.98}. The options inside `/gtr/box`^{→P.98} are `tcolorbox` options [4]. To add a yellowish background color and glow, we use:

```
%...  
    g[pivot,box={colback=yellow!20,no shadow,fuzzy halo},female]{first child}  
%...
```

All option settings are `pgfkeys` options. So, it is easy to create a new option style `highlight` which can be used for each node in the lineage. This can be done by `\gtrset`^{→P.58} or inside the option list of `\genealogytree`^{→P.55}.

```
\gtrset{highlight/.style={pivot,box={colback=yellow!20,no shadow,fuzzy halo}}}
```

Now, `highlight` can be used to apply `/gtr/pivot`^{→P.97} and `/gtr/box`^{→P.98} settings with one key word:


```
%...  
    g[highlight,female]{first child}  
%...
```



```

\begin{tikzpicture}
\genealogytree[template=signpost,
highlight/.style={pivot,box={colback=yellow!20,no shadow,fuzzy halo}},
]{
parent{
g[highlight,female]{first child}
c[male]{second child}
c[female]{third child}
parent{
c[female]{aunt}
g[highlight,male]{father}
c[male]{uncle}
parent
{
g[male]{grandfather}
p[male]{great-grandfather}
p[female]{great-grandmother}
}
parent{
g[highlight,female]{grandmother}
p[male]{great-grandfather 2}
p[highlight,female]{great-grandmother 2}
c[male]{granduncle}
}
}
parent
{
c[male]{uncle 2}
g[female]{mother}
p[male]{grandfather 2}
p[female]{grandmother 2}
}
}
}
\end{tikzpicture}


```



2.1.6 Changing the Timeflow

A *genealogy tree* may be grown in four directions depending on the given `/gtr/timeflow`^{P. 80}. Now, we will let the time flow to the left. Additionally, we replace the `/gtr/template`^{P. 269} setting by individual settings for `/gtr/processing`^{P. 138}, `/gtr/level size`^{P. 84}, `/gtr/node size from`^{P. 86}, and `/gtr/box`^{P. 98}.

```
\begin{tikzpicture}
\genealogytree[
  timeflow=left,
  processing=tcolorbox,
  level size=3.3cm,node size from=5mm to 4cm,
  box={size=small,halign=center,valign=center,fontupper=\small\sffamily},
  highlight/.style={pivot,box={colback=yellow!20,no shadow,fuzzy halo}},
]{
  parent{
    g[highlight,female]{first child}
    c[male]{second child}
    c[female]{third child}
    parent{
      c[female]{aunt}
      g[highlight,male]{father}
      c[male]{uncle}
      parent
      {
        g[male]{grandfather}
        p[male]{great-grandfather}
        p[female]{great-grandmother}
      }
    }
    parent{
      g[highlight,female]{grandmother}
      p[male]{great-grandfather 2}
      p[highlight,female]{great-grandmother 2}
      c[male]{granduncle}
    }
  }
  parent
  {
    c[male]{uncle 2}
    g[female]{mother}
    p[male]{grandfather 2}
    p[female]{grandmother 2}
  }
}
\end{tikzpicture}
```




2.2 Tutorial: Diagram Manipulation by ID values (Descendant Tree)

This tutorial shows how set up and save a descendant diagram which is going to be manipulated without changing the base data.

2.2.1 Creation of a Basic Descendant Diagram


For a *genealogy tree* displaying a descendant lineage, we take the **child** construct. As a first step, we start with a single family. As always, this root family has to have a **g**-node which serves no important role for a root family, but stands for a parent here. The resulting *genealogy tree* will contain just small nodes without names to display some interconnection. For this, a preset value from a given `/gtr/template` ^{P. 269} is used for quick setup.

```
\begin{tikzpicture}
  \genealogytree[template=formal graph]{
    child{
      g[male]{a_1}
      p[female]{a_2}
      c[female]{a_3}
      c[male]{a_4}
      c[female]{a_5}
    }
  }
\end{tikzpicture}
```



The nodes of the diagram already have some options settings. To select and manipulate some or many nodes later without editing the data, the nodes and families can be given unique `/gtr/id` ^{P. 92} values.


```
\begin{tikzpicture}
  \genealogytree[template=formal graph]{
    child[id=fam_A]{
      g[id=na1,male]{a_1}
      p[id=na2,female]{a_2}
      c[id=na3,female]{a_3}
      c[id=na4,male]{a_4}
      c[id=na5,female]{a_5}
    }
  }
\end{tikzpicture}
```



2.2.2 Growing the Tree


The nodes a_3 and a_4 shall become parent of their own families. To proceed in small steps, we make them **g**-nodes of single-member **child** families which does not change the diagram. Both new families get their own `/gtr/idP.92` values for later reference.

```
\begin{tikzpicture}
\genealogytree[template=formal graph]{
  child[id=fam_A]{
    g[id=na1,male]{a_1}
    p[id=na2,female]{a_2}
    child[id=fam_B]{
      g[id=na3,female]{a_3}
    }
    child[id=fam_C]{
      g[id=na4,male]{a_4}
    }
    c[id=na5,female]{a_5}
  }
}
\end{tikzpicture}
```



Now, the new families are populated by a second parent and children.


```
\begin{tikzpicture}
\genealogytree[template=formal graph]{
  child[id=fam_A]{
    g[id=na1,male]{a_1}
    p[id=na2,female]{a_2}
    child[id=fam_B]{
      p[id=nb1,male]{b_1}
      g[id=na3,female]{a_3}
      c[id=nb2,male]{b_2}
      c[id=nb3,female]{b_3}
    }
    child[id=fam_C]{
      g[id=na4,male]{a_4}
      p[id=nc1,female]{c_1}
      c[id=nc2,male]{c_2}
    }
    c[id=na5,female]{a_5}
  }
}
\end{tikzpicture}
```



As a specialty, a **union** construct can be used inside a **child** family. This represents a second husband or wife including children for the **g**-node of the current **child** family. A **union** does not get its own **g**-node but shares the **g**-node of the **child** family.

In our example, node a_4 gets a **union** which has to be placed inside the family with id value `fam_C`:

```
\begin{tikzpicture}
\genealogytree[template=formal graph]{
  child[id=fam_A]{
    g[id=na1,male]{a_1}
    p[id=na2,female]{a_2}
    child[id=fam_B]{
      p[id=nb1,male]{b_1}
      g[id=na3,female]{a_3}
      c[id=nb2,male]{b_2}
      c[id=nb3,female]{b_3}
    }
  }
  child[id=fam_C]{
    g[id=na4,male]{a_4}
    p[id=nc1,female]{c_1}
    c[id=nc2,male]{c_2}
    union[id=fam_D]{
      p[id=nd1,female]{d_1}
      c[id=nd2,female]{d_2}
      c[id=nd3,male]{d_3}
      c[id=nd4,male]{d_4}
    }
  }
  c[id=na5,female]{a_5}
}
\end{tikzpicture}
```



As the reader may note, for **union** constructs, the edges between the nodes are likely to overlap. Therefore, to attenuate the effect, the vertical positions of the edges for `fam_C` and `fam_D` are shifted automatically. Also, note the small visual separation at the crosspoint of both family edges. This is generated by using `/gtr/edge/foregroundP.213` and `/gtr/edge/backgroundP.214` (here, as preset values).


In some context, `fam_C` and `fam_D` will be seen as a single aggregated family and will be called *patchwork* family.

The tree is now grown further following the previous construction pattern.

```

\begin{tikzpicture}
\genealogytree[template=formal graph]{
  child[id=fam_A]{
    g[id=na1,male]{a_1}
    p[id=na2,female]{a_2}
    child[id=fam_B]{
      p[id=nb1,male]{b_1}
      g[id=na3,female]{a_3}
      c[id=nb2,male]{b_2}
      child[id=fam_E]{
        p[id=ne1,male]{e_1}
        g[id=nb3,female]{b_3}
        c[id=ne2,male]{e_2}
        c[id=ne3,female]{e_3}
      }
    }
  }
  child[id=fam_C]{
    g[id=na4,male]{a_4}
    p[id=nc1,female]{c_1}
    child[id=fam_F]{
      g[id=nc2,male]{c_2}
      p[id=nf1,female]{f_1}
      c[id=nf2,male]{f_2}
      c[id=nf3,female]{f_3}
      c[id=nf4,male]{f_4}
    }
  }
  union[id=fam_D]{
    p[id=nd1,female]{d_1}
    child[id=fam_G]{
      p[id=ng1,male]{g_1}
      g[id=nd2,female]{d_2}
      c[id=ng2,male]{g_2}
      c[id=ng3,female]{g_3}
      union[id=fam_H]{
        p[id=nh1,male]{h_1}
        c[id=nh2,male]{h_2}
      }
    }
  }
  c[id=nd3,male]{d_3}
  child[id=fam_I]{
    g[id=nd4,male]{d_4}
    p[id=ni1,female]{i_1}
    c[id=ni2,female]{i_2}
    c[id=ni3,female]{i_3}
    c[id=ni4,female]{i_4}
  }
}
c[id=na5,female]{a_5}
}
\end{tikzpicture}


```



2.2.3 Separating Diagram Data and Diagram Drawing


For the second part of this tutorial, the final diagram data is now saved into a file `example.formal.graph`, see Section 15.3 on page 361. That is everything inside `\genealogytree`^{→P.55} without the options of `\genealogytree`^{→P.55}. Using the `input` construct, graph drawing is done simply by the following:

```
\begin{tikzpicture}
  \genealogytree[template=formal graph]
    {input{example.formal.graph}}
\end{tikzpicture}
```



In our example, the given `/gtr/id`^{→P.92} values are easy to remember since we choose them nearly identical to the node content. For a not-so-formal example, this will be different. To avoid digging into the data source for finding some `/gtr/id`^{→P.92} value, the `/gtr/show id`^{→P.265} setting from the `debug` library is useful:

```
\begin{tikzpicture}
  \genealogytree[template=formal graph,show id]
    {input{example.formal.graph}}
\end{tikzpicture}
```




2.2.4 Emphasizing a Relationship Path

For the given example data, we will emphasize the relationship between node e_3 and node i_2 in our graph. The diagram above exposes the id values along the relationship path as **ne3**, **nb3**, **na3**, **na1** and **na2**, **na4**, **nd4**, **ni2**. For emphasizing, we dim the colors of all other nodes and brighten the colors for the nodes along this path.

All these manipulations are done inside the option list of `\genealogytree`^{P.55} without changing the diagram data directly.

1. `/gtr/box`^{P.98} sets options to wash out all nodes.
2. `/gtr/edges`^{P.204} sets options to wash out all edges.
3. `/gtr/options for node`^{P.95} sets box options to all nodes along the selected path to display them emphasized.
4. `/gtr/extra edges for families`^{P.227} sets extra edge options to all emphasized the connection line along the selected path.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
box={colback=white,colupper=black!50,opacityframe=0.25},
edges={foreground=black!25,background=black!5},
options for node={ne3,nb3,na3,na1,na2,na4,nd4,ni2}%
{box={colback=blue!50!red!20,colupper=black,opacityframe=1,fuzzy halo}},
extra edges for families={
x={fam_E}{nb3}{ne3},x={fam_B}{na3}{nb3},
x={fam_A}{na1,na2}{na3,na4},
x={fam_D}{na4}{nd4},x={fam_I}{nd4}{ni2}
}{foreground=blue!50!red,no background},
]
{input{example.formal.graph}}
\end{tikzpicture}
```




Also, the parameters for the auto-layout algorithm can be changed using the known id values. Our selected relationship path is emphasized further by straightening the lineages. This is done by inserting `/gtr/pivot→P.97` values through `/gtr/options for node→P.95`.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
box={colback=white,colupper=black!50,opacityframe=0.25},
edges={foreground=black!25,background=black!5},
options for node={ne3,nb3,na3,na1,na2,na4,nd4,ni2}%
{box={colback=blue!50!red!20,colupper=black,opacityframe=1,fuzzy halo}},
extra edges for families={
x={fam_E}{nb3}{ne3},x={fam_B}{na3}{nb3},
x={fam_A}{na1,na2}{na3,na4},
x={fam_D}{na4}{nd4},x={fam_I}{nd4}{ni2}
}{foreground=blue!50!red,no background},
options for node={ne3,nb3,nd4,ni2}{pivot},
options for node={na3,na4}{pivot=parent},
]
{input{example.formal.graph}}

\node[below] at (ne3.south) {Start of path};
\node[below] at (ni2.south) {End of path};
\path (na1) -- node[above=5mm]{Common ancestors} (na2);

\end{tikzpicture}
```



All given `/gtr/id→P.92` values are also TikZ nodes. Therefore, a *genealogy tree* can easily be annotated and extended by TikZ instructions.


2.2.5 Coloring Subtrees

For the given example data, the descendants of the root family should now be colored with three different colors. All in-law nodes should be visually separated from descendants of a_1 and a_2 .

As a first step, the subtree denoted by `fam_B` is colored in red by `/gtr/options for subtree→P.107`. Analogously, `fam_C` is colored in blue. Node a_5 is a leaf node without own family and, therefore, is colored using `/gtr/options for node→P.95`. Also, the preset `/gtr/male→P.101` and `/gtr/female→P.101` styles are made ineffective for this drawing.


This gives a colored *genealogy tree*, but not only the direct descendants are colored, but all members of descendant families:

```
\begin{tikzpicture}
  \genealogytree[template=formal graph,
    male/.style={},female/.style={box={circular arc}},
    options for subtree={fam_B}{box={colback=red!20!white}},
    options for subtree={fam_C,fam_D}{box={colback=blue!20!white}},
    options for node={na5}{box={colback=green!20!white}},
  ]
  {input{example.formal.graph}}
\end{tikzpicture}
```



As can be inspected using `/gtr/show type→P.267` from the `lib debug` library, the nodes to be excluded are all **p**-nodes:

```
\begin{tikzpicture}
  \genealogytree[template=formal graph,show type,
    male/.style={},female/.style={box={circular arc}},
    options for subtree={fam_B}{box={colback=red!20!white}},
    options for subtree={fam_C,fam_D}{box={colback=blue!20!white}},
    options for node={na5}{box={colback=green!20!white}},
  ]
  {input{example.formal.graph}}
\end{tikzpicture}
```




This node type is accessible by `\gtrnodetype`^{→ P. 59} or `\gtrifpnode`^{→ P. 59}. We use this to set up a `tcolorbox` style `bleach p` which wash out the in-law nodes, when `\gtrifpnode`^{→ P. 59} expands to `\true`. This style is formulated locally by `/gtr/tcbset`^{→ P. 115}:

```
%...
tcbset={bleach p/.code={%
  \gtrifpnode{\tcbset{enhanced jigsaw,opacityback=0.2}}{\}%
}},
%...
```

This gives:

```
\begin{tikzpicture}
  \genealogytree[template=formal graph,
    male/.style={},female/.style={box={circular arc}},
    tcbset={bleach p/.code={%
      \gtrifpnode{\tcbset{enhanced jigsaw,opacityback=0.2}}{\}%
    }},
    options for subtree={fam_B}{box={colback=red!20!white,bleach p}},
    options for subtree={fam_C,fam_D}{box={colback=blue!20!white,bleach p}},
    options for node={na5}{box={colback=green!20!white}},
  ]
  {input{example.formal.graph}}

  \draw[decorate,decoration={brace,amplitude=4mm,mirror,raise=2mm},
    line width=1pt,yshift=0pt] (nb2.south west|-ne3.south) -- (ne3.south east)
    node [align=center,below=9mm,midway,fill=red!20!white] {Descendants of $a_3$};
  \draw[decorate,decoration={brace,amplitude=4mm,mirror,raise=2mm},
    line width=1pt,yshift=0pt] (nf2.south west) -- (ni4.south east)
    node [align=center,below=9mm,midway,fill=blue!20!white] {Descendants of $a_4$};
\end{tikzpicture}
```



2.3 Tutorial: A Database Family Diagram (Sand Clock)

This tutorial shows the application of a database concept for representing the node content. Also, the sand clock diagram is shown which units ancestor and descendant graphs.

2.3.1 Creation of a Basic Sand Clock Diagram

The **sandclock** construct is the starting point for a sand glass type *genealogy tree*. The *proband* is the constriction for the sand glass where the ancestors and descendants of the proband meet. Therefore, a **sandclock** can and should contain **child** and **parent** constructs. There has to be exactly one **child**, because a **sandclock** has no own **g**-node but inherits it from the **child**.

For the following examples, we use `genealogypicture`^{→P.57} to create *genealogy trees*. This is a handy combination of `tikzpicture` and `\genealogytree`^{→P.55}.


```
% minimal sandclock diagram
\begin{genealogypicture}[template=formal graph]
sandclock
{
  child{
    g{\text{ proband }}
  }
}
\end{genealogypicture}
```



A single box labeled "proband" with a red border, representing the central node of a sand clock diagram.

Now, we can add **parent** and **child** constructs. Here, we use single-member families since the tree will be grown later on.

```
% basic sandclock diagram (ready to be extended)
\begin{genealogypicture}[template=formal graph]
sandclock
{
  child{
    g{\text{ proband }}
    p{a}
    child{% grows in child direction
      g{b}
    }
    child{% grows in child direction
      g{c}
    }
  }
  parent{% grows in parent direction
    g{A}
  }
  parent{% grows in parent direction
    g{B}
  }
}
\end{genealogypicture}
```



2.3.2 Node Content in Database Format

In the following, we will construct a family diagram for Carl Friedrich Gauß (1777–1855).

We step back a little bit and consider the minimal sand clock diagram as starting point. The node content, of course, may be any formatted L^AT_EX text.

```
\begin{genealogypicture}
sandclock
{
  child{
    g{Carl Friedrich \textbf{Gau\ss{}},
      born 1777, died 1855
    }
  }
}
\end{genealogypicture}
```

Carl
Friedrich
Gauß, born
1777, died
1855

In this context, the database approach means that the node content should not contain a formatted text but just the data core which is going to be formatted later. This is the same principle as for creating a bibliography with `biblatex` or `bibtex`.

So, we tell `genealogytree` that we want to use such a database concept by setting `/gtr/processing`^{→P.138} to `database`. Now, the content can be given as a key-value list. See Chapter 7 on page 161 for all feasible keys.

Further, we tell `genealogytree` how to format this given data by setting `/gtr/database format`^{→P.174} to some predefined value. Everything can be customized later.

The basic information for a person is `/gtr/database/name`^{→P.165},
`/gtr/database/male`^{→P.165} or `/gtr/database/female`^{→P.165},
`/gtr/database/birth`^{→P.169} and `/gtr/database/death`^{→P.170}.

```
\begin{genealogypicture}[
  processing=database,
  database format=medium marriage below,
]
sandclock
{
  child{
    g[id=GauxCarl1777]{
      male,
      name={Johann \pref{Carl Friedrich} \surn{Gau\ss{}},
      birth={1777-04-30}{Braunschweig (Niedersachsen)},
      death={1855-02-23}{G\''ottingen (Niedersachsen)},
      profession={Mathematiker, Astronom, Geod\''at und Physiker},
      image={Carl_Friedrich_Gauss.jpg},
    }
  }
}
\end{genealogypicture}
```

Johann Carl
Friedrich GAUSS
★ April 30, 1777
in Braunschweig
(Niedersachsen)
† February 23,
1855 in Göttingen
(Niedersachsen)
Mathematiker,
Astronom, Geodät
und Physiker.

In the example above, we also added a `/gtr/database/profession`^{→P.166} which appears in the output, and an `/gtr/database/image`^{→P.166} which is not used. Note the markup with `\pref`^{→P.184} and `\surn`^{→P.184} inside the `/gtr/database/name`^{→P.165} which marks preferred name parts and the surname. There is no name parsing as known from `bib(1a)tex`.

As `/gtr/id`^{→P.92} for Carl Friedrich Gauß, «GauxCarl1777» was chosen. Such id values could be chosen to your liking. As a common guideline, they should be human readable/understandable, because they may be needed to manipulate the graph afterwards and something like «gd0h-xhag-0ugh-opod-89sq-sdqj-8pah» may not be easily associated with

Gauß. Also, they should be automatically producible for the comfortable case, that a genealogy program exports data in this format.

In this tutorial, this common guideline is sharpened to follow these rules:

- A person id is build as `XxxxYyyyZzzz`, where `Xxxx` are four letters of the surname, `Yyyy` are four letters of the (preferred) first name, and `Zzzz` is the year of birth (maybe, estimated).
- A family id is build as `AaaaBbbbZzzz`, where `Aaaa` are four letters of the husbands surname, `Bbbb` are four letters of the wifes surname, and `Zzzz` is the year of marriage (maybe, estimated).
- Only `a, . . . , z, A, . . . , Z` letters are used. Accented letters like umlauts are replaced by letters from the masks above. If a name part is shorter than four letters, letters from the masks are used for complement.
- If two identical id values are produced for two or more persons or families following these rules, they are distinguished by adding `-⟨counter⟩`.

2.3.3 Formatting the Node Content

First, we adapt some graph geometry settings to our liking. `/gtr/node size`^{P.85}, `/gtr/level size`^{P.84}, and `/gtr/level distance`^{P.83} set size and distance values.

With `/gtr/box`^{P.98}, we set `tclobox` options for the appearance of the node box. Note that `\gtrDBsex` is set to `male` by the database values inside the node content. There are predefined `/tcb/male`^{P.101} and `/tcb/female`^{P.101} styles, but with `/gtr/tcbset`^{P.115} we change them to colorize also the interior of the box.

```
\begin{genealogypicture}[
  processing=database,
  database format=medium marriage below,
  node size=2.4cm,
  level size=3.5cm,
  level distance=6mm,
  tcbset={male/.style={colframe=blue,colback=blue!5},
    female/.style={colframe=red,colback=red!5}},
  box={fit basedim=7pt,boxsep=2pt,segmentation style=solid,
    align=left,before upper=\parskip1pt,
    \gtrDBsex,drop fuzzy shadow,
  },
]
sandclock
{
  child{
    g[id=GauxCarl1777]{
      male,
      name={Johann \pref{Carl Friedrich} \surn{Gau\ss{}}},
      birth={1777-04-30}{Braunschweig (Niedersachsen)},
      death={1855-02-23}{G\"ottingen (Niedersachsen)},
      profession={Mathematiker, Astronom, Geod\"at und Physiker},
      image={Carl_Friedrich_Gauss.jpg},
    }
  }
}
\end{genealogypicture}
```

Johann Carl
Friedrich GAUSS
★ April 30, 1777
in Braunschweig
(Niedersachsen)
† February 23,
1855 in Göttingen
(Niedersachsen)
Mathematiker,
Astronom,
Geodät und
Physiker.

As second step, we adapt the format of the given data inside the node output.

```
%...
list separators hang,
name font=\bfseries,
surn code={\textcolor{red!50!black}{#1}},
place text={\newline}{},
date format=d/mon/yyyy,
%...
```

With `/gtr/list separators hang`^{→ P. 195}, the event list is formatted with hanging indent. `/gtr/name font`^{→ P. 185} and `/gtr/surn code`^{→ P. 184} are used to format the name of the person. `/gtr/place text`^{→ P. 190} inserts a `\newline` before the place of an event is printed in our example. Finally, `/gtr/date format`^{→ P. 186} is used to change the way dates are printed.

```
\begin{genealogypicture}[
  processing=database,
  database format=medium marriage below,
  node size=2.4cm,
  level size=3.5cm,
  level distance=6mm,
  list separators hang,
  name font=\bfseries,
  surn code={\textcolor{red!50!black}{#1}},
  place text={\newline}{},
  date format=d/mon/yyyy,
  tcbset={male/.style={colframe=blue,colback=blue!5},
    female/.style={colframe=red,colback=red!5}},
  box={fit basedim=7pt,boxsep=2pt,segmentation style=solid,
    halign=left,before upper=\parskip1pt,
    \gtrDBsex,drop fuzzy shadow,
  },
]
sandclock
{
  child{
    g[id=GauxCarl1777]{
      male,
      name={Johann \pref{Carl Friedrich} \surn{Gau\ss{}}},
      birth={1777-04-30}{Braunschweig (Niedersachsen)},
      death={1855-02-23}{G\"ottingen (Niedersachsen)},
      profession={Mathematiker, Astronom, Geod\"at und Physiker},
      image={Carl_Friedrich_Gauss.jpg},
    }
  }
}
\end{genealogypicture}
```

**Johann Carl
Friedrich Gauß**
★ 30/Apr/1777
Braunschweig
(Niedersachsen)
† 23/Feb/1855
Göttingen
(Niedersachsen)
*Mathematiker,
Astronom, Geodät
und Physiker.*

2.3.4 Adding Images

The predefined `/gtr/database format`^{→ P.174} options do not consider images. But we can add image code easily to be `/gtr/box`^{→ P.98} definition which accepts `tcolorbox` settings.

`/tcb/if image defined`^{→ P.200} decides, if an image is present, and sets `tcolorbox` options accordingly. The file name of this image is `\gtrDBimage` which is set to `Carl_Friedrich_Gauss.jpg`¹ by the database values inside the node content. Here, it is accessed by `/tikz/fill overzoom DBimage`^{→ P.201}.

Options from *The tcolorbox package* [4] are used to enlarge the box width by 25mm and fill the space with this image:

```
\begin{genealogypicture}[
  processing=database,
  database format=medium marriage below,
  node size=2.4cm,
  level size=3.5cm,
  level distance=6mm,
  list separators hang,
  name font=\bfseries,
  surn code={\textcolor{red!50!black}{\#1}},
  place text={\newline}{},
  date format=d/mon/yyyy,
  tcbset={male/.style={colframe=blue,colback=blue!5},
    female/.style={colframe=red,colback=red!5}},
  box={fit basedim=7pt,boxsep=2pt,segmentation style=solid,
    halign=left,before upper=\parskip1pt,
    \gtrDBsex,drop fuzzy shadow,
    if image defined={add to width=25mm,right=25mm,
      underlay={\begin{tcbclipinterior}\path[fill overzoom DBimage]
        ([xshift=-24mm]interior.south east) rectangle (interior.north east);
      \end{tcbclipinterior}}},
    }{},
  },
]
sandclock
{
  child{
    g[id=GauxCarl1777]{
      male,
      name={Johann \pref{Carl Friedrich} \surn{Gau\ss{}}},
      birth={1777-04-30}{Braunschweig (Niedersachsen)},
      death={1855-02-23}{G\''ottingen (Niedersachsen)},
      profession={Mathematiker, Astronom, Geod\''at und Physiker},
      image={Carl_Friedrich_Gauss.jpg},
    }
  }
}
\end{genealogypicture}
```



¹http://commons.wikimedia.org/wiki/File:Carl_Friedrich_Gauss.jpg

2.3.5 Full Example with Frame

The **sandclock** example is now extended with family and ancestors and descendants of Gauß as shown at the beginning of this tutorial. The full **sandclock** example is saved as «example.gauss.graph»:

File «example.gauss.graph»

```
sandclock{
  child[id=GauaOsth1805]{
    p[id=OsthJoha1780]{
      female,
      name={\pref{Johanna} Elisabeth Rosina \surn{Osthoff}},
      birth={1780-05-08}{Braunschweig (Niedersachsen)},
      marriage={1805-10-09}{Braunschweig (Niedersachsen)},
      death={1809-10-11}{G\"ottingen (Niedersachsen)},
      comment={Wei\ss{}gerberstochter},
    }
    g[id=GauxCarl1777]{
      male,
      name={Johann \pref{Carl Friedrich} \surn{Gau\ss{}}},
      birth={1777-04-30}{Braunschweig (Niedersachsen)},
      death={1855-02-23}{G\"ottingen (Niedersachsen)},
      profession={Mathematiker, Astronom, Geod\"at und Physiker},
      image={Carl_Friedrich_Gauss.jpg},
    }
  }
  c[id=GauxCarl1806]{
    male,
    name={\pref{Carl} Joseph \surn{Gau\ss{}}},
    birth={1806-08-21}{Braunschweig (Niedersachsen)},
    death={1873-07-04}{Hannover (Niedersachsen)},
  }
  c[id=GauxWilh1808]{
    female,
    name={\pref{Wilhelmina} \surn{Gau\ss{}}},
    birth={1808-02-29}{G\"ottingen (Niedersachsen)},
    death={1840-08-12}{T\"ubingen (Baden-W\"urttemberg)},
  }
  c[id=GauxLudw1809]{
    male,
    name={\pref{Ludwig} \surn{Gau\ss{}}},
    birth={1809-09-10}{G\"ottingen (Niedersachsen)},
    death={1810-03-01}{G\"ottingen (Niedersachsen)},
  }
  union[id=GauaWald1810]{
    p[id=WaldFrie1788]{
      female,
      name={\pref{Friederica} Wilhelmine \surn{Waldeck}},
      birth={1788-04-15}{G\"ottingen (Niedersachsen)},
      marriage={1810-08-14}{G\"ottingen (Niedersachsen)},
      death={1831-09-12}{G\"ottingen (Niedersachsen)},
      comment={Rechtswissenschaftlerstochter},
    }
    c[id=GauxEuge1811]{
      male,
      name={\pref{Eugen} Peter Samuel Marius \surn{Gau\ss{}}},
      birth={1811-07-29}{G\"ottingen (Niedersachsen)},
      death={1896-07-04}{Columbia (Missouri)},
      profession={Rechtswissenschaftler, Kaufmann},
    }
  }
  c[id=GauxWilh1813]{
    male,
    name={\pref{Wilhelm} August Carl Matthias \surn{Gau\ss{}}},
    birth={1813-10-23}{G\"ottingen (Niedersachsen)},
  }
}
```

```

        death={1879-08-23}{St. Louis (Missouri)},
    }
    c[id=GauxTher1816]{
        female,
        name={Henriette Wilhelmine Karoline \pref{Therese} \surn{Gau\ss{}}},
        birth={1816-06-09}{G\ottingen (Niedersachsen)},
        death={1864-02-11}{Dresden (Sachsen)},
    }
}
}
parent[id=GoosEgge1735]{
    g[id=GauxGebh1743]{
        male,
        name={\pref{Gebhard} Dietrich \surn{Gau\ss{}}},
        birth={1743-02-13}{Braunschweig (Niedersachsen)},
        death={1808-04-14}{Braunschweig (Niedersachsen)},
        profession={G\artner, Wasserkunstmeister, Rechnungsf\uhrer},
    }
    parent[id=GoosLbtk1705]{
        g[id=GoosJyrg1715]{
            male,
            name={\pref{J\"urgen} \surn{Gooss}},
            birth={1715}{V\olkenrode (Niedersachsen)},
            death={1774-07-05}{Braunschweig (Niedersachsen)},
            profession={Lehmmaurer},
        }
        p[id=GoosHinr1655]{
            male,
            name={\pref{Hinrich} \surn{Gooss}},
            birth={ (caAD)1655}{},
            death={1726-10-25}{V\olkenrode (Niedersachsen)},
        }
        p[id=LxtkKath1674]{
            female,
            name={\pref{Katharina} \surn{L\"utken}},
            birth={1674-08-19}{V\olkenrode (Niedersachsen)},
            marriage={1705-11-24}{V\olkenrode (Niedersachsen)},
            death={1749-04-15}{V\olkenrode (Niedersachsen)},
        }
    }
}
p[id=EggeKath1710]{
    female,
    name={\pref{Katharina} Magdalena \surn{Eggenlings}},
    birth={ (caAD)1710}{Rethen},
    marriage={ (caAD)1735}{V\olkenrode (Niedersachsen)},
    death={1774-04-03}{Braunschweig (Niedersachsen)},
}
}
parent[id=BentKron1740]{
    g[id=BenzDoro1743]{
        female,
        name={\pref{Dorothea} \surn{Benze}},
        birth={1743-06-18}{Velpke (Niedersachsen)},
        marriage={1776-04-25}{Velpke (Niedersachsen)},
        death={1839-04-18}{G\ottingen (Niedersachsen)},
        comment={Steinhauerstochter},
    }
}
parent[id=BentBbbb1740]{
    g[id=BentChri1717]{
        male,
        name={\pref{Christoph} \surn{Bentze}},
        birth={1717}{Velpke (Niedersachsen)},
        death={1748-09-01}{Velpke (Niedersachsen)},
        profession={Steinhauer},
    }
}

```

```

    }
    p[id=BentAndr1687]{
      male,
      name={\pref{Andreas} \surn{Bentze}},
      birth={1687-02}{},
      death={(caAD)1750}{Velpke (Niedersachsen)},
    }
  }
  p[id=KronKath1710]{
    female,
    name={\pref{Katharina} \surn{Krone}},
    birth={(caAD)1710}{},
    death={1743/}{Velpke (Niedersachsen)},
  }
}
}

```

As final polish, `/gtr/edges`^{→ P. 204} are set to be **rounded** and the used symbols are recorded by `/gtr/symbols record reset`^{→ P. 243} and displayed by `\gtrSymbolsLegend`^{→ P. 244} inside `/gtr/after tree`^{→ P. 115}.


Finally, the whole diagram is put into a titled `tcolorbox` to exhibit the example:

```

\begin{tcolorbox}[enhanced,sharp corners,boxrule=0.6pt,left=0pt,right=0pt,
  colback=blue!50!black,interior style image=goldshade.png,
  halign=center,center title,fonttitle=\bfseries,
  title={The Family of Carl Friedrich Gau\ss{} (1777--1855)} ]
\begin{genealogypicture}[
  processing=database,
  database format=medium marriage below,
  node size=2.4cm,
  level size=3.5cm,
  level distance=6mm,
  list separators hang,
  name font=\bfseries,
  surn code={\textcolor{red!50!black}{\#1}},
  place text={\newline}{},
  date format=d/mon/yyyy,
  tcbset={male/.style={colframe=blue,colback=blue!5},
    female/.style={colframe=red,colback=red!5}},
  box={fit basedim=7pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,
    \gtrDBsex,drop fuzzy shadow,
    if image defined={add to width=25mm,right=25mm,
      underlay={\begin{tcbclipinterior}\path[fill overzoom DBimage]
        ([xshift=-24mm]interior.south east) rectangle (interior.north east);
      \end{tcbclipinterior}}},
    }{},
  },
  edges=rounded,
  symbols record reset,
  after tree={\node[font=\scriptsize\itshape,text width=1.8cm,below left,
    fill=white,fill opacity=0.4,text opacity=1]
    at (current bounding box.north east) {\gtrSymbolsLegend}};},
]
  input{example.gauss.graph}
\end{genealogypicture}
\end{tcolorbox}

```

The Family of Carl Friedrich Gauß (1777–1855)



2.4 Tutorial: Descendants of the Grandparents (Connecting Trees)


This tutorial will show how to create a «descendants of the grandparents» type of diagram. For this, two *genealogy trees* have to be connected.

2.4.1 Descendants of the Two Grandparents

Since «descendants of the grandparents» cannot be formulated by the grammar of this package, see Chapter 4 on page 63, a descendants tree for each pair of grandparents is considered.

In this example, the proband is c_4 . First, we take a look at the descendants of the father's parents a_1 and a_2 . Note that we arranged the red colored father's family at the right hand side and that the father node c_1 has a combined `/gtr/id→P.92` of $c_1@a$, because we added an `/gtr/id suffix→P.94` of $@a$ to every id value of our first tree.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,id suffix=@a,
  tcbset={male/.style={sharp corners},female/.style={circular arc}},
  edges={anchoring=center},box={colback=green!25}]
{
  child{
    g[male]{a_1} p[female]{a_2} c[female]{a_3}
    child{
      p[male]{a_4} g[female]{a_5} c[female]{a_6}
      child{
        p[male]{a_7} g[female]{a_8} c[male]{a_9}
      }
    }
  }
  child[family box={colback=red!25}]{
    g[male,id=c1]{c_1} p[female]{c_2}
    c[female]{c_3} c[female,box={fuzzy halo,colback=yellow}]{c_4} c[male]{c_5}
  }
}
\end{tikzpicture}
```



The other settings in this example are less important, but one may observe that the `/tcb/male→P.101` and `/tcb/female→P.101` styles were redefined to show not different colors but different shapes.

Secondly, we take a look at the descendants of the mother's parents b_1 and b_2 . Note that this time we arranged the red colored mother's family at the left hand side and that the father node c_1 has a different `/gtr/id→P.92` of $c_1@b$, because we added an `/gtr/id suffix→P.94` of $@b$ to every id value of our second tree.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,id suffix=@b,
tcbset={male/.style={sharp corners},female/.style={circular arc}},
edges={anchoring=center},box={colback=blue!25}]
{
  child{
    g[male]{b_1} p[female]{b_2}
    child[family box={colback=red!25}]{
      p[male,id=c1]{c_1} g[female]{c_2}
      c[female]{c_3} c[female,box={fuzzy halo,colback=yellow}]{c_4} c[male]{c_5}
    }
    child{
      p[male]{b_3} g[female]{b_4}
      c[female]{b_5} c[male]{b_6} c[male]{b_7}
      union{
        p[male]{b_8} c[female]{b_9}
      }
    }
  }
  child{
    g[male]{b_{10}} p[female]{b_{11}}
    c[female]{b_{12}} c[male]{b_{13}}
  }
}
\end{tikzpicture}
```



2.4.2 Connected Diagram

After the preparations, the `\genealogytree→P.55` diagrams can easily be put together.

Using `/gtr/set position→P.111` with value $c_1@b$ at $c_1@a$ for the second `\genealogytree→P.55` puts node c_1 from the diagram directly on node c_1 of the first `\genealogytree→P.55`. Note that in a more complicated situation more manual intervention may be necessary to avoid unwanted overlapping of other nodes.


In the first `\genealogytree→P.55`, one sees a `/gtr/phantom*→P.127` option which makes the first family c_1, \dots, c_5 invisible but still space reserving.

Using `/gtr/id suffix→P.94` or `/gtr/id prefix→P.94` allows to distinguish nodes with the same id value in different trees. Otherwise, the id values would have to be changed manually.


```

\begin{tikzpicture}
\gtrset{template=formal graph,
tcbset={male/.style={sharp corners},female/.style={circular arc}},
edges={anchoring=center},
}
\genealogytree[box={colback=green!25},id suffix=@a]
{
  child{
    g[male]{a_1} p[female]{a_2} c[female]{a_3}
    child{
      p[male]{a_4} g[female]{a_5} c[female]{a_6}
      child{
        p[male]{a_7} g[female]{a_8} c[male]{a_9}
      }
    }
  }
  child[phantom*]{
    g[male,id=c1]{c_1} p[female]{c_2}
    c[female]{c_3} c[female]{c_4} c[male]{c_5}
  }
}
\genealogytree[box={colback=blue!25}, id suffix=@b, set position=c1@b at c1@a ]
{
  child{
    g[male]{b_1} p[female]{b_2}
    child[family box={colback=red!25}]{
      p[male,id=c1]{c_1} g[female]{c_2}
      c[female]{c_3} c[female,box={fuzzy halo,colback=yellow}]{c_4} c[male]{c_5}
    }
  }
  child{
    p[male]{b_3} g[female]{b_4}
    c[female]{b_5} c[male]{b_6} c[male]{b_7}
    union{
      p[male]{b_8} c[female]{b_9}
    }
  }
  child{
    g[male]{b_{10}} p[female]{b_{11}}
    c[female]{b_{12}} c[male]{b_{13}}
  }
}
\end{tikzpicture}

```




2.5 Tutorial: Multi-Ancestors

In the following, a multi-ancestor denotes an ancestor who is connected over more than one descendency line to the proband, i.e. where descendants have children with other descendants. This situation *is not covered* by the auto-layout algorithm. Depending on the complexity, such a graph can be drawn by manipulating one or more *genealogy trees*.

2.5.1 Triple Ancestor Example

In this example, X and Y are triple ancestors of the proband Z . As first step, a **child** diagram is set up with all three descendency lines from X and Y to Z , but only the c line is drawn fully. In our example, a_5 and b_5 are parents to b_6 , also b_6 and c_5 are parents to Z (not yet displayed).

```
\begin{genealogypicture}[template=formal graph,timeflow=left,
]
child{
  g[male]{X} p[female]{Y}
  child{ g[male]{a_1}
    child{ g[female]{a_2}
      child{ g[female]{a_3}
        child{ g[male]{a_4}
          child{ g[female]{a_5}
        }
      }
    }
  }
}}}
child{ g[male]{b_1}
  child{ g[male]{b_2}
    child{ g[male]{b_3}
      child{ g[male]{b_4}
        child{ g[male]{b_5}
          child{ g[female]{b_6}
        }
      }
    }
  }
}
child{ g[male]{c_1}
  child{ g[female]{c_2}
    child{ g[male]{c_3}
      child{ g[female]{c_4}
        child{ g[male]{c_5}
          child{ g[male]{Z}
        }
      }
    }
  }
}
}}}
}}
}
\end{genealogypicture}
```




2.5.2 Adding Edges Manually

Now, we add the missing connections. For this, `/gtr/id→P.92` values are added to all involved nodes and families. Then, the connections are drawn using `/gtr/add parent→P.222` to add a_5 as additional parent for b_6 , and to add b_6 as additional parent for Z .

The diagram has all necessary edges now, but, currently, is not balanced.

```
\begin{genealogypicture}[template=formal_graph,timeflow=left,
  add parent=a5 to AB_fam,
  add parent=b6 to BC_fam,
]
child{
  g[male]{X} p[female]{Y}
  child{ g[male]{a_1}
    child{ g[female]{a_2}
      child{ g[female]{a_3}
        child{ g[male]{a_4}
          child{ g[female,id=a5]{a_5}
        }}}
  child{ g[male]{b_1}
    child{ g[male]{b_2}
      child{ g[male]{b_3}
        child{ g[male]{b_4}
          child[id=AB_fam]{ g[male]{b_5}
            child{ g[female,id=b6]{b_6}
          }}}
    child{ g[male]{c_1}
      child{ g[female]{c_2}
        child{ g[male]{c_3}
          child{ g[female]{c_4}
            child[id=BC_fam]{ g[male]{c_5}
              child{ g[male]{Z}
            }}}
          }}}
  }}}
}
\end{genealogypicture}
```




2.5.3 Manual Position Adjustments

To balance the graph, the final position of the b_6 is adjusted using the `/gtr/tikz→P.103` option with some TikZ shift operations. These final shiftings do not influence the auto-layout algorithm, but the edges move with the nodes.

Alternatively, `/gtr/distance→P.96`, `/gtr/pivot→P.97`, and `/gtr/pivot shift→P.106` can be used to influence the auto-layout algorithm. `/gtr/pivot shift→P.106` was used for the Z node to move it inside its family. But these manipulations would not move a node from its layer as was done for b_6 to display the generation skip.

```
\begin{genealogypicture}[template=formal graph,timeflow=left,
  add parent=a5 to AB_fam,
  add parent=b6 to BC_fam,
]
child{
  g[male]{X} p[female]{Y}
  child{ g[male]{a_1}
    child{ g[female]{a_2}
      child{ g[female]{a_3}
        child{ g[male]{a_4}
          child{ g[female,id=a5]{a_5}
        }}}
    child{ g[male]{b_1}
      child{ g[male]{b_2}
        child{ g[male]{b_3}
          child{ g[male]{b_4}
            child[id=AB_fam]{ g[male]{b_5}
              child{ g[female,id=b6,tikz={xshift=-6.5mm,yshift=5.5mm}]{b_6}
            }}}
        child{ g[male]{c_1}
          child{ g[female]{c_2}
            child{ g[male]{c_3}
              child{ g[female]{c_4}
                child[id=BC_fam,pivot shift=-8.25mm]{ g[male]{c_5}
                  child{ g[male]{Z}
                }}}
            }}}
        }}}
  }}}
}
\end{genealogypicture}
```



2.6 Tutorial: Externalization

Creating diagrams requires a considerable amount of compilation time. Especially, if the document contains several diagrams, it is desirable to avoid compiling already finished diagrams on every document run. One solution would be to create a document for every diagram and to include the resulting PDF to the main document. Another way is known as *externalization*.

2.6.1 Externalization Process

Externalization means that diagrams are edited inside the main document as usual, but they are automatically exported to external files, compiled if necessary, and the resulting PDF files are included to the main document as images. At least two externalization options are available:

- **TikZ** externalization: Here, the whole original document is compiled in a sophisticated way. The `external` library of **TikZ** can automatically externalize all `tikzpicture` environments, see [5].
- **tcolorbox** externalization: Here, marked code snippets are compiled in a not so sophisticated but more robust way. The `external` library of **tcolorbox** only externalizes marked and named snippets. Besides `tikzpicture` environments, `genealogypicture` environments and other constructs can be externalized. These snippets are written to external files, compiled and the resulting PDF files are included to the main document as images, see [4].

The further tutorial describes the externalization using the `external` library of **tcolorbox**. This library is already included by the **genealogytree** package.

2.6.2 Document Setup

To use the externalization, the preamble of the main document has to contain the `\tcbEXTERNALIZE` command. Without this command, no externalization operation will be executed. Typically, `\tcbEXTERNALIZE` is the *last* entry of the preamble. Everything between `\tcbEXTERNALIZE` and `\begin{document}` is thrown away in the external document.

```
\documentclass{article}
\usepackage[all]{genealogytree}

\tcbEXTERNALIZE

\begin{document}
  \section{My heading}
  % ...
  Your main document containing texts, diagrams, figures, etc.
  % ...
\end{document}
```

To use the externalization options, the compiler has to be called with the `-shell-escape` permission to authorize potentially dangerous system calls. Be warned that this is a security risk.


2.6.3 Marking Diagrams for Externalization

Before we care about externalization, we set up an example with two genealogy tree diagrams. One uses a `tikzpicture` and the other one the `genealogypicture`^{→ P.57} shortcut.


```
This is the first example:\par\smallskip
\begin{tikzpicture}
\genealogytree[template=symbol nodes]{
  child{
    gm pf cf
    child{gm pf cf cm}
    child{gm pf cm c- cm}
  }
}
\end{tikzpicture}

\bigskip Now follows the second example:\par\smallskip
\begin{genealogypicture}[template=tiny boxes]
  child{
    g-p-c-
    child{g-p-c-c-}
    child{g-p-c-c-c-}
  }
}
\end{genealogypicture}
```

This is the first example:



Now follows the second example:



To externalize the diagrams, the document has to be set up as described in the previous subsection. Further, both diagrams have to be marked for externalization:

- Replace `tikzpicture` by `extikzpicture` and add a *unique name* as additional parameter.
- Replace `genealogypicture`^{→ P.57} by `exgenealogypicture`^{→ P.57} and add a *unique name* as additional parameter.

By default, these *unique names* are the names of the external files inside an `external` sub-directory. Depending on the operation system, the sub-directory `external` may have to be generated manually.


```

This is the first externalized example:\par\smallskip
\begin{extikzpicture}{first_example}
\genealogytree[template=symbol nodes]{
  child{
    gm pf cf
    child{gm pf cf cm}
    child{gm pf cm c- cm}
  }
}
\end{extikzpicture}


\bigskip Now follows the second externalized example:\par\smallskip
\begin{exgenealogypicture}{second_example}[template=tiny boxes]
  child{
    g-p-c-
    child{g-p-c-c-}
    child{g-p-c-c-c-}
  }
}
\end{exgenealogypicture}

```

This is the first externalized example:



Now follows the second externalized example:



After the diagrams are generated, they are compiled only again, if the diagram content changes. Changes caused by global settings will not be recognized.

To force recreation, just delete the external files. Another way is to add an exclamation mark as an option.

```

% The next example is always compiled because of '!' :
\begin{exgenealogypicture}[!]{second_example}[template=tiny boxes]
  child{
    g-p-c-
    child{g-p-c-c-}
    child{g-p-c-c-c-}
  }
}
\end{exgenealogypicture}

```

More details about controlling the externalization process are found in [4].

2.7 Tutorial: Conversion to Pixel Images

This tutorial is somewhat off-topic, because it considers the conversion of vector images to pixel images and is not directly related to genealogy trees. On the other hand, the need for conversion of such diagrams arises often, e.g. for third-party photo quality printing, web content, and import to pixel-focused software.

- This tutorial only considers the conversion from PDF (vector image) to PNG (pixel image). Further conversions to e.g. JPEG can be adapted or easily done from PNG to JPEG with many available tools.
- This presentation is not exhaustive. It only gives a short glimpse of some selected options for the conversion tools.

2.7.1 Command Line Conversion with MuPDF

Here, we assume to already have a vector image file `example.pdf` which has to be converted to PNG.

First, MuPDF² has to be installed on the system, if it not already is. It provides a command line tool `mutool` for conversion which is not necessarily allocatable by the standard system path settings.

The following example conversion has to be given on a single line using a command shell (command window) or inside a script:

Command line example (a single line)

```
mutool draw -r 600 -o "example.png" "example.pdf"
```

- Replace `mutool` by an appropriate adaption (with path) for your system.
- The example input file is `"example.pdf"` and the example output file is `"example.png"`.
- Adapt `-r 600` to get larger or smaller pixel images. It defines the dots per inch resolution.

2.7.2 Command Line Conversion with Ghostscript

Here, we assume to already have a vector image file `example.pdf` which has to be converted to PNG.

First, Ghostscript³ has to be installed on the system, if it not already is. It provides a command line tool `gs` or `gswin32c` or `gswin64c` for conversion which is not necessarily allocatable by the standard system path settings.

The following example conversion has to be given on a single line using a command shell (command window) or inside a script:

Command line example (a single line)

```
gswin64c -dSAFER -dBATCH -dNOPAUSE -sDEVICE=png16m -r600 -dTextAlphaBits=4  
-dGraphicsAlphaBits=4 -sOutputFile="example.png" "example.pdf"
```

- Replace `gswin64c` by an appropriate adaption (with path) for your system.
- The example input file is `"example.pdf"` and the example output file is `"example.png"`.
- Adapt `-r600` to get larger or smaller pixel images. It defines the dots per inch resolution.

²mupdf.com

³www.ghostscript.com

2.7.3 Command Line Conversion with ImageMagick

Here, we assume to already have a vector image file `example.pdf` which has to be converted to PNG.

First, ImageMagick⁴ has to be installed on the system, if it not already is. It provides a command line tool `convert` for conversion which is typically allocatable by the standard system path settings.

The following example conversion has to be given on a single line using a command shell (command window) or inside a script:

Command line example

```
convert -density 600 -alpha Remove -quality 90 "example.pdf" "example.png"
```

- Replace `convert` by an appropriate adaption for your system, if needed. On Windows, there are other programs named `convert` which may lead to conflicts.
- The example input file is `"example.pdf"` and the example output file is `"example.png"`.
- Adapt `-density 600` to get larger or smaller pixel images. It defines the dots per inch resolution.

2.7.4 Conversion with the 'standalone' Package

Conversion to pixel images can be done using the `standalone` package. Also, this package is designed to create standalone graphics.

By default, the package uses ImageMagick for conversion in the background. See the package documentation for specific considerations for Windows.

```
\documentclass[
  border=2mm,
  convert={ density=600 -alpha Remove, outext=.png }
]{standalone}
\usepackage[all]{genealogytree}
\usepackage{lmmodern}

\begin{document}

\begin{genealogypicture}[template=symbol nodes]
  parent{
    g{male}
    insert{gtrparent4}
  }
\end{genealogypicture}

\end{document}
```

- If the document above is compiled with the `-shell-escape` permission, the compiled PDF file is converted to PNG automatically.
- Adapt `density=600` to get larger or smaller pixel images. It defines the dots per inch resolution.

⁴<http://www.imagemagick.org>

2.7.5 Conversion during Externalization

If externalization with `tcolorbox` is used, see Section 2.6 on page 49, possibly many PDF vector images are created. With the following hack, an automatic conversion with `mutool` from MuPDF is added to the external compilation.

```
\documentclass{article}
\usepackage[all]{genealogytree}
\usepackage{lmodern}

\tcbEXTERNALIZE

\makeatletter
\ExplSyntaxOn
\sys_shell_now:e { mkdir~external }
\appto\tcbexternal@corecompile
{
  \sys_shell_now:e
  {
    "mutool" ~
    draw ~
    -r~600 ~
    -o~"\tcbexternal@job@name.png" ~
    "\tcbexternal@job@name.pdf"
  }
}
\ExplSyntaxOff
\makeatother

\begin{document}

\begin{exgenealogypicture}[!]{export}[template=symbol nodes]
parent{
  g{male}
  insert{gtrparent4}
}
\end{exgenealogypicture}

\end{document}
```

- If the document above is compiled with the `--shell-escape` permission, all externalized graphics (here: one) are converted to PNG automatically.
- Replace "mutool" by an appropriate adaption (possibly with path) for your system.
- Adapt `-r 600` to get larger or smaller pixel images. It defines the dots per inch resolution.
- Note that this is a hack of internals of `tcolorbox`. This hack may become useless in the future. Especially, for a single image, the `standalone` package should be preferred.

3

Genealogy Tree Macros

3.1 Creating a Genealogy Tree


`\genealogytree[<options>]{<tree contents>}`

This is the main genealogy tree drawing macro of the package. The *<tree contents>* has to obey to the tree grammar rules documented in Chapter 4 on page 63.

The *<options>* control how the drawing is done. These *<options>* are `pgf` keys with the key tree path `/gtr/` and they are described in the following.

The actual drawing is done with help of the `TikZ` package. Therefore, every `\genealogytree` has to be placed into a `tikzpicture` environment. It is possible to put several `\genealogytree` macros into the same `tikzpicture` and interconnect them.

```
\begin{tikzpicture}
\genealogytree[template=signpost]
{
  parent{
    g[male]{proband}
    c[female]{sister}
    c[male]{brother}
    p[male]{father}
    p[female]{mother}
  }
}
\end{tikzpicture}
```



Detailed information about the genealogy tree grammar is found in Chapter 4 on page 63. The short version is that a genealogy tree can have three types of nodes:

- **c** nodes are *child* nodes to a family,
- **p** nodes are *parent* nodes to a family,
- **g** nodes are usually *child* nodes to one family and *parent* nodes another family or even several families. Here, **g** can be memorized as *genealogy* node.

A *family* is a set of *parent* and *child* nodes which has to contain exactly one *genealogy* node (**g** node). All nodes of a family are interconnected with an edge set. In contrast to ordinary tree structures where an edge connects one node to another node, here, an edge connects a node to a family.


A genealogy tree can have following types of families:

- **parent**: A *parent* family may contain other **parent** families. Trees with this construction grow into *ancestor direction*.
- **child**: A *child* family may contain other **child** families or **union** families. Trees with this construction grow into *descendant direction*.
- **union**: A *union* ties a second child-type family to a **g** node as parent of this family.
- **sandclock**: A *sandclock* connects ancestors and descendants starting from a single proband.

```

\begin{tikzpicture}
\genealogytree[template=signpost]
{
  parent{
    g[male]{proband}
    c[female]{sister}
    c[male]{brother}
    parent{
      g[male]{father}
      p[male]{grandfather}
      p[female]{grandmother}
    }
    p[female]{mother}
  }
}
\end{tikzpicture}

```




`\genealogytreeinput` [*options*] {*file name*}

Uses the content of the file denoted by *file name* to create a `\genealogytree`^{→ P. 55} with the given *options*. See Section 15.1 on page 359 for the file of the following example.

```

\begin{tikzpicture}
\genealogytreeinput[template=signpost]{example.option.graph}
\end{tikzpicture}


```



```
\begin{genealogypicture}[\langle options \rangle]
  \langle tree content \rangle
\end{genealogypicture}
```

This is a shortcut combination of one `\genealogytree`^{→ P. 55} inside a `tikzpicture`. For `\langle options \rangle` and `\langle tree contents \rangle` see `\genealogytree`^{→ P. 55}. This environment allows more compact source code, but one cannot combine several trees and adding additional TikZ commands has to be done by `/gtr/tikzpicture`^{→ P. 114} or `/gtr/after tree`^{→ P. 115}.

```
\begin{genealogypicture}
[template=signpost]
parent{
  g[male]{proband}
  c[female]{sister}
  c[male]{brother}
  p[male]{father}
  p[female]{mother}
}
\end{genealogypicture}
```



```
\begin{exgenealogypicture}[\langle externalization options \rangle]{\langle name \rangle}[\langle options \rangle]
  \langle tree content \rangle
\end{exgenealogypicture}
```

This is an externalized version of `genealogypicture` using the `external` library of the package `tcolorbox` [4]. The picture is drawn by automatic compilation of an external file denoted by `\langle name \rangle` (usually prefixed by a directory or string). Afterwards, the created pdf image is included into the main document. As long as the `\langle tree contents \rangle` and the `\langle options \rangle` are not changed, the external file is not compiled again which saves overall compilation time. The process can be controlled by `\langle externalization options \rangle`, see [4].

For a detailed application example, see Section 2.6 on page 49.


3.2 Using Tree Options

`\gtrset{⟨options⟩}`

Sets $\langle options \rangle$ for every following `\genealogytree`^{P.55} inside the current T_EX group. These $\langle options \rangle$ are pgf keys with the key tree path `/gtr/` and they are described in the following.

```
% Setting options for the following
\gtrset{template=signpost}


\begin{tikzpicture}
\genealogytree
{
  parent{
    g[male]{proband}
    c[female]{sister}
    c[male]{brother}
    p[male]{father}
    p[female]{mother}
  }
}
\end{tikzpicture}
```



Another important field of application for `\gtrset` is to create own styles for later usage.

```
% Setting options for the following
\gtrset{mytree/.style={
  template=signpost,
  box={colback=yellow!20},
  edges={swing,no background,
    foreground=yellow!50!black},
}}

\begin{tikzpicture}
\genealogytree[mytree]% own style
{
  parent{
    g[male]{proband}
    c[female]{sister}
    c[male]{brother}
    p[male]{father}
    p[female]{mother}
  }
}
\end{tikzpicture}
```



`\gtrkeysappto{⟨hook⟩}{⟨key list⟩}`

Auxiliary macro which appends a $\langle key list \rangle$ (options) to a $\langle hook \rangle$ macro which may already contain a key list.

`\gtrkeysgappto{⟨hook⟩}{⟨key list⟩}`

Auxiliary macro which globally appends a $\langle key list \rangle$ (options) to a $\langle hook \rangle$ macro which may already contain a key list.

3.3 Accessing Information inside Nodes

Inside the node content, there are several processing informations available which can be used for debugging or steering the output. Also see Section 11.4 on page 265 for displaying these values.

`\gtrnodetype`

Holds the node type `g`, `p`, or `c`.

`\gtrnodeid`

Holds the `/gtr/idP.92` value of the node.

`\gtrnodenumber`

Holds the internal node number.


`\gtrnodefamily`

Holds the internal family number this node belongs to.

`\gtrnodelevel`

Holds the tree level number this node belongs to.

```
\begin{tikzpicture}
\genealogytree[
  template=signpost,
  level size=2cm,
  content interpreter content={
    \begin{tabular}{@{}r@{: }l@{}}
      type & \gtrnodetype\\
      id & \gtrnodeid\\
      number & \gtrnodenumber\\
      family & \gtrnodefamily\\
      level & \gtrnodelevel\\
    \end{tabular}}
]{
  parent{
    g[male,id=Abc]{}
    c[female]{}
    c[male]{}
    parent{
      g[male,id=Bob]{}
      p[male,id=Jim]{}
      p[female]{}
    }
    p[female]{}
  }
}
\end{tikzpicture}
```



`\gtrifnodeid{<true>}{<false>}`

Expands to `<true>`, if `/gtr/idP.92` was set, and to `<false>` otherwise.

`\gtrifgnode{<true>}{<false>}`

Expands to `<true>`, if the node type is `g`, and to `<false>` otherwise.

`\gtrifcnode{<true>}{<false>}`

Expands to `<true>`, if the node type is `c`, and to `<false>` otherwise.

`\gtrifpnode{<true>}{<false>}`

Expands to `<true>`, if the node type is `p`, and to `<false>` otherwise.

3.4 Auxiliary Tools

N 2020-06-08
N 2020-06-08

```
\gtrautosizebox{<width>}{<height>}{<contents>}
\gtrautosizebox*{<width>}{<height>}{<contents>}
```

Puts the $\langle contents \rangle$ into a horizontal box and resizes this box to fit into a rectangular frame of given $\langle width \rangle$ and $\langle height \rangle$. The resizing keeps the aspect ratio intact. The star (*) variant does shrinking only and keeps small boxes unchanged.

If $\langle width \rangle$ is missing or is not greater than 0pt, then only the $\langle height \rangle$ is considered for scaling.

If $\langle height \rangle$ is missing or is not greater than 0pt, then only the $\langle width \rangle$ is considered for scaling.

If $\langle width \rangle$ and $\langle height \rangle$ are both missing or both are not greater than 0pt, the box is kept unscaled.

```
\gtrautosizebox{10mm}{10mm}{AA}
\gtrautosizebox{5mm}{10mm}{BB}
\gtrautosizebox{10mm}{5mm}{CC}
\gtrautosizebox{}{10mm}{DD}
\gtrautosizebox{10mm}{}{EE}
\gtrautosizebox{}{}{FF}
\gtrautosizebox*{10mm}{10mm}{GG}
\gtrautosizebox*{3mm}{3mm}{HH}
```

AA BB CC DD EE FF GG Š

N 2020-06-08

```
\begin{autosizetikzpicture}[<options>]{<width>}{<height>}
  <environment content>
\end{autosizetikzpicture}
```

N 2020-06-08

```
\begin{autosizetikzpicture*}[<options>]{<width>}{<height>}
  <environment content>
\end{autosizetikzpicture*}
```

A tikzpicture environment with given TikZ $\langle options \rangle$ is put into $\backslash\text{gtrautosizebox}$ or $\backslash\text{gtrautosizebox*}$ with given $\langle width \rangle$ and $\langle height \rangle$.

```
\begin{autosizetikzpicture}{1cm}{1cm}
  \filldraw[red] (0,0) circle (5cm);
\end{autosizetikzpicture}

\begin{autosizetikzpicture}{1cm}{1cm}
  \filldraw[blue] (0,0) circle (1mm);
\end{autosizetikzpicture}

\begin{autosizetikzpicture*}{1cm}{1cm}
  \filldraw[cyan] (0,0) circle (5cm);
\end{autosizetikzpicture*}

\begin{autosizetikzpicture*}{1cm}{1cm}
  \filldraw[green] (0,0) circle (1mm);
\end{autosizetikzpicture*}
```



4

Graph Grammar




4.1 Graph Structure

In graph theory, a *graph* is defined by a set of vertices (or nodes) and a set of edges connecting these vertices. A general graph structure would certainly allow to depict genealogy data, but building and displaying such a general graph is not supported by this L^AT_EX package.

An ordinary *tree* structure is a specialized (directed) graph which has a *root* node as starting point. Every node may have one or more descendant nodes. In this relationship, the first node is called *parent* and the second is called *child*. Such tree structures are heavily used for many applications. Also, there exist excellent L^AT_EX packages to display such structures. Such *tree* structures can also be used for several kinds of genealogy type diagrams, but, by definition, they miss the core element of genealogy: the *family* consisting of two parents and several childs.

The graph structure used by the **genealogytree** package is intended to put the *family* as a set of *parent* and *child* nodes in the foreground. Every *family* is allowed to have more than one *parent* and more than one *child*. The interconnection between the *parent* and *child* nodes of a family is not considered to be bilateral between pairs of nodes, but to be multilateral between all nodes of the family. From the idea, a node is connected not to another node, but to one or more families. Still, there apply strong restrictions on the set of possible graphs, because graphs have to be reasonable processable and presentable. The restrictions are realized by the following graph grammar. In the following, the resulting graphs are called *genealogy trees*.

A *family* is a set of *parent* and *child* nodes which has to contain exactly one *genealogy* node



(**g** node). Therefore, a family can have three types of nodes:

- **c** nodes are *child* nodes to a family, see Section 4.6 on page 73,
- **p** nodes are *parent* nodes to a family, see Section 4.7 on page 73,
- **g** nodes are usually *child* nodes to one family and *parent* nodes another family or even several families, see Section 4.8 on page 73.

A genealogy tree can have following types of families:

- **parent**: A *parent* family may contain other **parent** families. Trees with this construction grow into *ancestor direction*, see Section 4.2 on page 65,
- **child**: A *child* family may contain other **child** families or **union** families. Trees with this construction grow into *descendant direction*, see Section 4.3 on page 67,
- **union**: A *union* ties a second child-type family to a **g** node as parent of this family, see Section 4.4 on page 69,
- **sandclock**: A *sandclock* connects ancestors and descendants starting from a single proband, see Section 4.5 on page 71.

As will be documented on the following pages, the graph input data is strongly hierarchically organized. Each element is allowed to have specific sub-elements. The starting point is the *root* element which is the top element inside `\genealogytree`^{→P.55}. The *root* of a parsable graph is one of the following:

- a **parent** (for ancestor graphs), see Section 4.2 on the facing page,
- a **child** (for descendant graphs), see Section 4.3 on page 67,
- a **sandclock** (for mixed ancestor/descendant graphs), see Section 4.5 on page 71.

4.2 Subgraph 'parent'

A **parent** subgraph is a family where the **g** node acts as a child. This family may have arbitrary child and parent leaves. Also, this family may have arbitrary **parent** subgraphs.


Syntax for a 'parent' subgraph

```
parent[⟨parent options⟩]{
  g[⟨node options⟩]{⟨node content⟩}      mandatory; exactly once
  c[⟨node options⟩]{⟨node content⟩}      optional; zero or many times
  p[⟨node options⟩]{⟨node content⟩}      optional; zero or many times
  parent[⟨parent options⟩]{⟨subtree content⟩} optional; zero or many times
  input{⟨file name⟩}                    optional; zero or many times
  insert{⟨cname⟩}                      optional; zero or many times
}
```

'g', 'c', 'p', 'parent', 'input' may appear in arbitrary order.


The optional *⟨parent options⟩* can be settings for the current family or the whole subgraph. See Chapter 5 on page 77 and especially Section 5.6 on page 104 and Section 5.7 on page 107 for feasible options.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={pA}{box={colback=red!20!white}}]
{
  parent{
    c[id=pB]{B\\(child)}
    g[id=pA]{A\\(proband)}
    c[id=pC]{C\\(child)}
    c[id=pD]{D\\(child)}
    p[id=pE]{E\\(parent)}
    p[id=pF]{F\\(parent)}
  }
}
\end{tikzpicture}
```



`\gtrparserdebug`^{→ P. 250} can help to detect structural errors. Here, we get:

```
\gtrparserdebug{
  parent{
    c[id=pB]{B\\(child)}
    g[id=pA]{A\\(proband)}
    c[id=pC]{C\\(child)}
    c[id=pD]{D\\(child)}
    p[id=pE]{E\\(parent)}
    p[id=pF]{F\\(parent)}
  }
}
```



Genealogytree Parser Debugger	
	Start: Parent Family 1, Level 1
c	Child: Individual 1, Family 1, Level 0 Options: id=pB Content: B\\(child)
g	Child: Individual 2, Family 1, Level 0 Options: id=pA Content: A\\(proband)
c	Child: Individual 3, Family 1, Level 0 Options: id=pC Content: C\\(child)
c	Child: Individual 4, Family 1, Level 0 Options: id=pD Content: D\\(child)
p	Parent: Individual 5, Family 1, Level 1 Options: id=pE Content: E\\(parent)
p	Parent: Individual 6, Family 1, Level 1 Options: id=pF Content: F\\(parent)
	End: Parent Family 1, Level 1
End of Genealogytree Parser Debugger	

4.3 Subgraph 'child'

A **child** subgraph is a family where the **g** node acts as a parent. This family may have arbitrary child and parent leaves. Also, this family may have arbitrary **child** and **union** subgraphs.


Syntax for a 'child' subgraph

```
child[⟨child options⟩]{
  g[⟨node options⟩]{⟨node content⟩}      mandatory; exactly once
  c[⟨node options⟩]{⟨node content⟩}      optional; zero or many times
  p[⟨node options⟩]{⟨node content⟩}      optional; zero or many times
  child[⟨child options⟩]{⟨subtree content⟩} optional; zero or many times
  union[⟨union options⟩]{⟨subtree content⟩} optional; zero or many times
  input{⟨file name⟩}                    optional; zero or many times
  insert{⟨cname⟩}                      optional; zero or many times
}
```

'g', 'c', 'p', 'child', 'union', 'input' may appear in arbitrary order.


The optional *⟨child options⟩* can be settings for the current family or the whole subgraph. See Chapter 5 on page 77 and especially Section 5.6 on page 104 and Section 5.7 on page 107 for feasible options.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={pA}{box={colback=red!20!white}}]
{
  child{
    g[id=pA]{A\\(proband)}
    p[id=pB]{B\\(parent)}
    c[id=pC]{C\\(child)}
    c[id=pD]{D\\(child)}
    c[id=pE]{E\\(child)}
  }
}
\end{tikzpicture}
```



`\gtrparserdebug`^{→ P. 250} can help to detect structural errors. Here, we get:

```
\gtrparserdebug{
  child{
    g[id=pA]{A\\(proband)}
    p[id=pB]{B\\(parent)}
    c[id=pC]{C\\(child)}
    c[id=pD]{D\\(child)}
    c[id=pE]{E\\(child)}
  }
}
```



Genealogytree Parser Debugger	
	Start: Child Family 1, Level 0
	Parent: Individual 1, Family 1, Level 0
g	Options: id=pA Content: A\\(proband)
	Parent: Individual 2, Family 1, Level 0
p	Options: id=pB Content: B\\(parent)
c	Child: Individual 3, Family 1, Level -1 Options: id=pC Content: C\\(child)
c	Child: Individual 4, Family 1, Level -1 Options: id=pD Content: D\\(child)
c	Child: Individual 5, Family 1, Level -1 Options: id=pE Content: E\\(child)
	End: Child Family 1, Level 0
End of Genealogytree Parser Debugger	

4.4 Subgraph 'union'

A **union** subgraph is a family without a **g** node. The **g** node (parent) is inherited from an embedding **child** family. A **union** family may have arbitrary child and parent leaves. Also, this family may have arbitrary **child** subgraphs.


Syntax for a 'union' subgraph

```
union[⟨union options⟩]{
  c[⟨node options⟩]{⟨node content⟩}           optional; zero or many times
  p[⟨node options⟩]{⟨node content⟩}           optional; zero or many times
  child[⟨child options⟩]{⟨subtree content⟩}    optional; zero or many times
  input{⟨file name⟩}                          optional; zero or many times
  insert{⟨cname⟩}                             optional; zero or many times
}
```

'c', 'p', 'child', 'input' may appear in arbitrary order.


The optional *⟨child options⟩* can be settings for the current family or the whole subgraph. See Chapter 5 on page 77 and especially Section 5.6 on page 104 and Section 5.7 on page 107 for feasible options. As a special case for unions, note that the **g** node of the embedding **child** family will not be affected by these options.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={pA}{box={colback=red!20!white}}]
{
  child{
    p[id=pB]{B\\(parent)}
    g[id=pA]{A\\(proband)}
    c[id=pC]{C\\(child)}
    union{
      p[id=pD]{D\\(parent)}
      c[id=pE]{E\\(child)}
    }
  }
}
\end{tikzpicture}
```



`\gtrparserdebug`^{→ P. 250} can help to detect structural errors. Here, we get:

```
\gtrparserdebug{
  child{
    p[id=pB]{B\\(parent)}
    g[id=pA]{A\\(proband)}
    c[id=pC]{C\\(child)}
    union{
      p[id=pD]{D\\(parent)}
      c[id=pE]{E\\(child)}
    }
  }
}
```



4.5 Subgraph 'sandclock'


A **sandclock** subgraph is a family without a **g** node. The **g** node (child) is inherited from an embedded **child** family. A **sandclock** family may have arbitrary child and parent leaves. Also, this family must have at least one **child** subgraph and may have arbitrary **parent** subgraphs.

Syntax for a 'sandclock' subgraph

```
sandclock[⟨sandclock options⟩]{
  c[⟨node options⟩]{⟨node content⟩}           optional; zero or many times
  p[⟨node options⟩]{⟨node content⟩}           optional; zero or many times
  child[⟨child options⟩]{⟨subtree content⟩}    mandatory; one or many times
  parent[⟨parent options⟩]{⟨subtree content⟩}  optional; zero or many times
  input{⟨file name⟩}                          optional; zero or many times
  insert{⟨cname⟩}                             optional; zero or many times
}
```

'c', 'p', 'child', 'parent', 'input' may appear in arbitrary order.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={pA}{box={colback=red!20!white}}]
{
  sandclock{
    c[id=pB]{B\\(child)}
    child
    {
      g[id=pA]{A\\(proband)}      c[id=pa]{a\\(child)}
      c[id=pb]{b\\(child)}      p[id=pX]{X\\(partner)}
    }
    p[id=pC]{C\\(parent)}
    parent{
      g[id=pD]{D\\(parent)}      c[id=pE]{E\\(child)}      p[id=pF]{F\\(parent)}
    }
  }
}
\end{tikzpicture}
```



```

\gtrparserdebug{
  sandclock{
    c[id=pB]{B\\(child)}
    child
    {
      g[id=pA]{A\\(proband)}      c[id=pa]{a\\(child)}
      c[id=pb]{b\\(child)}      p[id=pX]{X\\(partner)}
    }
    p[id=pC]{C\\(parent)}
    parent{
      g[id=pD]{D\\(parent)}      c[id=pE]{E\\(child)}      p[id=pF]{F\\(parent)}
    }
  }
}

```



4.6 Node 'c'

The **c** (child) node is a leaf node which is child to a family.


Syntax for a 'c' node

```
c[⟨node options⟩]{⟨node content⟩}
```

For the optional *⟨node options⟩*, see Chapter 5 on page 77 and especially Section 5.5 on page 95.

The *⟨node content⟩* can be any text to be displayed inside the node. This *⟨node content⟩* can also be processed before displaying, see Chapter 6 on page 137 and especially Chapter 7 on page 161 for database processing. Also, the *⟨node content⟩* can be completely ignored for processing. In this case, one can use `c{}` or even shorter `c⟨token⟩` for the node.

```
\begin{genealogypicture}[
  template=formal graph,
  content interpreter content=
    {n_{\gtrnode number}},
]
  child{ g-p-c-c-
    child{ p-g-
      child{ p-g-c-c-c- }
      c-c-
    }
    c-c-
  }
\end{genealogypicture}
```



4.7 Node 'p'

The **p** (parent) node is a leaf node which is parent to a family.

Syntax for a 'p' node

```
p[⟨node options⟩]{⟨node content⟩}
```

For the optional *⟨node options⟩*, see Chapter 5 on page 77 and especially Section 5.5 on page 95. For *⟨node content⟩*, see Section 4.6 on page 73.

4.8 Node 'g'

The **g** (genealogy) node is an interconnecting individual which is member of at least two families. For one family it is a child, for another one it is a parent.

Syntax for a 'g' node

```
g[⟨node options⟩]{⟨node content⟩}
```

For the optional *⟨node options⟩*, see Chapter 5 on page 77 and especially Section 5.5 on page 95. For *⟨node content⟩*, see Section 4.6 on page 73.

4.9 Data 'input'


Feasible subgraphs may be read from external files using the **input** command at places where such subgraphs are expected.

Syntax for data 'input'

```
input{⟨file name⟩}
```

The following example reads a **parent** subgraph from a file. See Section 15.1 on page 359 for the file contents.

```
\begin{tikzpicture}
\genealogytree[template=signpost]
{
  parent{
    g{Puppy}
    input{example.option.graph}
    parent
    {
      g[female]{Nanny}
      p[male]{Pa}
      p[female]{Ma}
    }
  }
}
\end{tikzpicture}
```



4.10 Control Sequence 'insert'

Feasible subgraphs may be inserted from control sequences using the **insert** command at places where such subgraphs are expected.


Syntax for data 'insert'

```
insert{<cname>}
```

<cname> is the name of a control sequence without the leading backslash '\'. This control sequence has to be a parameterless macro whose replacement text is a feasible subgraph.

The following example creates such a macro \mytest:

```
\newcommand{\mytest}{  
  parent{ g{x_1}  
    parent{ g{x_2} p{x_3} p{x_4} }  
    parent{ g{x_5} p{x_6} p{x_7} }  
  }  
  
  \begin{tikzpicture}  
  \genealogytree[template=formal graph]  
  {  
    parent{  
      g{a_1}  
      parent{  
        g{a_3}  
        insert{mytest}  
        insert{mytest}  
      }  
      insert{mytest}  
    }  
  }  
  \end{tikzpicture}
```



5

Option Setting

For the $\langle options \rangle$ in $\backslash genealogytree^{\rightarrow P.55}$, $genealogypicture^{\rightarrow P.57}$, and $\backslash gtrset^{\rightarrow P.58}$, keys with **pgf** syntax can be applied as documented in the following. The key tree path `/gtr/` is not to be used inside these macros. It is easy to add your own style keys using the syntax for **pgf** keys, see [5].

Some of the following examples use a standard graph file which is documented in Section 15.1 on page 359.

5.1 Option Priorities

This section can be skipped on first reading. Option priorities are more or less natural. This section can be consulted later in case of doubt.

Options for the graph drawing can be set at several spots inside the code using the **pgf** key-value syntax:

- as parameter of $\backslash gtrset^{\rightarrow P.58}$ for setting (global) options,
- as optional parameter of $\backslash genealogytree^{\rightarrow P.55}$ or $genealogypicture^{\rightarrow P.57}$,
- as optional parameter of a family identifier like **parent** or **child**,
- as optional parameter of a node identifier like **g**, **p**, or **c**.

Depending on where the options are given, they are treated with different priority. If an option is given several times with the same priority, the last one wins.

- For options like $/gtr/pivot^{\rightarrow P.97}$, an option setting with higher priority overwrites an option setting with lower priority.
- For options like $/gtr/box^{\rightarrow P.98}$, an option setting with higher priority appends to an option setting with lower priority. Thus, $/gtr/box^{\rightarrow P.98}$ options which are not overwritten, stay active.

5.1.1 Option Priorities for Nodes

Example: Priorities for setting box options to a node with id=A

```
\gtrset{
... % priorities identical to options for \genealogytree
}
\genealogytree[
options for node={A}{box={...}},           % priority (1) highest
options for family={fam_a}{box={...}},      % priority (5)
options for subtree={fam_a}{box={...}},     % priority (9)
level 2/.style={
  node={box={...}},                         % priority (3)
  family={box={...}},                       % priority (7)
  subtree={box={...}},                      % priority (11)
level/.code={\ifnum#1=2\relax\gtrset{
  node={box={...}},                         % priority (4)
  family={box={...}},                       % priority (8)
  subtree={box={...}}\fi},                 % priority (12)
box={...},                                 % priority (13) lowest
...
]}%
{
...
parent[ id=fam_a,      % family with id 'fam_a'
        family={box={...}}, % priority (6)
        subtree={box={...}}, % priority (10)
      ]
  {
    ...
    p[id=A,           % node with id 'A'
      box={...}]{A} % priority (2)
    ...
  }
  ...
}
```

The priorities for options regarding nodes

1. `/gtr/options for node`^{→P.95} has the highest priority. The node has to be identified by a given `/gtr/id`^{→P.92}. `/gtr/options for node`^{→P.95} should be given using `\gtrset`^{→P.58} or as option of `\genealogytree`^{→P.55}.
2. Optional parameter of a node identifier like **g**, **p**, or **c**.
3. Option `/gtr/node`^{→P.96} inside `/gtr/level n`^{→P.110}.
4. Option `/gtr/node`^{→P.96} inside `/gtr/level`^{→P.109}.
5. `/gtr/options for family`^{→P.104}; the family has to be identified by a given `/gtr/id`^{→P.92}.
6. `/gtr/family`^{→P.105} as optional parameter of a family identifier like **parent** or **child**.
7. Option `/gtr/family`^{→P.105} inside `/gtr/level n`^{→P.110}.
8. Option `/gtr/family`^{→P.105} inside `/gtr/level`^{→P.109}.
9. `/gtr/options for subtree`^{→P.107}; the subtree has to be identified by a given `/gtr/id`^{→P.92}.
10. `/gtr/subtree`^{→P.108} as optional parameter of a family identifier like **parent** or **child**.
11. Option `/gtr/subtree`^{→P.108} inside `/gtr/level n`^{→P.110}.
12. Option `/gtr/subtree`^{→P.108} inside `/gtr/level`^{→P.109}.
13. Setting as parameter of `\genealogytree`^{→P.55} or `\gtrset`^{→P.58} has the lowest priority.

5.1.2 Option Priorities for Families

Example: Priorities for setting edges options to a family with id=fam_a

```

\gtrset{
  ... % priorities identical to options for \genealogytree
}
\genealogytree[
  options for family={fam_a}{edges={...}},           % priority (1) highest
  options for subtree={fam_a}{edges={...}},           % priority (5)
  level 2/.style={family={edges={...}}               % priority (3)
                  subtree={edges={...}}},             % priority (7)
  level/.code={\ifnum#1=2\relax%
    \gtrset{family={edges={...}},                     % priority (4)
             subtree={edges={...}}}                   % priority (8)
    \fi},
  edges={...},                                         % priority (9) lowest
  ...
] %
{
  ...
  parent[ id=fam_a, % family with id 'fam_a'
          family={edges={...}},                       % priority (2)
          subtree={edges={...}},                       % priority (6)
        ]
  {
    ...
  }
  ...
}

```

The priorities for options regarding families

1. `/gtr/options for family`^{→P.104} has the highest priority. The family has to be identified by a given `/gtr/id`^{→P.92}. `/gtr/options for family`^{→P.104} should be given using `\gtrset`^{→P.58} or as option of `\genealogytree`^{→P.55}.
2. Optional `/gtr/family`^{→P.105} parameter of a family identifier like **parent** or **child**.
3. Option `/gtr/family`^{→P.105} inside `/gtr/level n`^{→P.110}.
4. Option `/gtr/family`^{→P.105} inside `/gtr/level`^{→P.109}.
5. `/gtr/options for subtree`^{→P.107}; the subtree has to be identified by a given `/gtr/id`^{→P.92}.
6. Optional `/gtr/subtree`^{→P.108} parameter of a family identifier like **parent** or **child**.
7. Option `/gtr/subtree`^{→P.108} inside `/gtr/level n`^{→P.110}.
8. Option `/gtr/subtree`^{→P.108} inside `/gtr/level`^{→P.109}.
9. Setting as parameter of `\genealogytree`^{→P.55} or `\gtrset`^{→P.58} has the lowest priority.


5.2 Graph Growth Setting (Time Flow)

A genealogy tree may grow in one of four directions. This `/gtr/timeflow` setting is valid for the whole graph, but two graphs with different growth setting may be joined together.

`/gtr/timeflow=<direction>` (no default, initially **down**)

The `/gtr/timeflow` key controls the growing direction of a given graph. It is always used to place the generations according to this value. If the `<direction>` is set to **down**, a **child** graph will grow down, but a **parent** graph will grow up. Feasible values are:


- **down**
- **up**
- **left**
- **right**



See Section 15.1 on page 359 for the included example graph file.


timeflow=up

```
\begin{tikzpicture}
\genealogytree[template=signpost,timeflow=up]
{input{example.option.graph}}
\node at ([xshift=4cm]GmDo1956) (past) {Past};
\draw[very thick,->] (past) -- +(0,2) node[above] {Future};
\end{tikzpicture}
```




timeflow=left

```
\begin{tikzpicture}
\genealogytree[template=signpost,timeflow=left,node size=1.2cm,level size=3cm]
{input{example.option.graph}}
\node at ([yshift=-1.5cm]GmDo1956) (past) {Past};
\draw[very thick,->] (past) -- +(-2,0) node[left] {Future};
\end{tikzpicture}
```



timeflow=right

```
\begin{tikzpicture}
\genealogytree[template=signpost,timeflow=right,node size=1.2cm,level size=3cm]
{input{example.option.graph}}
\node at ([yshift=-1.5cm]GmDo1956) (past) {Past};
\draw[very thick,->] (past) -- +(2,0) node[right] {Future};
\end{tikzpicture}
```



Past → Future

5.3 Graph Geometry

The following geometry settings are usually set for the whole graph, but they can be set for every `/gtr/level→P.109` separately. Inside a level, they are fixed.

`/gtr/level distance=<length>` (no default, initially 5mm)

The given `<length>` defines the distance between two following generations. This distance can be set in dependency of the `/gtr/level→P.109`.




The `/gtr/level distance` can be specified for individual level numbers, e.g.

```

\gtrset{
  level 0/.style={level distance=5mm},
  level -1/.style={level distance=10mm}
}
...

```




`/gtr/level size=<length>` (no default, initially 3.5cm)


The given $\langle length \rangle$ defines one dimension of a node.

- If `/gtr/timeflowP.80` is up or down, then `/gtr/level size` sets the height of a node.
- If `/gtr/timeflowP.80` is left or right, then `/gtr/level size` sets the width of a node.

The `/gtr/level size` be set in dependency of the `/gtr/levelP.109`.



```
\gtrset{
  level 0/.style={level size=15mm},
}
...
```




Some actual node implementations may not respect the given `/gtr/level size`. Note that the placement algorithm ignores deviations and assumes that the restrictions hold.

`/gtr/node size=<length>` (no default, initially 2.5cm)


The given $\langle length \rangle$ defines one dimension of a node.

- If `/gtr/timeflow`^{P.80} is up or down, then `/gtr/level size`^{P.84} sets the width of a node.
- If `/gtr/timeflow`^{P.80} is left or right, then `/gtr/level size`^{P.84} sets the height of a node.

The `/gtr/node size` can be set in dependency of the `/gtr/level`^{P.109}. Note that the `/gtr/node size` may be ignored by nodes boxes which set the width individually or depending from the content width.




```
\gtrset{
  level 0/.style={level size=15mm},
}
...
```



If the size should be changed for an individual node, use `/gtr/box`^{P.98} instead of `/gtr/node size`:

```
...
c[id=A,box={width=15mm}]{C_3}
...
```



Some actual node implementations may not respect the given `/gtr/node size`. The placement algorithm accepts deviations and calculates positions accordingly.


/gtr/node size from= $\langle minlength \rangle$ to $\langle maxlenlength \rangle$ (no default, initially 2.5cm to 2.5cm)

Sets the **/gtr/node size**^{→P.85} in a flexible way ranging from $\langle minlength \rangle$ to $\langle maxlenlength \rangle$. The actual size of a node is determined by the node content. A node will be enlarged up to $\langle maxlenlength \rangle$ before the content font size is allowed to shrink. Note that the **/gtr/node size from** may be ignored by nodes boxes which set the width individually or depending on the content width.

/gtr/child distance in parent graph= $\langle length \rangle$ (no default, initially 1mm)

The given $\langle length \rangle$ defines the minimum distance of two children of a family in a **parent** graph. The **/gtr/child distance in parent graph** can be set in dependency of the **/gtr/level**^{→P.109}. For an individual node, this distance can be overruled by setting **/gtr/distance**^{→P.96}.


```
...
\genealogytree[
  ...
  child distance in parent graph=5mm]
{
  parent{
    p{P_1}
    p{P_2}
    g{C_1}
    c[id=A]{A}
    c[id=B]{B}
  }
}
...
```



`/gtr/child distance in child graph=<length>` (no default, initially 2mm)

The given `<length>` defines the minimum distance of two children of a family in a **child** graph. The `/gtr/child distance in child graph` can be set in dependency of the `/gtr/level`^{P.109}. For an individual node, this distance can be overruled by setting `/gtr/distance`^{P.96}.

```
...
\genealogytree[
  ...
  child distance in child graph=5mm]
{
  child{
    g{P_1}
    p{P_2}
    c{C_1}
    c[id=A]{A}
    c[id=B]{B}
  }
}
...
```



`/gtr/child distance=<length>` (no default, style)


This is an abbreviation for setting `/gtr/child distance in parent graph`^{P.86} and `/gtr/child distance in child graph` to the same `<length>`.

`/gtr/parent distance in parent graph=<length>` (no default, initially 2mm)

The given $\langle length \rangle$ defines the minimum distance of two parents of a family in a **parent** graph. The `/gtr/parent distance in parent graph` can be set in dependency of the `/gtr/level`^{P.109}. For an individual node, this distance can be overruled by setting `/gtr/distance`^{P.96}.

```
...
\genealogytree[
  ...
  parent distance in parent graph=5mm]
{
  parent{
    p[id=A]{A}
    p[id=B]{B}
    g{C_1}
    c{C_2}
    c{C_3}
  }
}
...
```

parent distance




`/gtr/parent distance in child graph=<length>` (no default, initially 1mm)

The given `<length>` defines the minimum distance of two parents of a family in a **child** graph. The `/gtr/parent distance in parent graph`^{P.88} can be set in dependency of the `/gtr/level`^{P.109}. For an individual node, this distance can be overruled by setting `/gtr/distance`^{P.96}.

```
...
\genealogytree[
  ...
  parent distance in child graph=5mm]
{
  child{
    g[id=A]{A}
    p[id=B]{B}
    c{C_1}
    c{C_2}
    c{C_3}
  }
}
...
```

parent distance




`/gtr/parent distance=<length>` (no default, style)

This is an abbreviation for setting `/gtr/parent distance in parent graph`^{P.88} and `/gtr/parent distance in child graph` to the same `<length>`.

`/gtr/further distance=<length>` (no default, initially 3mm)


The given $\langle length \rangle$ defines the minimum distance of two nodes which are not parents or children of the same family. The `/gtr/further distance` can be set in dependency of the `/gtr/level`^{P.109}. For an individual node, this distance can be overruled by setting `/gtr/distance`^{P.96}.

```
...
\gtrset{
  further distance=5mm
}
...
```



If `/gtr/further distance→P.90` is set in level dependency, it is worth to note that this distance is not used for the nodes on the specified layer but for joining the subtrees on the specified layer. In the following example, the distances set on layer 1 and on layer 2 influence different nodes on layer 3.

```
...
\gtrset{
  level 1/.style={further distance=10mm},
  level 2/.style={further distance=5mm},
}
...
```



5.4 Identifiers

Identifiers play an important role for semi-automatic processing of graph data. Every node and every family can be marked by an `/gtr/id` for later reference. If the graph data is exported or generated by a tool, all nodes and families *should* be marked. This allows to manipulate the graph without editing the generated data.

`/gtr/id=<name>` (no default, initially empty)


Every node and every family can be marked by a `<name>` using this option. This `<name>` is used by `/gtr/options for node`^{P.95}, `/gtr/options for family`^{P.104}, etc, to set options for the specified node or family.

- The `<name>` should be unique inside the `tikzpicture` environment.
- A TikZ node `<name>` is automatically created for later usage.

```
...
child[id=family_a]{      % family with id 'family_a'
  p[id=A]{Father}       % node with id 'A'
  p[id=B]{Mother}       % node with id 'B'
  c[id=C]{Child}        % node with id 'C'
}
...
```


For example, let us consider the Smith-Doe graph used many times in this document, see Section 15.1 on page 359. Using the identifiers, Jane Doe should be emphasized strongly. Without specific manipulation, the graph data is depicted as follows:

```
\begin{tikzpicture}
\genealogytree[template=signpost]
{input{example.option.graph}}
\end{tikzpicture}
```




One could inspect the source code in Section 15.1 on page 359 to see the given identifiers. For a large dataset, this may become inconvenient. A good alternative is to use `/gtr/show id`^{P.265} to overlay the depicted graph with all given `/gtr/id`^{P.92} values.

```
\begin{tikzpicture}
\genealogytree[template=signpost,show id]
{input{example.option.graph}}
\end{tikzpicture}
```



Now, Jane Doe can be emphasized. Note that the id value Jane1982 is also a TikZ node and can be used such.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={Jane1982}{box={colback=red!50},pivot},
options for node={Harr1987}{distance=3.5cm} ]
{input{example.option.graph}}
\draw [decorate,decoration={brace,amplitude=5pt,mirror,raise=2pt},
line width=1pt,yshift=0pt] (Jane1982.south east) -- (Jane1982.north east)
node [align=center,right=9pt,midway,fill=yellow] {Most important\\ person};
\end{tikzpicture}
```




`/gtr/id prefix=<text>`

(no default, initially empty)

N 2015-06-09

The given $\langle text \rangle$ is prefixed to every `/gtr/id`^{P.92}. This option is intended to be used as part of an option list for a `\genealogytree`^{P.55} or `genealogypicture`^{P.57}. If not used there, it will be set to empty by `\genealogytree`^{P.55}.

```
\begin{tikzpicture}
\genealogytree[template=signpost,id prefix=xx:,show id]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/id suffix=<text>`

(no default, initially empty)

N 2015-06-09

The given $\langle text \rangle$ is suffixed to every `/gtr/id`^{P.92}. This option is intended to be used as part of an option list for a `\genealogytree`^{P.55} or `genealogypicture`^{P.57}. If not used there, it will be set to empty by `\genealogytree`^{P.55}.

```
\begin{tikzpicture}
\genealogytree[template=signpost,id suffix=@yy,show id]
{input{example.option.graph}}
\end{tikzpicture}
```




5.5 Node Options

U 2020-07-27

`/gtr/options for node={⟨id list⟩}{⟨options⟩}` (style, no default)

The given `⟨options⟩` are set for all nodes with `/gtr/id→P.92` values from the given `⟨id list⟩`. If an `/gtr/id→P.92` value is not existing, the setting is silently ignored. The intended spot for using `/gtr/options for node` is before `\genealogytree→P.55` or inside its option list. Also see Section 5.1.1 on page 78.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={Arth2008,John1980}{%
box={interior style={top color=red!30,bottom color=red}}
}]
{input{example.option.graph}}
\end{tikzpicture}
```



U 2020-07-27

`\gtrsetoptionsfor node={⟨id list⟩}{⟨options⟩}`

N 2020-07-27


`\getree_set_options_for_node:nn={⟨id list⟩}{⟨options⟩}`

Identical to using `/gtr/options for node`.

`/gtr/node={⟨options⟩}` (style, no default)

The given $\langle options \rangle$ are set for all nodes within the current scope. This scope is primarily intended to be a `/gtr/level→P.109` or `/gtr/level n→P.110` definition. For other spots, where `/gtr/node` is not needed, it may be ignored or directly replaced by its content. Also see Section 5.1.1 on page 78.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
  level 2/.style={
    node={box={interior style={top color=red!30,bottom color=red}}}
  ]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/distance=⟨length⟩` (no default, initially -1sp)

A non-negative $\langle length \rangle$ replaces the default minimum distance to the preceding sibling. The default settings are given by `/gtr/child distance in parent graph→P.86` etc.

```
\begin{tikzpicture}
\genealogytree[template=signpost,options for node={GpDo1955}{distance=2cm}]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/pivot=<value>` (default both, initially none)


Using this option, a node can gain a pivot role in the graph construction.

Feasible values are

- **none**: no special treatment.
- **child**: pivot role as a child of a family. The node will be placed centered according to its parents or its pivot parent.
- **parent**: pivot role as a parent of a family. The node will be placed centered according to its children or its pivot child.
- **both**: pivot role as a child and as a parent.

A sequence of `/gtr/pivot` settings for ancestors or descendants can be used to emphasize a certain lineage. In the following example, the nodes marked in red form such a lineage. The green node is a pivot as a child.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={Bert2010,John1980,GpSm1949}{pivot,
box={interior style={top color=red!30,bottom color=red}}},
options for node={Jane1982}{pivot=child,box={colback=green!50}} ]
{input{example.option.graph}}
\end{tikzpicture}
```



/gtr/box={⟨options⟩} (no default)

Passes the given ⟨options⟩ to the underlying **/gtr/node processor**^{→P.138}. Depending on the selected processor, the ⟨options⟩ are usually **tcloborbox** options which describe how a node box is drawn. If a processor is not based on the **tcloborbox** package, the ⟨options⟩ can be different, e.g. **TikZ** options.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
options for node={node_B}{box={colback=green!50}},
]{%
child{
g[box={colback=red!50}]{A}
p[id=node_B]{B}
c{C} c{D} c{E}
}
}
\end{tikzpicture}
```




/gtr/box clear (no value)

/gtr/box settings are additive. To clear all box settings, use this option.

/gtr/node box=⟨options⟩ (no default)

This is an abbreviation for placing **/gtr/box** inside **/gtr/node**^{→P.96}.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
level -1/.style={node box={colback=red!50}},
]{%
child{
g{A} p{B}
c{C} c{D} c{E}
}
}
\end{tikzpicture}
```



`/gtr/family box=<options>` (no default)

This is an abbreviation for placing `/gtr/box`^{→P. 98} inside `/gtr/family`^{→P. 105}.


```
\begin{tikzpicture}
\genealogytree[template=formal graph]
]{%
  child{
    g{A} p{B}
    child[family box={colback=red!50}]{
      g{C} p{a_1} c{a_2}
      child{ g{a_3} p{a_4} c{a_5} c{a_6} }
    }
    c{D} c{E}
  }
}
\end{tikzpicture}
```



`/gtr/subtree box=<options>` (no default)

This is an abbreviation for placing `/gtr/box`^{→P. 98} inside `/gtr/subtree`^{→P. 108}.

```
\begin{tikzpicture}
\genealogytree[template=formal graph]
]{%
  child{
    g{A} p{B}
    child[subtree box={colback=red!50}]{
      g{C} p{a_1} c{a_2}
      child{ g{a_3} p{a_4} c{a_5} c{a_6} }
    }
    c{D} c{E}
  }
}
\end{tikzpicture}
```




`/gtr/turn=<option>` (default `right`, initially `off`)

This is a special `/gtr/box`^{P.98} style to rotate the content a node. Typically, all nodes of a `/gtr/level n`^{P.110} may be rotated together.


Feasible `<option>` values are:

- `off`: no rotation.
- `right`: rotation by 90 degrees.
- `upside-down`: rotation by 180 degrees.
- `left`: rotation by 270 degrees.

```
\begin{tikzpicture}
\genealogytree[template=formal graph]{%
  child{
    g[turn]{A}
    p{B}
    c[turn=left]{C}   c{D}   c{E}
  }
}
\end{tikzpicture}
```




```
\begin{tikzpicture}
\genealogytree[template=signpost,
  level 2/.style={level size=3cm,node size from=1cm to 2cm,
    node={turn,box={no shadow,drop fuzzy shadow southwest}}}]
{input{example.option.graph}}
\end{tikzpicture}
```




```

\begin{tikzpicture}
\genealogytree[template=signpost,
  level 0/.style={level size=2cm,node size from=1cm to 2cm,
    node={turn=left,box={no shadow,drop fuzzy shadow northeast}}}]
{input{example.option.graph}}
\end{tikzpicture}

```



The following three options are `tcolorbox` options which are declared by the `genealogytree` package. They can be redefined for customization.

`/tcb/male` (style, no value)

A `tcolorbox` option defined as

```
\tcbset{male/.style={colframe=blue}}
```

`/tcb/female` (style, no value)

A `tcolorbox` option defined as

```
\tcbset{female/.style={colframe=red}}
```

`/tcb/neuter` (style, no value)

A `tcolorbox` option defined as

```
\tcbset{neuter/.style={}}
```

The following three options are `genealogytree` options which are shortcuts for setting the three options above inside a `/gtr/box`^{P. 98}.

`/gtr/male` (style, no value, initially unset)

This is an abbreviation for placing `/tcb/male` inside `/gtr/box`^{P. 98}.

`/gtr/female` (style, no value, initially unset)

This is an abbreviation for placing `/tcb/female` inside `/gtr/box`^{P. 98}.

`/gtr/neuter` (style, no value, initially unset)


This is an abbreviation for placing `/tcb/neuter` inside `/gtr/box`^{P. 98}.

Also see `/gtr/database/sex`^{P. 165}.

```

\begin{tikzpicture}
\genealogytree[template=formal graph,
]{
  child{
    g[male]{A}
    p[female]{B}
    c[female]{C}   c[male]{D}   c[neuter]{E}
  }
}
\end{tikzpicture}


```



```

\tcbset{
  male/.style={sharp corners,colframe=blue,colback=blue!10,
    watermark text=\gtrSymbolsSetDraw{blue!30}\gtrsymMale},
  female/.style={arc=4pt,colframe=red,colback=red!10,
    watermark text=\gtrSymbolsSetDraw{red!30}\gtrsymFemale},
  neuter/.style={arc=2pt,colframe=black!80!white,colback=black!5,
    watermark text=\gtrSymbolsSetDraw{black!20}\gtrsymNeuter},
}%
\begin{tikzpicture}
\genealogytree[template=formal graph,
]{%
  child{
    g[male]{A}
    p[female]{B}
    c[female]{C}   c[male]{D}   c[neuter]{E}
  }
}
\end{tikzpicture}


```




Applies extra TikZ *<options>* for drawing a node. These *<options>* are *not* used for the node box content, even if `/gtr/processing`^{→P.138} is set to `tikznode`. They are used in the drawing process to reserve a node space for the later placement of the box content.

The most interesting usage is to move the node from its computed position. Note that the auto-layout algorithm is *not* aware of such movements, but edge drawing will follow the new positioning.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
]{%
  child{
    g{A}   p{B}
    c[tikz={xshift=-20mm,yshift=-5mm}]{C}
    c{D}   c{E}
  }
}
\end{tikzpicture}
```



```
\begin{tikzpicture}
\genealogytree[template=formal graph,
]{%
  child{
    g{A}
    p[tikz={xshift=10mm,yshift=5mm,draw=green!75,line width=2mm}]{B}
    c[tikz={
      pin=[{fill=red!30,inner sep=2pt}left:Description]
    }]{C}
    c{D}   c{E}
  }
}
\end{tikzpicture}
```




For node movements which influence the auto-layout algorithm, see `/gtr/distance`^{→P.96}, `/gtr/pivot`^{→P.97}, and `/gtr/pivot shift`^{→P.106}. For node content option settings like coloring, see `/gtr/box`^{→P.98}.

5.6 Family Options

`/gtr/options for family={⟨id list⟩}{⟨options⟩}` (style, no default) [U](#) 2020-07-27

The given `⟨options⟩` are set for all families with `/gtr/id→P.92` values from the given `⟨id list⟩`. If an `/gtr/id→P.92` value is not existing, the setting is silently ignored. The intended spot for using `/gtr/options for family` is before `\genealogytree→P.55` or inside its option list. Also see Section 5.1.1 on page 78 and Section 5.1.2 on page 79.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for family={Doe}{box={
coltext=green!25!black,fontupper=\bfseries,width=3cm,
interior style={top color=green!50!white,bottom color=green!75!black}
}}]
{input{example.option.graph}}
\end{tikzpicture}
```



`\gtrsetoptionsforfamily{⟨id list⟩}{⟨options⟩}`
`\getree_set_options_for_family:nn{⟨id list⟩}{⟨options⟩}`

[U](#) 2020-07-27


[N](#) 2020-07-27

Identical to using `/gtr/options for family`.

`/gtr/family={⟨options⟩}` (style, no default)

The given $\langle options \rangle$ are set for all nodes and edges within the current scope. This scope is intended to be a `/gtr/level \rightarrow P.109` or `/gtr/level $n \rightarrow$ P.110` definition or an option of a family identifier like `parent` or `child`. Also see Section 5.1.1 on page 78 and Section 5.1.2 on page 79.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
  level 2/.style={
    family={
      edges={swing,foreground=red,background=red!20},
      box={interior style={top color=red!30,bottom color=red}}}
    ]
  {input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/pivot shift=<length>` (no default, initially 0pt)

For a family, there is a parent pivot point (typically centered between the parents) and a child pivot point (typically centered between the children). Normally, the auto-layout algorithms brings both points in congruence. Using a `/gtr/pivot shift`, there is a shift of the given `<length>` between these two points. Note that this works for **child**, **parent**, and **sandclock**, but not for **union**.

```
\begin{tikzpicture}
\genealogytree[template=signpost]
{
  parent[pivot shift=-1.5cm]{
    g{Child}
    p[male]{Father}
    p[female]{Mother}
  }
}
\genealogytree[tree offset=4.5cm]{
  parent{
    g{Child}
    p[male]{Father}
    p[female]{Mother}
  }
}
\genealogytree[tree offset=9cm]{
  parent[pivot shift=1.5cm]{
    g{Child}
    p[male]{Father}
    p[female]{Mother}
  }
}
}\end{tikzpicture}
```




5.7 Subtree Options

U 2020-07-27 `/gtr/options for subtree={⟨id list⟩}{⟨options⟩}` (style, no default)

The given `⟨options⟩` are set for all subtrees with `/gtr/id→P.92` values from the given `⟨id list⟩`. Subtrees are identified by the `/gtr/id→P.92` of the root family of the subtree. If an `/gtr/id→P.92` value is not existing, the setting is silently ignored. The intended spot for using `/gtr/options for subtree` is before `\genealogytree→P.55` or inside its option list. Also see Section 5.1.1 on page 78 and Section 5.1.2 on page 79.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for subtree={SmithDoe}{%
box={interior style={top color=red!30,bottom color=red}}}
]
{
parent{
g{Puppy}
input{example.option.graph}
parent
{
g[female]{Nanny}
p[male]{Pa}
p[female]{Ma}
}
}
}
\end{tikzpicture}
```



U 2020-07-27 `\gtrsetoptionsforsubtree{⟨id list⟩}{⟨options⟩}`
N 2020-07-27 `\getree_set_options_for_subtree:nn{⟨id list⟩}{⟨options⟩}`


Identical to using `/gtr/options for subtree`.

`/gtr/subtree={⟨options⟩}`

(style, no default)

The given $\langle options \rangle$ are set for all families and their nodes and edges within the current scope. This scope is intended to be a `/gtr/levelP.109` or `/gtr/level nP.110` definition or an option of a family identifier like `parent` or `child`. Also see Section 5.1.1 on page 78 and Section 5.1.2 on page 79.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
  level 2/.style={%
    subtree={edges={swing,foreground=red,background=red!20}}}
]
{
  parent{
    g{Puppy}
    input{example.option.graph}
    parent
    {
      g[female]{Nanny}
      p[male]{Pa}
      p[female]{Ma}
    }
  }
}
\end{tikzpicture}
```



5.8 Level Options

With `/gtr/level` and `/gtr/level n`^{P.110} options can be set for individual levels of the graph. Inside the key list of these styles, the following options can be used:


- All geometry options, see Section 5.3 on page 83.
- `/gtr/node`^{P.96} to set options for nodes.
- `/gtr/family`^{P.105} to set options for families.
- `/gtr/subtree`^{P.108} to set options for subtrees.
- Also see `/gtr/ignore`^{P.117} and `/gtr/ignore level`^{P.119}.

Also see Section 5.1.1 on page 78 and Section 5.1.2 on page 79.

`/gtr/level=<number>` (style, initially empty)

An initially empty style which is applied at each level with the level `<number>` as parameter. This style can be redefined.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
  level/.style={node={show=level #1}} ]
  {input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/level n`

(style, initially unset)

At each level with the level number n this style is applied after `/gtr/level`^{P.109}. This style can be (re-)defined.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
  level 2/.style={node box={colback=black!30}},
  level 1/.style={node box={colback=red!30}},
  level 0/.style={node box={colback=yellow!30}},
]
{input{example.option.graph}}
\end{tikzpicture}
```



5.9 Tree Positioning Options

/gtr/proband level= $\langle number \rangle$ (no default, initially 0)

Sets the level number of the proband to $\langle number \rangle$. All level numbers inside the given tree will be adapted accordingly. This is useful in connection with **/gtr/level**^{→P.109} dependent settings, especially when two trees are connected.

/gtr/tree offset= $\langle length \rangle$ (no default, initially 0pt)

Sets the offset value of the root family to $\langle length \rangle$. Depending on the given **/gtr/timeflow**^{→P.80}, this means a shift in horizontal or vertical direction in reference of the **tikzpicture** coordinate system.

/gtr/after parser= $\langle code \rangle$ (no default, initially empty)

Adds $\langle code \rangle$ to a list of code which is executed after the tree content is parsed and before the parsed data is drawn. This is used internally by other options and may not be needed by a normal user.

The following options allow to shift the whole tree such that a specific node is placed at a specific position.

- **/gtr/set position**: place a node centered at a position.
- **/gtr/adjust position**^{→P.112}: place a node relative to a position (respecting the node dimensions).
- **/gtr/adjust node**^{→P.113}: place a node relative to another node (respecting both node dimensions).


/gtr/set position= $\langle node \rangle$ at $\langle position \rangle$ (style, no default)

Adjusts the current graph such that a $\langle node \rangle$ of the graph is placed at the given $\langle position \rangle$. If the $\langle position \rangle$ is given by coordinates, one has to use curly brackets to enclose $\langle position \rangle$, e.g. {2,3}. The $\langle node \rangle$ is identified by a **/gtr/id**^{→P.92}.

```
\begin{tikzpicture}
\node[draw,fill=red!30,minimum size=3cm] (X) at (0,0) {};
\draw[white] (X.south west)--(X.north east) (X.north west)--(X.south east);

\genealogytree[template=signpost,
  set position=Harr1987 at X,
  options for node={Harr1987}{box={colback=yellow!50}}]
{input{example.option.graph}}

\draw[red!70] (Harr1987) circle (1.5cm);
\end{tikzpicture}
```



`/gtr/adjust position=<node> <direction> of <position>` (style, no default)
`distance <distance> shift <shift>`


Adjusts the current graph such that a `<node>` of the graph is placed in the given `<direction>` relative to the given `<position>` with a given `<distance>` in this direction and an optional `<shift>` orthogonal to the direction. The `<node>` is identified by a `/gtr/id→P.92`.

Feasible values for the `<direction>` are

- `right`
- `left`
- `above`
- `below`

```
\begin{tikzpicture}
\draw[red] (-0.3,-0.3)---+(0.6,0.6) (-0.3,0.3)---+(0.6,-0.6);
\node[right=3mm] at (0,0) {Reference Position};

\genealogytree[template=signpost,
adjust position=Harr1987 left of {0,0} distance 1cm,
options for node={Harr1987}{box={colback=yellow!50}}]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/adjust node=<node> <direction> of <reference node>` (style, no default)
`distance <distance> shift <shift>`


Adjusts the current graph such that a `<node>` of the graph is placed in the given `<direction>` relative to the given `<reference node>` (a TikZ node) with a given `<distance>` in this direction and an optional `<shift>` orthogonal to the direction. The `<node>` is identified by a `/gtr/id→P.92`.

Feasible values for the `<direction>` are

- `right` (right of `<reference node>.east`)
- `left` (left of `<reference node>.west`)
- `above` (above of `<reference node>.north`)
- `below` (below of `<reference node>.south`)

```
\begin{tikzpicture}
\node[fill=yellow!50,draw=red] (R) {Reference Node};

\genealogytree[template=signpost,
adjust node=Harr1987 left of R distance 1cm,
options for node={Harr1987}{box={colback=yellow!50}}]
{input{example.option.graph}}
\end{tikzpicture}
```




5.10 TikZ and Tcolorbox Options

Also see `/gtr/tikz` ^{→ P. 103}.

`/gtr/tikzpicture={⟨tikz options⟩}` (no default, initially empty)

Used to insert `⟨tikz options⟩` to the `tikzpicture` environment inside `genealogypicture` ^{→ P. 57}.
This option is ignored by `\genealogytree` ^{→ P. 55}!

```
\begin{genealogypicture}[template=formal graph,
  tikzpicture={execute at end picture={
    \path[draw=red,double,double distance=1pt,very thick,rounded corners]
      ([xshift=-5mm,yshift=-5mm]current bounding box.south west) rectangle
      ([xshift=5mm,yshift=5mm]current bounding box.north east);}} ]
  child{
    g[box={colback=red!50}]{A}
    p{B}
    c{C} c{D} c{E}
  }
\end{genealogypicture}
```




`/gtr/tikzset={⟨tikz options⟩}` (no default, initially empty)

Used to insert `⟨tikz options⟩` before the tree is drawn by `\genealogytree` ^{→ P. 55} or `genealogypicture` ^{→ P. 57}. In contrast to `/gtr/tikzpicture`, one can use `/gtr/tikzset` also for `\genealogytree` ^{→ P. 55}, but some settings may need to be given in the argument of `tikzpicture` (see *The TikZ and PGF Packages* [5]).

Note that `\genealogytree` ^{→ P. 55} does not limit the scope of these settings.


```
\begin{genealogypicture}[template=formal graph,
  tikzset={myfill/.style={top color=yellow,bottom color=red}} ]
  child{
    g[box={interior style=myfill}]{A}
    p{B}
    c{C} c{D} c{E}
  }
\end{genealogypicture}
```



`/gtr/after tree={\tikz code}` (no default, initially empty)

Used to insert `\tikz code` after the tree is drawn by `\genealogytree`^{P.55} or `genealogypicture`^{P.57}. This is also used internally by other options.

```
\begin{genealogypicture}[template=formal graph,
  after tree={ \draw[very thick,blue,-Latex] (node_A) to[out=180,in=120] (node_C);
  }]
  child{
    g[box={colback=red!50},id=node_A]{A}
    p{B}
    c[id=node_C]{C}   c{D}   c{E}
  }
\end{genealogypicture}
```




`/gtr/tcbset={\tcolorbox options}` (no default, initially empty)

Used to insert `\tcolorbox options` before the tree is drawn by `\genealogytree`^{P.55} or `genealogypicture`^{P.57}.

Note that `\genealogytree`^{P.55} does not limit the scope of these settings.

```
\begin{genealogypicture}[template=formal graph,
  tcbset={
    male/.style={colframe=blue,colback=blue!5},
    female/.style={colframe=red,colback=red!5}
  }
]
  child{
    g[male]{A}
    p[female]{B}
    c[male]{C}   c[female]{D}   c[male]{E}
  }
\end{genealogypicture}
```



`/tikz/fit to family=<id>` (style, no default)


This is an extension to the `fit` library of TikZ. This option must be given to a `node` path command. The `<id>` has to be an `/gtr/idP.92` value of a family. All nodes of this family are given to the `fit` option of a TikZ node which is sized to frame all family members.

`/tikz/fit to subtree=<id>` (style, no default)

Like `/tikz/fit to family`, this is an extension to the `fit` library of TikZ. All nodes of the subtree identified by `<id>` are given to the `fit` option of a TikZ node which is sized to frame the whole subtree.

```
\begin{tikzpicture}
\genealogytree[template=tiny boxes]
{
  child[id=R,family box={colback=blue}]{
    g-p-
    child{
      g-p-c-c-c-c-c-
      child{ p-g-c- }
    }
  }
  c-c-
  child{ g-p-c- }
  child[id=X,subtree box={colback=red}]{
    p-g-
    child{ g-p-c-c-c-c-c- }
    union{
      p-c-c-
      child{ g-p-c-c- }
    }
  }
}
}

\node[draw=blue,fill=blue!20,fill opacity=0.25,inner sep=0.5mm,
pin={[pin edge=blue]left:family with id R},
fit to family=R] {};
\node[draw=red,fill=red!20,fill opacity=0.25,inner sep=0.5mm,
pin={[pin edge=red]right:subtree with id X},
fit to subtree=X] {};
\end{tikzpicture}
```



5.11 Ignoring Input

The following options allow to ignore some parts of the input data. Note that debugging using the methods from Chapter 11 on page 249 will usually ignore the ignore settings. Also, if some counters are incremented by node or family options, these increments may not be undone by ignoring the particular node or family.

`/gtr/ignore=true|false` (default `true`, initially `false`)

The `/gtr/ignore` option can be used inside the option list for any node or family specifier. Child `c` and parent `p` leaf nodes are simply ignored, if this option is used. An error will arise, if a `g` node is ignored and there is no other `g` node for the family.

- Using `/gtr/ignore` inside a node ignores this node.
- Using `/gtr/ignore` inside a family means that the whole subtree becomes ignored.
- Using `/gtr/ignore` inside `/gtr/level n`^{P.110} means that all families on this level are ignored. Since families span two levels, the effect may not be restricted to the target level. Leaf nodes on the target level are not affected. Also see `/gtr/ignore level`^{P.119}.

To ignore a node or subtree by its `/gtr/id`^{P.92}, use `/gtr/ignore node`^{P.118} or `/gtr/ignore subtree`^{P.118}.

```
\begin{tikzpicture}
\genealogytree[template=signpost,timeflow=left,level size=3cm]
{
  parent[id=DoeJones]{
    g[id=Deir2012,female]{Deirdre\\gtrsymBorn\,2012}
    parent[id=Jones]{
      g[id=Mary1988,female]{Aunt Mary\\gtrsymBorn\,1988}
      p[id=JimJ1944,male]{Jim Jones\\gtrsymBorn\,1944}
      % the following node is going to be ignored
      p[ignore,id=Jenn1949,female]{Jenny Jones\\gtrsymBorn\,1949}
    }
  }
}
\end{tikzpicture}
```




`/gtr/ignore node={⟨id list⟩}`

(style, no default)

[U 2020-07-27](#)

All nodes with `/gtr/id→P.92` values from the given `⟨id list⟩` are ignored. If an `/gtr/id→P.92` value is not existing, the setting is silently ignored.

```
\begin{tikzpicture}
\genealogytree[template=signpost,ignore node={Bert2010,Char2014,Harr1987}]
{input{example.option.graph}}
\end{tikzpicture}
```



`\gtrignorenode{⟨id list⟩}`

[U 2020-07-27](#)

Identical to using `/gtr/ignore node`.


`/gtr/ignore subtree={⟨id list⟩}`

(style, no default)

[U 2020-07-27](#)

All subtrees with `/gtr/id→P.92` values from the given `⟨id list⟩` are ignored. If an `/gtr/id→P.92` value is not existing, the setting is silently ignored.

```
\begin{tikzpicture}
\genealogytree[template=signpost,ignore subtree={Doe}]
{input{example.option.graph}}
\end{tikzpicture}
```



`\gtrignoresubtree{⟨id list⟩}`

[U 2020-07-27](#)

Identical to using `/gtr/ignore subtree`.

`/gtr/ignore level=<number>` (style, no default)


The level with the given $\langle number \rangle$ is ignored. This also removes unconnected nodes and families. **Note that `/gtr/ignore level` should never be used, if `/gtr/proband level`^{P.111} was set!**

This style sets `/gtr/level n`^{P.110} options to remove all unwanted nodes and families. Depending on the algebraic sign of $\langle number \rangle$ the implementation differs. Zero has no effect.

```
\gtrset{ignore level=4}  
% is equal to  
\gtrset{level 4/.style={node=ignore},level 5/.style={ignore}}
```

```
\gtrset{ignore level=-4}  
% is equal to  
\gtrset{level -4/.style={ignore,node=ignore}}
```


```
\begin{tikzpicture}  
\genealogytree[template=signpost,ignore level=2]  
{input{example.option.graph}}  
\end{tikzpicture}
```



Ignores all child nodes `c` in a `parent` graph. Thereby, all siblings in an ancestor tree are removed.

This is a global option for the whole graph and cannot be applied locally.

```
\begin{tikzpicture}
\genealogytree[template=signpost,ignore parent childs]
{input{example.option.graph}}
\end{tikzpicture}
```



5.12 Inserting Input

The following options allow to insert parsable data into the input. This is a powerful feature with the risk to corrupt the structure of the resulting graph. Note that grammar checks are not so strictly applied at the insertion points and occurring errors may be difficult to detect.


`\gtrparserdebug`^{→P. 250} ignores inserting options, while `\gtrprocessordebug`^{→P. 252} uses these options.

Recursive insertion is possible, i.e. inserting into already inserted data, but should be handled with care. Especially, using `/gtr/insert after node` and `/gtr/insert after family`^{→P. 122} should never be used to insert data after the root element of an inserted node or family.

`/gtr/insert after node={⟨id⟩}{⟨input data⟩}` (style, no default)

Inserts `⟨input data⟩` into the graph data right after the node with the given `⟨id⟩` was processed. If no node with `⟨id⟩` exists, this setting is silently ignored. If more than one insert command was given for a specific node, following insert commands for this node are ignored. Note that grammar checks are not so strictly applied at the insertion point, i.e. one has to be more careful to obey the rules to avoid mess.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
insert after node={A}{ c[box={colback=yellow!50}]- },
insert after node={B}{ child[subtree box={colback=red!50}]{g-p-c-c-c-} },
]
{
child{ g-p-
child{ g-p-c-c[box={colback=blue!30},id=A]-c- }
c[box={colback=blue!30},id=B]-c-
}
}
\end{tikzpicture}
```



`/gtr/insert after family={⟨id⟩}{⟨input data⟩}` (style, no default)

Inserts $\langle input\ data \rangle$ into the graph data right after the family with the given $\langle id \rangle$ was processed. If no family with $\langle id \rangle$ exists, this setting is silently ignored. There should be not more than one `/gtr/insert after family` command for a specific family; using it twice may give unpredictable results. Note that grammar checks are not so strictly applied at the insertion point, i.e. one has to be more careful to obey the rules to avoid mess. Especially, never use `/gtr/insert after family` for the root family!


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
insert after family={fam_a}{
child[subtree box={colback=red!50}]{g-p-c-c-}
c[box={colback=yellow!50}]-
},
]
{
child[id=root]{ g-p-
child[subtree box={colback=blue!30},id=fam_a]{ g-p-c-c-c- }
c-c-
}
}
\end{tikzpicture}
```



`/gtr/insert at begin family={⟨id⟩}{⟨input data⟩}` (style, no default)

Inserts $\langle input data \rangle$ into the graph data of the family with the given $\langle id \rangle$, before the content of the family is processed. If no family with $\langle id \rangle$ exists, this setting is silently ignored. There should be not more than one `/gtr/insert at begin family` command for a specific family; using it twice may give unpredictable results. Note that grammar checks are not so strictly applied at the insertion point, i.e. one has to be more careful to obey the rules to avoid mess.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
insert at begin family={fam_a}{
child[subtree box={colback=red!50}]{g-p-c-c-}
p[box={colback=yellow!50}]-
},
]
{
child[id=root]{ g-p-
child[subtree box={colback=blue!30},id=fam_a]{ g-c-c-c- }
c-c-
}
}
\end{tikzpicture}
```



`/gtr/insert at end family={⟨id⟩}{⟨input data⟩}` (style, no default)

Inserts $\langle input\ data \rangle$ into the graph data of the family with the given $\langle id \rangle$, after the content of the family is processed. If no family with $\langle id \rangle$ exists, this setting is silently ignored. There should be not more than one `/gtr/insert at end family` command for a specific family; using it twice may give unpredictable results. Note that grammar checks are not so strictly applied at the insertion point, i.e. one has to be more careful to obey the rules to avoid mess.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
insert at end family={fam_a}{
child[subtree box={colback=red!50}]{g-p-c-c-}
p[box={colback=yellow!50}]-
},
]
{
child[id=root]{ g-p-
child[subtree box={colback=blue!30},id=fam_a]{ g-c-c-c- }
c-c-
}
}
\end{tikzpicture}
```



5.13 Phantom Nodes and Subtrees


U 2015-06-08

`/gtr/phantom=<length>`


(style, default `/gtr/node size` ^{P.85})

A `/gtr/subtree` ^{P.108} style which makes the whole current subtree invisible. This style can also be applied for single nodes. If a `<length>` value is used, the `/gtr/node size` ^{P.85} for all nodes of the subtree is replaced by `<length>` (width for vertical time flow and height for horizontal time flow).

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
]
{
child{ g-p-
child{ g-p-
c[id=A]-
% invisible phantom
c[phantom=2cm]-
c-
}
% phantom; borders made visible
child[phantom,subtree box={show bounding box}]{
g-p-c-c-c-
}
c[id=B]-
}
}
\end{tikzpicture}
```




```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
insert after node={A}{ c[phantom]- },
insert after node={B}{ c[phantom*]- },
]
{
parent{
g-c[id=A]-c[id=B]-
p-p-
}
}
\end{tikzpicture}
```



```


\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
]
{
child{ g-p-
child{ g-p-
child{ g-p-c-c-c-}
c-c-
child{ g-p-c-c-
child{ g-p-c-c-c-}
}
}
}
child[phantom=3cm]{g[id=P1]-c[id=P2]-}
child{ g-p-c-
child{ g-p-
child{ g-p-c-c-c-c-}
c-c-
}
}
}
}
}
\path[draw,top color=yellow!50,bottom color=blue!50]
(P2.south west) rectangle node {Phantom Area} (P1.north east);
\end{tikzpicture}

```



Identical to `/gtr/phantom` ^{→ P. 125}, but the phantom subtree is connected by an edge with its embedding family.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
content interpreter content={\gtrifnodeid{\gtrnodeid}{n_{\gtrnodenumber}}},
]
{
child{ g-p-
child{ g-p-
c[id=A]-
% invisible phantom
c[phantom*=2cm]-
c-
}
% phantom; borders made visible
child[phantom*,subtree box={show bounding box}]{
g-p-c-c-c-
}
c[id=B]-
}
}
\end{tikzpicture}
```



5.14 Childless Families

For childless families in a **child** or **sandclock** graph, there is in some situations the danger of overlapping edges, if the perpendicular edge drawing is used, also see Section 14.4 on page 356. In the following, a (partial) solution is described which automatically inserts phantom nodes (childs) to childless families using some options. For the impatient: try `/gtr/insert phantom for childless families`^{→P.130} and read the details later.

```
\begin{tikzpicture}
\genealogytree[template=tiny boxes,
childless/.style={family={box={colback=red!20},
edges={foreground={red,line width=0.2mm}}}} ]
{
  child{ g-p-
    child[childless,id=A]{ g-p- union{ p-c- } }
    child{ g-p-
      c-
      child[childless,id=C]{ g-p- }
      child{ g-c-c-
        child[childless,id=E]{ g- }
        child[childless,id=F]{ p-g- }
        c- }
      c-
      child[childless,id=D]{ g- }
      c-}
    child[childless,id=B]{ g-p- }
  }
}
\end{tikzpicture}
```



In the example above, childless families are marked in red color. Not all cases are critical. For the six childless families from left to right and top to bottom:

- The upper left childless family (A) also contains a **union** construct with a child. The resulting patchwork family is therefore not considered childless and there is no edge overlapping problem besides the usual one described in Section 14.2.2 on page 352. `/gtr/insert for childless families`^{→P.129} ignores this patchwork family.
- The upper right childless family (B) has overlapping edges with the edges of the sibling. Without coloring, the impression of four parents is given. Inserting a phantom child node is a way to avoid the problem.
- The same is true for the next family (middle left, C) where the nodes falsely appear like parents of the sibling family.
- The middle right childless family (D) is a fake family. Here, `child{ g- }` was used instead of `c-`. Currently, this makes no difference, but `/gtr/insert for childless families`^{→P.129} will insert a phantom child which changes the layout.
- The lower left childless family (E) is the same kind of fake family. Inserting a phantom node will increase the graph by one (useless) level.


- The lower right childless family (F) will also get a phantom node increasing the graph by one level. Since this family is on the lowest layer, edge overlapping is not possible and a phantom child is not needed. Nevertheless, `/gtr/insert for childless families` will add a child, if not hindered by setting `/gtr/insert for childless families level limit`^{→P.131} to a suitable number.

N 2020-05-20

`/gtr/insert for childless families={⟨input data⟩}` (no default, initially empty)

Inserts `⟨input data⟩` into the graph data of *all* **child** families which are childless, after the content of the family is processed. Alternatively, a more fine granular control is possible by using `/gtr/insert at end family`^{→P.124} for all needed cases. See the discussion above about childless families.

```
\begin{tikzpicture}
\genealogytree[template=tiny boxes,
insert for childless families={c[box={colback=black!90}]{}},
childless/.style={family={box={colback=red!20},
edges={foreground={red,line width=0.2mm}}}} ]
{
child{ g-p-
child[childless,id=A]{ g-p- union{ p-c- } }
child{ g-p-
c-
child[childless,id=C]{ g-p- }
child{ g-c-c-
child[childless,id=E]{ g- }
child[childless,id=F]{ p-g- }
c- }
c-
child[childless,id=D]{ g- }
c-}
child[childless,id=B]{ g-p- }
}
}
\end{tikzpicture}
```



Note that the patchwork family (upper left) is not considered childless, does not need inserted input and does not get one.

Also note that the two single-person families without child do not need inserted input, but get one anyhow. Avoid this by using `c-` instead of `child{ g- }`.


For the lowest level, the layout algorithm does not need inserted input at all, but get it. This can be avoided manually by setting `/gtr/insert for childless families level limit`^{→P.131} appropriately.

This is a shortcut for using

`/gtr/insert for childless families`^{→P.129}`={c[phantom]{}}`

An invisible `/gtr/phantom`^{→P.125} node is inserted for every childless family in a **child** (**sandclock**) graph to avoid overlapping edges with sibling families. Details see above.

```
\begin{tikzpicture}
\genealogytree[template=tiny boxes,
insert phantom for childless families,
childless/.style={family={box={colback=red!20},
edges={foreground={red,line width=0.2mm}}}} ]
{
child{ g-p-
child[childless,id=A]{ g-p- union{ p-c- } }
child{ g-p-
c-
child[childless,id=C]{ g-p- }
child{ g-c-c-
child[childless,id=E]{ g- }
child[childless,id=F]{ p-g- }
c- }
c-
child[childless,id=D]{ g- }
c-}
child[childless,id=B]{ g-p- }
}
}
\end{tikzpicture}
```




Note the superfluous vertical space below the graph. Here, the space for the phantom nodes of the lowest level row is reserved. This can be avoided manually by setting `/gtr/insert for childless families level limit`^{→P.131} appropriately.

`/gtr/insert for childless families level limit=<level>` (no default, initially -2147483647)

`/gtr/insert for childless families`^{→ P.129} and `/gtr/insert phantom for childless families`^{→ P.130} are only respected, if the current `/gtr/level`^{→ P.109} is larger than `/gtr/insert for childless families level limit`.

Typically, `/gtr/insert for childless families level limit` is set to the lowest level number of the graph to avoid an inserted empty level. See `/gtr/level`^{→ P.109} for an example to display the level numbers.

```
\begin{tikzpicture}
\genealogytree[template=tiny boxes,
insert phantom for childless families,
insert for childless families level limit=-3,
childless/.style={family={box={colback=red!20},
edges={foreground={red,line width=0.2mm}}}} ]
{
child{ g-p-
child[childless,id=A]{ g-p- union{ p-c- } }
child{ g-p-
c-
child[childless,id=C]{ g-p- }
child{ g-c-c-
child[childless,id=E]{ g- }
child[childless,id=F]{ p-g- }
c- }
c-
child[childless,id=D]{ g- }
c-}
child[childless,id=B]{ g-p- }
}
}
\end{tikzpicture}
```



5.15 Autofill Parent Graphs (Ancestors)

Missing nodes (ancestors) in a **parent** graph can be automatically added using the following options. All options in this section complement parents in a family to two parents. Note that the algorithm does not check and will fail, if a family contains three or more parent nodes.

The options are global for the graph and cannot be applied for subtrees. See `\gtrparent1`^{→P.309}, `\gtrparent2`^{→P.309}, etc. for local complementation.

`/gtr/autofill parents unspecific=<level>` (default 5, initially unset) N 2020-06-05
`/gtr/autofill parents unspecific*=<level>` (default 5, initially unset) N 2020-06-05


Complements all ancestors of **parent** families up to the given `<level>`.

All added nodes are customized by `/gtr/complemented`^{→P.135}.

- For a **parent** family with zero parents, two parents are added.
- For a **parent** family with a single parent, one parent is added.
- For a **parent** family with two parents, nothing is added.

`/gtr/autofill parents unspecific` also sets `/gtr/ignore level`^{→P.119} to `<level>+1`.

```
\begin{tikzpicture}
\genealogytree[template=formal graph,
autofill parents unspecific=3,
complemented/.style={box={colframe=gray!50,colback=gray!10}},
complemented family/.style={edges={%
foreground={gray!50,line width=1pt},background={white,line width=1.75pt}}},
]
{
parent{
g{A}
parent{
g{B}
p{C}
parent{
g{D}
p{E}
}
}
}
p{F}
}
}
\end{tikzpicture}
```



`/gtr/autofill parents male female=<level>` (default 5, initially unset)

`/gtr/autofill parents male female*=<level>` (default 5, initially unset)

This options needs `/gtr/processing`^{→ P.138}=`database`. See Chapter 7 on page 161 for the database processing concept.


Complements all ancestors of `parent` families up to the given `<level>`.

All added nodes are customized by `/gtr/complemented`^{→ P.135}.

- For a `parent` family with zero parents, a `/gtr/database/male`^{→ P.165} and a `/gtr/database/female`^{→ P.165} parent node are added.
- For a `parent` family with a single `/gtr/database/male`^{→ P.165} parent, a `/gtr/database/female`^{→ P.165} parent node is added.
- For a `parent` family with a single `/gtr/database/female`^{→ P.165} parent, a `/gtr/database/male`^{→ P.165} parent node is prefixed.
- For a `parent` family with two parents which are `/gtr/database/male`^{→ P.165} and `/gtr/database/female`^{→ P.165}, nothing is changed.
- For a `parent` family with two parents which are `/gtr/database/female`^{→ P.165} and `/gtr/database/male`^{→ P.165}, the sorting order is reversed.

`/gtr/autofill parents male female` also sets `/gtr/ignore level`^{→ P.119} to `<level>+1`.

```
\begin{tikzpicture}
\genealogytree[template=database sideways,
  database format=name,empty name text={},
  level size=3cm,node size from=6mm to 50mm,
  box={valign=center},
  autofill parents male female=3,
]
{
  parent{
    g{male,name=\pref{Frederik} \surn{Smith}}
    parent{
      g{male,name=\pref{Ernest} \surn{Smith}}
      parent{
        g{male,name=\pref{Dominik} \surn{Schmidt}}
        p{female,name=\pref{Katharina} \surn{Schmidt}}
      }
      p{female,name=\pref{Maria} \surn{Huber}}
    }
  }
}
\end{tikzpicture}
```



<code>/gtr/autofill parents female male=<level></code>	(default 5, initially unset)	N 2020-06-05
<code>/gtr/autofill parents female male*=<level></code>	(default 5, initially unset)	N 2020-06-05

This options needs `/gtr/processing→P.138=database`. See Chapter 7 on page 161 for the database processing concept.


Complements all ancestors of **parent** families up to the given `<level>`.

All added nodes are customized by `/gtr/complemented→P.135`.

- For a **parent** family with zero parents, a `/gtr/database/female→P.165` and a `/gtr/database/male→P.165` parent node are added.
- For a **parent** family with a single `/gtr/database/male→P.165` parent, a `/gtr/database/female→P.165` parent node is prefixed.
- For a **parent** family with a single `/gtr/database/female→P.165` parent, a `/gtr/database/male→P.165` parent node is added.
- For a **parent** family with two parents which are `/gtr/database/male→P.165` and `/gtr/database/female→P.165`, the sorting order is reversed.
- For a **parent** family with two parents which are `/gtr/database/female→P.165` and `/gtr/database/male→P.165`, nothing is changed.

`/gtr/autofill parents female male` also sets `/gtr/ignore level→P.119` to `<level>+1`.

```
\begin{tikzpicture}
\genealogytree[template=database sideways,
  database format=name,empty name text={},
  level size=3cm,node size from=6mm to 50mm,
  box={valign=center},
  autofill parents female male=3,
]
{
  parent{
    g{male,name=\pref{Frederik} \surn{Smith}}
    parent{
      g{male,name=\pref{Ernest} \surn{Smith}}
      parent{
        g{male,name=\pref{Dominik} \surn{Schmidt}}
        p{female,name=\pref{Katharina} \surn{Schmidt}}
      }
      p{female,name=\pref{Maria} \surn{Huber}}
    }
  }
}
\end{tikzpicture}
```



<code>/gtr/autofill parents none</code>	(initially set)	N 2020-05-26
-----------------------------------------	-----------------	--------------

Switches the autofill algorithm off, i.e. this sets the normal case.

N 2020-05-26 `/gtr/complemented` (style, initially empty)

An initially empty style which is applied for every complemented parent node. This style can be redefined, see example for `/gtr/autofill parents unspecific` ^{→ P. 132}.

N 2021-09-28 `/gtr/complemented family` (style, initially empty)

An initially empty style which is applied for every complemented parent family. This style can be redefined, e.g. to set a dimmed edge drawing for complemented families. Note that this style does not apply to a family, where just one parent was autofilled.

```
\gtrset{
  complemented family/.style={%
    edges={rounded=3pt,
      foreground={gray!50,line width=0.2mm},
      background={white,line width=0.6mm}
    },
  }
}
```

N 2020-06-03 `/gtr/complemented phantom` (style)

A style which sets `/gtr/complemented/.style={phantom}`. This sets all complemented nodes to be `/gtr/phantom` ^{→ P. 125} nodes (invisible).

5.16 Special and Auxiliary Options


/gtr/reset (no value)

Resets all options to their default values.

/gtr/code= $\langle code \rangle$ (no default)

The given $\langle code \rangle$ is executed immediately. This option is useful to place some arbitrary code into an option list.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
code={\newcommand{\mycom}{(a_{\gtrnodenumber})}},
]{
  child{
    g{A~\mycom}
    p{B}
    c{C}   c{D~\mycom}   c{E}
  }
}
\end{tikzpicture}
```



/gtr/keysfrom= $\langle macro \rangle$ (no default)

The given $\langle macro \rangle$ (without parameters) is supposed to contain an option list. The keys from the list are applied.

```
\newcommand{\mylist}{
  level distance=1cm,
  level -1/.style={node box={colback=red!50}},
  edges={no background,foreground={blue,Circle-Latex}},
}
%
\begin{tikzpicture}
\genealogytree[template=formal graph, keysfrom=\mylist]
]{
  child{
    g{A}
    p{B}
    c{C}   c{D}   c{E}
  }
}
\end{tikzpicture}
```



6

Node Data (Content) Processing

Every node in a `\genealogytree`^{→P.55} graph is drawn inside a rectangular box. These boxes are arranged by the auto-layout algorithm to build the entire graph.

The interior of a node box is created by an element called `/gtr/node processor`^{→P.138}. Several customizable node processors are predefined by the package to choose from. Further, an own node processor can be added easily.

The node data may be used *as-is* or changed in some way before the node processor displays it. This is done by an element called `/gtr/content interpreter`^{→P.155}. Again, several content interpreters are predefined by the package to choose from and own interpreters can be added.

The combination of node interpreter and node processor is called *node data processing* in the following.

Two classes of node processings can be distinguished:

- Non-interpreting node data processings take their content text *as-is* and just format it with colors, fonts, frames, etc; see Section 6.2 on page 139.
- Interpreting node data processings use some `/gtr/content interpreter`^{→P.155} to possibly change the content.
 - The most prominent processing is database node processing where the node content is interpreted as organized data. Some representation of the data will form the visual output; see Chapter 7 on page 161.
 - Further interpreters are documented in Section 6.4 on page 155.

6.1 Setting a Node Data Processing and Processor

In this context, there is a small difference between *node data processing* and a *node data processors*. The *processing* is the combination of an *node data interpreter* and a *node data processors*. If the interpreter does not change the node data, the difference vanishes.

/gtr/node processor= $\langle macro \rangle$ (no default)

Sets a $\langle macro \rangle$ for processing the content of a node. This $\langle macro \rangle$ has to be defined without parameters. It should display the node content which is stored in `\gtrBoxContent` ^{→ P. 154}.

```
\newcommand{\myprocessor}{%
  \tikz\node[outer sep=0pt]{\gtrBoxContent};%
}

\gtrset{node processor=\myprocessor}
```

This option is useful for authors who wish to implement some very specific node processing (drawing) which is not covered by the standard mechanisms. See `/gtr/processing` for the standard processors. Since the standard processors are highly customizable, there may be no need to create a specific processor for most use cases.

A predefined `/gtr/node processor` is set by using `/gtr/processing` which also sets a `/gtr/content interpreter` ^{→ P. 155}.

/gtr/processing= $\langle processing \rangle$ (no default, initially `fit`)

Defines the base procedure for processing the content of a node. Feasible values for $\langle processing \rangle$ are

- **fit**: The content is set *as-is* inside a `\tcboxfit` macro from the `tcolorbox` package, see Section 6.2.1 on page 139.
- **tcolorbox**: The content is set *as-is* inside a `tcolorbox` environment from the `tcolorbox` package, see Section 6.2.2 on page 143.
- **tcbox**: The content is set *as-is* inside a `\tcbox` macro from the `tcolorbox` package, see Section 6.2.3 on page 146.
- **tcbox***: As a variant to `tcbox`, the content is also set *as-is* inside a `\tcbox` macro from the `tcolorbox` package, see Section 6.2.4 on page 149.
- **tikznode**: The content is set *as-is* inside a `\node` macro from the `tikz` package, see Section 6.2.5 on page 152.
- **database**: The content is interpreted as database key-value pairs. The processed content is set inside a `\tcboxfit` macro from the `tcolorbox` package, see Chapter 7 on page 161.

Values given to `/gtr/box` ^{→ P. 98} will be interpreted according to the defined $\langle processing \rangle$. For **tcolorbox**, the values have to be `tcolorbox` settings; for **tikznode**, the values have to be `tikz` settings.

6.2 Predefined Non-Interpreting Processings

6.2.1 fit

```
/gtr/processing→P.138=fit
```

The preset processing is based on `\tcboxfit` of the `tcolorbox` package [4]. Options given to `/gtr/box→P.98` have to be `tcolorbox` options which are used by `\tcboxfit`.

The `/gtr/no content interpreter→P.157` is used. The main characteristics of the applied node data processor are:


- Full observance of `/gtr/level size→P.84`, `/gtr/node size→P.85`, and `/gtr/node size from→P.86`. These options can be used without restriction.
- The node content is set inside a `minipage`. The text size of the content and the margins are shrunk automatically, if needed. The used font should be freely scalable for this.
- Due to the fit algorithm, this node processing will consume more compilation time than other ones.
- To observe node and level settings as far as possible, the dimensions can be set by `/tcb/gtrNodeDimensions` or `/tcb/gtrNodeDimensionsLandscape`. `/tcb/gtrNodeDimensions` is initially set.

This processor is also used for database processing, see Chapter 7 on page 161.

```

\begin{genealogypicture}[processing=fit]
  child{ g{root} p{X}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}


```




```

\begin{genealogypicture}[processing=fit,
  level size=1cm,node size from=1.5cm to 4cm,
  box={halign=center,valign=center,size=small,arc=2mm,colback=red!20}]
child{ g{root} p{This is some longer text.}
  child{ p{Y} g{A} c{B} c{C} }
  c{D}
  child{ g{E}
    p{This is a quite long text. This text so long that
      the font size has to shrink.}
    c{F} c{G} c{H} }
  }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=fit,
  timeflow=right,
  level size=3cm,level distance=10mm,
  node size from=1cm to 2cm,
  box={halign=center,valign=center,size=small,arc=2mm,colback=blue!20}]
%
child{ g{root} p{This is some longer text.}
  child{ p{Y} g{A} c{B} c{C} }
  c{D}
  child{ g{E}
    p{This is a quite long text. This text so long that
      the font size has to shrink.}
    c{F} c{G} c{H} }
  }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=fit,
  level size=1.5cm,level distance=5mm,node size=2cm,
  box={halign=center,valign=center,size=small,arc=2mm,colback=green!20}]
%
child{ g{root}
  c[turn=left]{Abc}
  c[turn=upsideup]{Bcd}
  c[turn=right]{Cde}
}
\end{genealogypicture}

```



6.2.2 tcolorbox

```
/gtr/processing→P.138=tcolorbox
```

This processing is based on the **tcolorbox** environment of the tcolorbox package [4]. Options given to `/gtr/box→P.98` have to be tcolorbox options.


The `/gtr/no content interpreter→P.157` is used. The main characteristics of the applied node data processor are:

- For `/gtr/timeflow→P.80` settings **up** and **down**, full observance of `/gtr/node size→P.85`, but no observance of `/gtr/node size from→P.86`. The `/gtr/level size→P.84` is observed, but content which is too large may overflow.
- For `/gtr/timeflow→P.80` settings **left** and **right**, full observance of `/gtr/level size→P.84`. `/gtr/node size→P.85` and `/gtr/node size from→P.86` are both observed, but content which is too large may overflow.
- Using the option **natural height**, the height of a node box can be freely adapted to its content. This may be especially useful for `/gtr/timeflow→P.80` settings **left** and **right**, but with some limited use for `/gtr/timeflow→P.80` settings **up** and **down**.
- Extremely customizable using options.
- To observe node and level settings as far as possible, the dimensions can be set by `/tcb/gtrNodeDimensions` or `/tcb/gtrNodeDimensionsLandscape`. `/tcb/gtrNodeDimensions` is initially set.

```

\begin{genealogypicture}[processing=tcolorbox]
  child{ g{root} p{X}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcolorbox,
  level size=1.2cm,node size=2.5cm,
  box={halign=center,valign=center,size=fbox,arc=2mm,colback=red!20} ]
  child{ g{root} p{This is some longer text.}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcolorbox,
    timeflow=right,
    level size=3cm,level distance=10mm,
    box={halign=center,natural height,size=title,arc=1mm,colback=blue!20} ]
child{ g{root} p{This is some longer text.}
    child{ p{Y} g{A} c{B} c{C} }
        c{D}
        child{ g{E} p{Z} c{F} c{G} c{H} }
    }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcolorbox,
    level size=1.5cm,level distance=5mm,node size=2cm,
    box={halign=center,valign=center,size=small,arc=2mm,colback=green!20}]
%
child{ g{root}
    c[turn=left]{Abc}
    c[turn=upsideup]{Bcd}
    c[turn=right]{Cde}
}
\end{genealogypicture}

```



6.2.3 tcbbox


`/gtr/processing→P.138=tcbbox`

This processing is based on `\tcbbox` of the `tcolorbox` package [4]. Options given to `/gtr/box→P.98` have to be `tcolorbox` options which are used by `\tcbbox`.

The `/gtr/no content interpreter→P.157` is used. The main characteristics of the applied node data processor are:

- For `/gtr/timeflow→P.80` settings `up` and `down`, no observance of `/gtr/node size→P.85` and `/gtr/node size from→P.86`, but full observance of `/gtr/level size→P.84`, if `/tcb/gtrNodeDimensions` is set.
- For `/gtr/timeflow→P.80` settings `left` and `right`, no observance of `/gtr/level size→P.84`. `/gtr/node size→P.85` and `/gtr/node size from→P.86` are both observed, if `/tcb/gtrNodeDimensions` is set.
- If not specified otherwise by options, the content is set as a single line and the box is sized according to its content.
- To observe node and level settings as far as possible, the dimensions can be set by `/tcb/gtrNodeDimensions` or `/tcb/gtrNodeDimensionsLandscape`. `/tcb/gtrNodeDimensions` is initially *not* set, but `/gtr/turn→P.100` will switch dimensions settings on.


```
\begin{genealogypicture}[processing=tcbbox]
  child{ g{root} p{X}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}
```



```

\begin{genealogypicture}[processing=tcbox,
  level size=1cm,
  box={valign=center,size=title,arc=2mm,colback=red!20} ]
child{ g{root} p{This is some longer text.}
  child{ p{Y} g{A} c{B} c{C} }
  c{D}
  child{ g{E} p{Z} c{F} c{G} c{H} }
}
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcbox,
  timeflow=right,
  level size=2cm,level distance=10mm,
  box={size=title,natural height,arc=0mm,colback=blue!20} ]
child{ g{root} p[box={varwidth upper=\gtrNodeMaxWidth}]{This is some longer text.}
  child{ p{Y} g{A} c{B} c{C} }
  c{D}
  child{ g{E} p{Z} c{F} c{G} c{H} }
}
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcbox,
  level size=1.5cm,level distance=5mm,node size=2cm,
  box={halign=center,valign=center,size=small,arc=2mm,colback=green!20}]
%
child{ g[turn=off]{root}
  c[turn=left]{Abc}
  c[turn=upsideup]{Bcd}
  c[turn=right]{Cde}
}
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcbox,
  level size=1.5cm,level distance=5mm,node size=2cm,
  box={halign=center,valign=center,size=small,natural height,
  arc=2mm,colback=green!20}]
%
child{ g{root}
  c[turn=left,box={natural height}]{Abc}
  c[turn=upsideup,box={natural height}]{Bcd}
  c[turn=right,box={natural height}]{Cde}
}
\end{genealogypicture}

```



6.2.4 tcbbox*

`/gtr/processing→ P.138=tcbbox*`

This processing is based on `\tcbbox` of the `tcolorbox` package [4]. Options given to `/gtr/box→ P.98` have to be `tcolorbox` options which are used by `\tcbbox`. This is a variant of Section 6.2.3 on page 146.


The `/gtr/no content interpreter→ P.157` is used. The main characteristics of the applied node data processor are:

- For `/gtr/timeflow→ P.80` settings `up` and `down`, observance of `/gtr/node size→ P.85` (but width may grow beyond) and full observance of `/gtr/level size→ P.84`, if `/tcb/gtrNodeDimensions` is set.
- For `/gtr/timeflow→ P.80` settings `left` and `right`, some observance of `/gtr/level size→ P.84` (but width may grow beyond). `/gtr/node size→ P.85` and `/gtr/node size from→ P.86` are both observed, if `/tcb/gtrNodeDimensions` is set.
- If not specified otherwise by options, the content is set horizontally and vertically centered as a single line.
- To observe node and level settings as far as possible, the dimensions can be set by `/tcb/gtrNodeDimensions` or `/tcb/gtrNodeDimensionsLandscape`. `/tcb/gtrNodeDimensions` is initially set.

```

\begin{genealogypicture}[processing=tcbox*]
  child{ g{root} p{X}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcbox*,
  level size=1cm,
  box={valign=center,size=title,arc=2mm,colback=red!20} ]
  child{ g{root} p{This is some longer text.}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcbox*,
    timeflow=right,
    level size=2cm,level distance=10mm,
    box={size=title,natural height,arc=0mm,colback=blue!20} ]
child{ g{root} p[box={varwidth upper=\gtrNodeMaxWidth}]{This is some longer text.}
    child{ p{Y} g{A} c{B} c{C} }
        c{D}
        child{ g{E} p{Z} c{F} c{G} c{H} }
    }
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tcbox*,
    level size=1.5cm,level distance=5mm,node size=2cm,
    box={halign=center,valign=center,size=small,arc=2mm,colback=green!20}]
%
child{ g[turn=off]{root}
    c[turn=left]{Abc}
    c[turn=upsidedown]{Bcd}
    c[turn=right]{Cde}
}
\end{genealogypicture}

```



6.2.5 tikznode


`/gtr/processing→P.138=tikznode`

This processing is based on `\node` of the `tikz` package [5]. Options given to `/gtr/box→P.98` have to be `tikz` options which are used by `\node`.

The `/gtr/no content interpreter→P.157` is used. The main characteristics of the applied node data processor are:

- No observance of `/gtr/level size→P.84`, `/gtr/node size→P.85`, and `/gtr/node size from→P.86`.
- Not as customizable as other processors, but full `tikz` options.
- This node processing will consume the smallest compilation time.
- To observe node and level settings as far as possible, the dimensions can be set by `/tikz/gtrNodeDimensions` or `/tikz/gtrNodeDimensionsLandscape`. `/tikz/gtrNodeDimensions` is initially *not* set, but `/gtr/turn→P.100` will switch dimensions settings on.


```
\begin{genealogypicture}[processing=tikznode]
  child{ g{root} p{X}
    child{ p{Y} g{A} c{B} c{C} }
    c{D}
    child{ g{E} p{Z} c{F} c{G} c{H} }
  }
\end{genealogypicture}
```



```

\begin{genealogypicture}[processing=tikznode,
  level size=8mm,box={fill=yellow!10}, ]
child{ g{root} p{X}
  child{ p{Y} g{A} c{B} c{C} }
  c{D}
  child{ g{E} p{Z} c{F} c{G} c{H} }
}
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tikznode,
  timeflow=right,
  level size=1cm,level distance=10mm ]
child{ g{root} p{X}
  child{ p{Y} g{A} c{B} c{C} }
  c{D}
  child{ g{E} p{Z} c{F} c{G} c{H} }
}
\end{genealogypicture}


```



```

\begin{genealogypicture}[processing=tikznode,
  level size=1.5cm,level distance=5mm,node size=2cm,
  box={fill=green!20,gtrNodeDimensions}]
%
child{ g{root}
  c[turn=left]{Abc}
  c[turn=upsidedown]{Bcd}
  c[turn=right]{Cde}
}
\end{genealogypicture}

```



6.3 Creating a Customized Non-Interpreting Processor

For most applications, one of the predefined non-interpreting processings with their processors will suffice, see Section 6.2 on page 139.

But using `/gtr/node processor`^{→ P. 138}, also a new node processor can be defined.

```
\gtrset{node processor=\myprocessor}
```

Here, `\myprocessor` is an own macro which has to be defined without parameters. Inside the macro definition, the following can be used.

`\gtrBoxContent`

Contains the (already interpreted or not interpreted) node content.

`\gtrNodeMinWidth`

Contains the current target minimum node width as defined by the various tree settings.

`\gtrNodeMaxWidth`

Contains the current target maximum node width as defined by the various tree settings.

`\gtrNodeMinHeight`

Contains the current target minimum node height as defined by the various tree settings.

`\gtrNodeMaxHeight`


Contains the current target maximum node height as defined by the various tree settings.

`\gtrNodeBoxOptions`

Contains the option settings for the current node. These are the assembled `/gtr/box`^{→ P. 98} settings as comma separated key-value list for the current node.

For demonstration, a simple processor based on the `minipage` environment is constructed:

```
\newcommand{\myprocessor}{%
  \begin{minipage}[c][\gtrNodeMinHeight]{\gtrNodeMinWidth}%
    \begin{center}\gtrBoxContent\end{center}\end{minipage}%
}%
%
\begin{genealogypicture}[node processor=\myprocessor,
  level size=8mm,level distance=10mm,node size=2cm]
%
  child{ g{root}
    c{Abc}
    c{Bcd}
    c{Cde}
  }
\end{genealogypicture}
```



6.4 Content Interpreters

The predefined non-interpreting processings from Section 6.2 on page 139 can easily be adapted to become interpreting, if `/gtr/content interpreter` or `/gtr/content interpreter code`^{→ P. 156} is set. The interpreter changes the node content somehow (see Chapter 7 on page 161 for the main example) and gives the changed content to the chosen `/gtr/node processor`^{→ P. 138}.

`/gtr/content interpreter=<macro>` (no default)

Sets `<macro>` for interpreting the content of a node. This `<macro>` has to take one mandatory parameter (the original box content). It has to define a new parameterless macro `\gtrBoxContent`^{→ P. 154} which should store the content which is given to the current `/gtr/node processor`^{→ P. 138} for further compilation.


```
\gtrset{content interpreter=\myinterpreter}
```

The most important interpreter is realized by database processing, see Chapter 7 on page 161. This option may be used to implement an own kind of database processing which differs from the package implementation.

Another use case is to replace the node content completely by some automated content like numbering the nodes.

```
\newcommand{\myinterpreter}[1]{\def\gtrBoxContent{#1~{(\gtrnodenumber)}}}


\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  content interpreter=\myinterpreter ]
{
  child{
    g{A} p{B}
    child{ p{C} g{D} c{E} c{F} }
    c{G}
  }
}
\end{tikzpicture}
```



`/gtr/content interpreter code={⟨code⟩}` (no default)

Sets ⟨code⟩ for interpreting the content of a node. This ⟨code⟩ can use a parameter #1 (the original box content) and has to define a new parameterless macro `\gtrBoxContent`^{→ P. 154} which should store the content which is given to the current `/gtr/node processor`^{→ P. 138} for further compilation.


```
\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  content interpreter code={\def\gtrBoxContent{#1~{(\gtrnodenumber)}}} ]
{
  child{
    g{A} p{B}
    child{ p{C} g{D} c{E} c{F} }
    c{G}
  }
}
\end{tikzpicture}
```



`/gtr/content interpreter content={⟨code⟩}` (no default)

Sets ⟨code⟩ for interpreting the content of a node. This ⟨code⟩ is the definition for `\gtrBoxContent`^{→ P. 154}. The ⟨code⟩ can use a parameter #1 (the original box content).


```
\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  content interpreter content={#1~{(\gtrnodenumber)}} ]
{
  child{
    g{A} p{B}
    child{ p{C} g{D} c{E} c{F} }
    c{G}
  }
}
\end{tikzpicture}
```




```

\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  content interpreter content={N_{\gtrnodenumber}} ]
{
  child{
    g- p-
    child{ p- g- c- c- c- union{ p- c- } }
    c-
    child{ g- p- c- child{ g- p- c- c- c- c- } }
  }
}
\end{tikzpicture}

```



`/gtr/no content interpreter`

(no value, initially set)

Virtually removes any content interpreter. The node content is given directly to the current `/gtr/processing`^{→P.138} for further compilation. Actually, this defines `\gtrBoxContent`^{→P.154} to contain the original box content.

`/gtr/deletion content interpreter`


(no value, initially set)

Deletes any box content. This leads to empty boxes.

```

\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  deletion content interpreter ]
{
  child{
    g{A} p{B}
    child{ p{C} g{D} c{E} c{F} }
    c{G}
  }
}
\end{tikzpicture}

```



/gtr/database content interpreter

(no value, initially set)

This is the content interpreter for database processing, see Chapter 7 on page 161.


```
% ... make database processing dependend on tcbbox*
processing=tcbbox*,
database content interpreter,
% ...
```

/gtr/id content interpreter

(no value, initially set)

The box content is not only used *as-is* but is also set as `/gtr/id`^{P.92} of the node. This implies that no macro code is used inside the nodes.


```
\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  id content interpreter,
  options for node={A,G}{box={colback=blue!50,colframe=blue}} ]
{
  child{
    g{A} p{B}
    child{ p{C} g{D} c{E} c{F} }
    c{G}
  }
}
\draw[-Latex,blue!75!black,thick]
(A) edge[out=180,in=180] (E)
    edge[out=90,in=90] (B)
(G) edge[out=270,in=0] (F) ;
\end{tikzpicture}
```



`/gtr/content interpreter id and content={\langle id \rangle}{\langle code \rangle}` (no default)

Sets $\langle code \rangle$ for interpreting the content of a node. This $\langle code \rangle$ is the definition for `\gtrBoxContent`^{P. 154}. Also, the $\langle id \rangle$ for the node is set. The $\langle code \rangle$ and $\langle id \rangle$ can use a parameter #1 (the original box content). Note that $\langle id \rangle$ will be fully expanded.

```
\begin{tikzpicture}
\genealogytree[
  template=formal graph,
  content interpreter id and content={n\gtrnodenumber}{N_{\gtrnodenumber}},
  options for node={n1,n7}{box={colback=blue!50,colframe=blue}} ]
{
  child{
    g-p-
    child{ p-g-c-c- }
    c-
  }
}
\draw[-Latex,blue!75!black,thick]
(n1) edge[out=180,in=180] (n5)
      edge[out=90,in=90]   (n2)
(n7) edge[out=270,in=0]   (n6) ;
\end{tikzpicture}
```



7

Database Processing

Database processing is a specialized node data processing, see Chapter 6 on page 137. The node content is interpreted as organized data and some representation of the data will form the visual output.

To switch to database processing, use

```
/gtr/processing→ P.138=database
```

The box content is interpreted as key-value database list. The actual box construction is based on `\tcboxfit` of the `tcolorbox` package [4]. Options given to `/gtr/box→ P.98` have to be `tcolorbox` options which are used by `\tcboxfit`.


The `/gtr/database content interpreter→ P.158` is used in combination with the node data processor described in Section 6.2.1 on page 139.

For a quick example-based overview, see the full samples in Section 7.5 on page 174 which use the data given in Section 7.2 on page 163.

7.1 Database Concept

The general idea of this *database* approach is to separate the data content of a node from the formatting. While this is also a common T_EX/L^AT_EX idea, the following concept goes somewhat further.

The content producer could be a human person directly, but more presumably a machine like a genealogy program. The node content is written as a comma separated key-value list. This list is processed and its content formatted by a database processor. For a quick survey with an example, see Section 7.2 on page 163.



The content is exported by a program or hand written as key-value list. The format of this list is described in Section 7.3 on page 165. This list is processed by an enclosing L^AT_EX document which is created and manipulated by a human. This enclosing document specifies how the content is displayed. This relieves the exporting program from caring about formatting issues and gives full visual control to a human author. The author is relieved from putting down data by hand which presumably is already data-processed with a genealogy program.

Also, the following methods allow to use the same database for different diagrams with possibly different goals and designs.

7.2 Example Settings

This example data is used in the following (also documented in Section 15.2 on page 360).

File «example.database.graph» for the following examples


```
child[id=SmitBowd1742]{
  g[id=SmitChar1722]{
    male,
    name      = {\pref{Charles} \surn{Smith}},
    birth     = {(caAD)1722}{London},
    baptism   = {1722-04-13}{London},
    death+    = {1764-10-12}{}{killed},
    profession = {Copper smith, soldier},
    comment   = {Invented the square wheel},
  }
  p[id=BowdJane1724]{
    female,
    name      = {\pref{Jane} \surn{Bowden}},
    floruit-  = {1724/1802},
    marriage  = {1742-03-02}{London},
    death-    = {/1815}
  }
  c[id=BowdAbra1740]{
    male,
    name      = {\pref{Abraham} \surn{Bowden}},
    birth+    = {1740-01-04}{London}{out of wedlock},
    death     = {1740-02-23}{London}
  }
  c[id=SmitEliz1744]{
    female,
    name      = {\pref{Elizabeth} \nick{Liz} \surn{Smith}},
    birth     = {1744-02-02}{London},
    floruit   = {1780/1805}{New York},
    death     = {1812-04-12}{Boston},
    comment   = {Had a store in Boston},
  }
  c[id=SmitMich1758]{
    male,
    name      = {\pref{Michael} \surn{Smith}},
    birth+    = {1758-03-01}{}{died},
  }
}
```

Note especially the `/gtr/id→P.92` values. They are essential as handle to access a singular node from an importing document without changing the database.

```

\begin{genealogypicture}[
  processing=database,database format=full,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style={solid},
    halign=left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}

```



7.3 Data Keys

/gtr/database/name= $\langle full\ name \rangle$ (no default, initially empty)

This key holds the $\langle full\ name \rangle$ of a person presumably with markup. For customization, the markup should be done with $\backslash pref \rightarrow P.184$, $\backslash surn \rightarrow P.184$, $\backslash nick \rightarrow P.184$ instead of common L^AT_EX font settings.

```
%...  
name = {\pref{Elizabeth} \nick{Liz} \surn{Smith}},  
%...
```

- $\backslash pref \rightarrow P.184$ marks a preferred given name.
- $\backslash nick \rightarrow P.184$ marks a nickname.
- $\backslash surn \rightarrow P.184$ marks a surname.

The saved data is accessible by $\backslash gtrDBname$.

/gtr/database/shortname= $\langle short\ name \rangle$ (no default, initially empty)

This key holds an optional $\langle short\ name \rangle$ of a person presumably with markup. For customization, the markup should be done with $\backslash pref \rightarrow P.184$, $\backslash surn \rightarrow P.184$, $\backslash nick \rightarrow P.184$ instead of common L^AT_EX font settings.

```
%...  
shortname = {\nick{Liz} \surn{Smith}},  
%...
```

The saved data is accessible by $\backslash gtrDBshortname$.

/gtr/database/sex= $\langle sex \rangle$ (no default, initially **neuter**)

This key holds the $\langle sex \rangle$ of a person. Feasible (but unchecked) values are **male** and **female**. **neuter** is an additional feasible default value, if the sex is unknown, e.g. for a stillborn child without further data. The saved data is accessible by $\backslash gtrDBsex$. It is recommended to use the shortcuts below.

```
%...  
sex = female,  
%...
```

/gtr/database/female (style, no value)

Shortcut for **/gtr/database/sex=female**.

/gtr/database/male (style, no value)

Shortcut for **/gtr/database/sex=male**.

/gtr/database/neuter (style, no value)

Shortcut for **/gtr/database/sex=neuter**.

/gtr/database/comment= $\langle text \rangle$ (no default, initially empty)

This key holds some comment $\langle text \rangle$ about a person, e.g. occupation or a very concise life description. The saved data is accessible by $\backslash gtrDBcomment$.

```
%...  
comment = {Had a store in Boston},  
%...
```

`/gtr/database/profession=<text>` (no default, initially empty) N 2017-01-27

This key holds some *<text>* about the profession a person. The saved data is accessible by `\gtrDBprofession`.

```
%...  
profession = {Copper smith, soldier},  
%...
```

`/gtr/database/image=<file name>` (no default, initially empty)

This key holds an image *<file name>* of a person's portrait. The saved data is accessible by `\gtrDBimage`.

```
%...  
image = Marry_Smith_1720.jpg,  
%...
```

`/gtr/database/imageopt={<options>}` (no default, initially empty) N 2018-04-16

This key holds some *<options>* to be applied for including an image with `/gtr/database/image`. These *<options>* should be valid for `\includegraphics`. The saved data is accessible by `\gtrDBimageopt`.

```
%...  
imageopt={viewport=30pt 50pt 150pt 180pt,clip},  
%...
```

`/gtr/database/viewport=<a b c d>` (style, no default) N 2018-04-16

This style is a shortcut for calling `/gtr/database/imageopt` with an `\includegraphics` viewport of *<a b c d>* plus `clip` option. The saved data is accessible by `\gtrDBimageopt`.

```
%...  
viewport=30pt 50pt 150pt 180pt,  
%...
```

`/gtr/database/uuid=<text>` (no default, initially empty)

This key holds an *universally unique identifier* (UUID) *<text>* of a person. In contrast to `/gtr/id`^{P.92}, the UUID should be globally constant. It may be used for interlinking beyond the scope of a genealogy tree diagram. The saved data is accessible by `\gtrDBuuid`.

```
%...  
uuid = 1021aa0c-2508-488c-9760-f9f84b4df1dd,  
%...
```

`/gtr/database/id=<name>` (style, no default) N 2026-05-05

This style is a shortcut for calling `/gtr/id`^{P.92}, i.e. one can set `/gtr/id`^{P.92} using a database key. If `/gtr/id`^{P.92} and `/gtr/database/id` are used both, the *<name>* of `/gtr/database/id` is used as the TikZ node *<name>* only, but the names from both can be used by `/gtr/options for node`^{P.95}.

```
%...  
id = person_a,  
%...
```

/gtr/database/kekule=*<number>* (no default, initially empty)

This key holds the Kekulé number of a person. The saved data is accessible by **\gtrDBkekule**.

```
%...
kekule = 1024,
%...
```

N 2020-06-03 **/gtr/database/relation**=*<relation>* (no default, initially **unrelated**)

This key holds the *<relation>* of a person to a proband. This proband is *not* necessarily the root node of the tree. Feasible (but unchecked) values are

- **ancestor**: direct ancestor of the proband.
- **descendant**: direct descendant of the proband.
- **sibling**: sibling of the proband which is not an ancestor or descendant, i.e. uncle, aunt, nephew, niece of arbitrary degree.
- **unrelated**: nothing of the above.

Adoptions and relations by marriage are not embraced by this key. The saved data is accessible by **\gtrDBrelation**. It is recommended to use the shortcuts below.

```
%...
relation = ancestor,
%...
```

N 2020-06-03 **/gtr/database/ancestor** (style, no value)

Shortcut for **/gtr/database/relation=ancestor**.

N 2020-06-03 **/gtr/database/descendant** (style, no value)

Shortcut for **/gtr/database/relation=descendant**.

N 2020-06-03 **/gtr/database/sibling** (style, no value)

Shortcut for **/gtr/database/relation=sibling**.

N 2020-06-03 **/gtr/database/unrelated** (style, no value)

Shortcut for **/gtr/database/relation=unrelated**.

/gtr/database/relationship=*<text>* (no default, initially empty)

This key holds a relationship *<text>* describing the person. **/gtr/database/relationship** may or may not be consistent with **/gtr/database/relation**. The saved data is accessible by **\gtrDBrelationship**.

```
%...
relationship = Grandfather,
%...
```

N 2020-05-28 **/gtr/database/age**=*<number or text>* (no default, initially empty)

This key holds a *<number or text>* describing the age (at death) of a person. The saved data is accessible by **\gtrDBage**.

```
%...
age = 87,
%...
age = {ca.\,70},
%...
```

`/gtr/database unknown key=<option>` (no default, initially **warn**)

The node data may contain more key-value pairs than needed for the current processing. This option controls how the package should react when detecting unknown keys. Feasible *<option>* values are

- **ignore**: ignore unknown keys,
- **warn**: warn about unknown keys,
- **error**: stop processing at unknown keys,
- **save**: store the value of an unknown key. If a key **dummy** is detected, its value is stored under `/gtr/database/save/dummy`.

The following data keys hold *events*. Every *event* consists of

- a *date*, see Section 7.4 on page 172,
- optionally a *place*
- and sometimes a *modifier*.

The three main events are

- Birth,
- Marriage,
- Death.

The other events may or may not be considered for data formatting.

The saved data for the events is accessible by `\gtrPrintEvent`^{→P.191}, `\gtrPrintDate`^{→P.186}, and `\gtrPrintPlace`^{→P.190}. The existence of data can be checked by `\gtrifdatedefined`^{→P.186} and `\gtrifplacedefined`^{→P.190}.

`/gtr/database/birth={⟨date⟩}{⟨place⟩}` (no default)

This key holds a birth event with given *⟨date⟩* and *⟨place⟩*.

```
%...  
birth = {1744-02-02}{London},  
%...
```

`/gtr/database/birth+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}` (no default)

This key holds a birth event with given *⟨date⟩*, *⟨place⟩*, and a *⟨modifier⟩* to describe the event further. Feasible values for the *⟨modifier⟩* are

- *empty* (normal),
- *out of wedlock*,
- *stillborn*,
- *died*.

```
%...  
birth+ = {1740-01-04}{London}{out of wedlock},  
%...
```

`/gtr/database/birth-=⟨date⟩` (no default)

This key holds a birth event with given *⟨date⟩*.

```
%...  
birth- = {1744-02-02},  
%...
```

`/gtr/database/baptism={⟨date⟩}{⟨place⟩}` (no default)

This key holds a baptism event with given *⟨date⟩* and *⟨place⟩*.

`/gtr/database/baptism+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}` (no default)

Identical to `/gtr/database/baptism` since there is no valid *⟨modifier⟩*.

`/gtr/database/baptism-=⟨date⟩` (no default)

This key holds a baptism event with given *⟨date⟩*.

<code>/gtr/database/engagement={⟨date⟩}{⟨place⟩}</code>	(no default)	
This key holds an engagement event with given $\langle date \rangle$ and $\langle place \rangle$.		
<code>/gtr/database/engagement+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}</code>	(no default)	
Identical to <code>/gtr/database/engagement</code> since there is no valid $\langle modifier \rangle$.		
<code>/gtr/database/engagement-=⟨date⟩</code>	(no default)	
This key holds an engagement event with given $\langle date \rangle$.		
<code>/gtr/database/marriage={⟨date⟩}{⟨place⟩}</code>	(no default)	
This key holds a marriage event with given $\langle date \rangle$ and $\langle place \rangle$.		
<code>/gtr/database/marriage+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}</code>	(no default)	
This key holds a marriage event with given $\langle date \rangle$, $\langle place \rangle$, and a $\langle modifier \rangle$ to describe the event further. Feasible values for the $\langle modifier \rangle$ are		
<ul style="list-style-type: none"> • <i>empty</i> (normal), • <i>other</i>. 		
<code>/gtr/database/marriage-=⟨date⟩</code>	(no default)	
This key holds a marriage event with given $\langle date \rangle$.		
<code>/gtr/database/divorce={⟨date⟩}{⟨place⟩}</code>	(no default)	
This key holds a divorce event with given $\langle date \rangle$ and $\langle place \rangle$.		
<code>/gtr/database/divorce+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}</code>	(no default)	
Identical to <code>/gtr/database/divorce</code> since there is no valid $\langle modifier \rangle$.		
<code>/gtr/database/divorce-=⟨date⟩</code>	(no default)	
This key holds a divorce event with given $\langle date \rangle$.		
<code>/gtr/database/floruit={⟨date⟩}{⟨place⟩}</code>	(no default)	N 2017-07-18
This key holds a floruit event with given $\langle date \rangle$ and $\langle place \rangle$.		
<code>/gtr/database/floruit+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}</code>	(no default)	N 2017-07-18
Identical to <code>/gtr/database/floruit</code> since there is no valid $\langle modifier \rangle$.		
<code>/gtr/database/floruit-=⟨date⟩</code>	(no default)	N 2017-07-18
This key holds a floruit event with given $\langle date \rangle$.		
<code>/gtr/database/death={⟨date⟩}{⟨place⟩}</code>	(no default)	
This key holds a death event with given $\langle date \rangle$ and $\langle place \rangle$.		
<code>/gtr/database/death+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}</code>	(no default)	
This key holds a death event with given $\langle date \rangle$, $\langle place \rangle$, and a $\langle modifier \rangle$ to describe the event further. Feasible values for the $\langle modifier \rangle$ are		
<ul style="list-style-type: none"> • <i>empty</i> (normal), • <i>killed</i>. 		
<code>/gtr/database/death-=⟨date⟩</code>	(no default)	
This key holds a death event with given $\langle date \rangle$.		

`/gtr/database/burial={⟨date⟩}{⟨place⟩}` (no default)

This key holds a burial event with given $\langle date \rangle$ and $\langle place \rangle$.

`/gtr/database/burial+={⟨date⟩}{⟨place⟩}{⟨modifier⟩}` (no default)

This key holds a burial event with given $\langle date \rangle$, $\langle place \rangle$, and a $\langle modifier \rangle$ to describe the event further. Feasible values for the $\langle modifier \rangle$ are

- *empty* (normal),
- *cremated*.

`/gtr/database/burial-=⟨date⟩` (no default)

This key holds a burial event with given $\langle date \rangle$.

Every *event* contains a *date*. If a *date* is unknown for an event like e.g. a birth, a *date range* can be used, see next section. Otherwise, e.g. '?' could be used for an unknown date, or more flexibly, something like an own macro `\nodate` which could be set differently for a specific application, e.g. `\newcommand{\nodate}{?}` or `\newcommand{\nodate}{\unskip}` ...

7.4 Input Format for Dates

A *date* can be given as a *single date* or as a *date range*. A *single date* is specified in the format

(c)yyyy-mm-dd

with calendar *c*, year *yyyy*, month *mm*, and day *dd*. The calendar *c* flag is optional and can be

- **AD**: Anno Domini; this is the default setting, if the calendar flag is omitted. Use this (or nothing) for every 'normal' date.
- **BC**: Before Christ; obviously used for dates before Christ.
- **GR**: Gregorian calendar; use this in situations, where the difference between Gregorian and Julian calendar should be emphasized.
- **JU**: Julian calendar; use this in situations, where the difference between Gregorian and Julian calendar should be emphasized.
- **caAD**: circa, but AD; use this for insecure date settings.
- **caBC**: circa, but BC; use this for insecure date settings.
- **ca**: circa; do not use this directly. The language settings for this will be used automatically, if **caAD** is given and `/gtr/calendar print→ P.188=all but AD` is set.
- *other*: other flags may be used without error. The flag is just noted.

The date format can be shortened to (c)yyyy-mm and (c)yyyy. Since the calendar flag is optional, yyyy-mm-dd, yyyy-mm, and yyyy are also possible.

A *date range* is specified in the format

(c)yyyy-mm-dd/(c)yyyy-mm-dd

Every partial date may be shortened as described above.

Also, /(c)yyyy-mm-dd and (c)yyyy-mm-dd/ are valid to denote open ranges.

Date Examples

Specification	Formatted Dates		
	d.M.yyyy	month d yyyy	dd/mon/yyyy
1875-12-07	7.XII.1875	December 7, 1875	07/Dec/1875
(JU)1642-12-25	25.XII.1642 ^{jul.}	December 25, 1642 ^{jul.}	25/Dec/1642 ^{jul.}
(GR)1599-08	VIII.1599 ^{greg.}	August, 1599 ^{greg.}	Aug/1599 ^{greg.}
1475	1475	1475	1475
(BC)27-01-16	16.I.27 BC	January 16, 27 BC	16/Jan/27 BC
/1690-03	before III.1690	before March, 1690	before Mar/1690
1775-07-15/	after 15.VII.1775	after July 15, 1775	after 15/Jul/1775
1888-05/1889-06-07	V.1888 to 7.VI.1889	May, 1888 to June 7, 1889	May/1888 to 07/Jun/1889
(caAD)1955-02	ca. II.1955	ca. February, 1955	ca. Feb/1955

\gtrParseDate{<name>}{<date>}

Dates are parsed as part of events automatically, see Section 7.3 on page 165. But with **\gtrParseDate**, a <date> can be parsed directly. The parsed data is stored using the given <name> as **\gtrDB<name>cal**, **\gtrDB<name>day**, **\gtrDB<name>month**, **\gtrDB<name>year**, **\gtrDB<name>endcal**, **\gtrDB<name>endday**, **\gtrDB<name>endmonth**, **\gtrDB<name>endyear**.

```
\gtrParseDate{xy}{1875-12-07}
```

The parsed date is

|**\gtrDBxycal**| (**\gtrDBxycal**),

|**\gtrDBxyday**| (**\gtrDBxyday**),

|**\gtrDBxymonth**| (**\gtrDBxymonth**),

|**\gtrDBxyyear**| (**\gtrDBxyyear**).

Formatted date: **\gtrset**{date format=d/M/yyyy}**\gtrPrintDate**{xy}

The parsed date is **\gtrDBxycal** (AD), **\gtrDBxyday** (07), **\gtrDBxymonth** (12), **\gtrDBxyyear** (1875).

Formatted date: 7/XII/1875

7.5 Formatting the Node Data

While the macros and options of the next sections describe how to format a single piece of data, the `/gtr/database format` integrates a collection of these pieces to format the total content of a node.

`/gtr/database format=<format>` (style, no default, initially `medium`)

U 2026-04-30


Selects a predefined `<format>` for selecting and arranging data values. The standard `<format>` designs use `gtrprintlist`^{→P.194} to list events. New `<format>` designs can be added by `\gtrDeclareDatabaseFormat`^{→P.182}. The following sections describe how to customize certain parts of the standard `<format>` designs, e.g. `/gtr/date format`^{→P.186} for changing the date style.

Feasible (standard) `<format>` values are

- **full**: name, birth, baptism, engagement, marriage, divorce, floruit, death, burial, and informations as profession and comment.
- **full marriage above**: identical to **full**, but engagement, marriage, divorce is put above and separated by a `\tcbline`.
- **full marriage below**: identical to **full**, but engagement, marriage, divorce is put below and separated by a `\tcbline`.
- **full no marriage**: identical to **full**, but without engagement, marriage, and divorce.
- **medium**: name, birth (or baptism), marriage (or engagement or divorce), death (or burial), and informations as profession and comment. Floruit is displayed, if there is no birth/baptism or death/burial.
- **medium marriage above**: identical to **medium**, but marriage (or engagement or divorce) is put above and separated by a `\tcbline`.
- **medium marriage below**: identical to **medium**, but marriage (or engagement or divorce) is put below and separated by a `\tcbline`.
- **medium no marriage**: identical to **medium**, but without engagement, marriage, and divorce.
- **short**: name, birth (or baptism), marriage (or engagement or divorce), and death (or burial). Floruit is displayed, if there is no birth/baptism or death/burial.
- **short marriage above**: identical to **short**, but marriage (or engagement or divorce) is put above and separated by a `\tcbline`.
- **short marriage below**: identical to **short**, but marriage (or engagement or divorce) is put below and separated by a `\tcbline`.
- **short no marriage**: identical to **short**, but without engagement, marriage, and divorce.
- **name**: name only.
- **symbol**: symbol only.
- **empty**: nothing.
- **marriage**: only marriage (or engagement or divorce). This format is intended to be used not for nodes, but for edge labels, see `/gtr/label database options`^{→P.219}.


database format=full

```
\begin{genealogypicture}[
  processing=database,database format=full,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=full marriage above

```
\begin{genealogypicture}[
  processing=database,database format=full marriage above,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=full marriage below

```
\begin{genealogypicture}[
  processing=database,database format=full marriage below,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=full no marriage

```
\begin{genealogypicture}[
  processing=database,database format=full no marriage,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=medium

```
\begin{genealogypicture}[
  processing=database,database format=medium,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=medium marriage above

```
\begin{genealogypicture}[
  processing=database,database format=medium marriage above,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=medium marriage below

```
\begin{genealogypicture}[
  processing=database,database format=medium marriage below,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=medium no marriage

```
\begin{genealogypicture}[
  processing=database,database format=medium no marriage,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=short

```
\begin{genealogypicture}[
  processing=database,database format=short,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=short marriage above

```
\begin{genealogypicture}[
  processing=database,database format=short marriage above,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=short marriage below

```
\begin{genealogypicture}[
  processing=database,database format=short marriage below,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=short no marriage

```
\begin{genealogypicture}[
  processing=database,database format=short no marriage,
  node size=3cm,level size=3.2cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=name

```
\begin{genealogypicture}[
  processing=database,database format=name,
  node size=3cm,level size=1cm,
  box={fit basedim=9pt,boxsep=2pt,
    halign=flush center,valign=center,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```




database format=symbol

```
\begin{genealogypicture}[
  processing=database,database format=symbol,
  node size=1cm,level size=1cm,
  box={fit basedim=16pt,boxsep=2pt,
    halign=flush center,valign=center,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```



database format=empty

```
\begin{genealogypicture}[
  processing=database,database format=empty,
  node size=1cm,level size=1cm,
  box={fit basedim=16pt,boxsep=2pt,
    halign=flush center,valign=center,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```



\gtrDeclareDatabaseFormat{<format>}{<option code>}{<content code>}


Declares a new <format> to be used as value for `/gtr/database format`^{→P.174}. The <option code> is used after the data is read and before the box is set. The <content code> is used to fill the box content. It is recommended to start a new <format> name with the letter 'x' to avoid collisions with future standard values.

```
\gtrDeclareDatabaseFormat{xkekule}{%
\ifdefined{\gtrDBkekule}{\gtrset{box={title=\gtrDBkekule}}}%
}%
\gtrPrintName%
\begin{gtreventlist}%
\gtrifdatedefined{birth}{\gtrlistseparator\gtrPrintEvent{birth}}{
\gtrifdatedefined{baptism}{\gtrlistseparator\gtrPrintEvent{baptism}}{}}%
}%
\gtrifdatedefined{death}{\gtrlistseparator\gtrPrintEvent{death}}{
\gtrifdatedefined{burial}{\gtrlistseparator\gtrPrintEvent{burial}}{}}%
}%
\end{gtreventlist}%
\begin{gtrinfo%
\gtrifprofessiondefined{\gtrlistseparator\gtrPrintProfession}{}%
\gtrifcommentdefined{\gtrlistseparator\gtrPrintComment}{}%
\end{gtrinfo%
\gtrifdatedefined{marriage}{\tcblline\begin{gtreventlist}%
\gtrlistseparator\gtrPrintEvent{marriage}\end{gtreventlist}}{}}%
}%
%
\begin{genealogypicture}[
processing=database,database format=xkekule,
node size=3cm,level size=3.2cm,
list separators hang,place text={\newline}{},
box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
center title,fonttitle=\bfseries\normalsize,
halign=flush left,before upper=\parskip1pt,\gtrDBsex } ]
child{
g[id=SmitChar1722]{
male,
kekule = 2,
name = {\pref{Charles} \surn{Smith}},
birth = {1722}{London},
baptism = {1722-04-13}{London},
death+ = {1764-10-12}{killed},
profession = {Copper smith, soldier},
}
p[id=BowdJane1724]{
female,
kekule = 3,
name = {\pref{Jane} \surn{Bowden}},
birth- = {1724},
marriage = {1742-03-02}{London},
death = {1802-07-07}{New York},
}
c[id=BowdAbra1740]{
male,
name = {\pref{Abraham} \surn{Bowden}},
birth+ = {1740-01-04}{London}{out of wedlock},
death = {1740-02-23}{London}
}
c[id=SmitEliz1744]{
female,
kekule = 1,
name = {\pref{Elizabeth} \nick{Liz} \surn{Smith}},
birth = {1744-02-02}{London},
}
```

```

    death   = {1812-04-12}{Boston},
    comment = {Had a store in Boston},
  }
  c[id=SmitMich1758]{
    male,
    name    = {\pref{Michael} \surn{Smith}},
    birth+  = {1758-03-01}{}{died},
  }
}
\end{genealogypicture}

```



N 2019-04-08

\gtrPrintDatabase

Internally used to print the formatted data inside a node or an edge label. This command will not be needed by most users since it is applied automatically. The format of the output is defined by `\gtrDeclareDatabaseFormat`^{→ P. 182}.

```

\gtrset{database/.cd,
  name={\pref{Elizabeth} \nick{Liz} \surn{Smith}},
  birth  = {1744-02-02}{London},
  death  = {1812-04-12}{Boston},
  comment = {Had a store in Boston},
}
%...
\gtrPrintDatabase

```

Elizabeth "Liz" SMITH
 ★ February 2, 1744 in London
 † April 12, 1812 in Boston
Had a store in Boston.

7.6 Formatting Names

`\gtrPrintName`

Used to insert the formatted name. The output format of the name is controlled by `/gtr/name` and other following options.

```
\gtrset{database/.cd,name={\pref{Elizabeth} \nick{Liz} \surn{Smith}}}  
%...  
\gtrPrintName
```

Elizabeth “Liz” SMITH

`\pref{⟨given name⟩}`

Marks a preferred *⟨given name⟩*. May be redefined directly or using `/gtr/pref code`.

`\surn{⟨surname⟩}`

Marks a *⟨surname⟩*. May be redefined directly or using `/gtr/surn code`.

`\nick{⟨nickname⟩}`

Marks a *⟨nickname⟩*. May be redefined directly or using `/gtr/nick code`.

`/gtr/pref code={⟨code⟩}` (no default)

Redefines `\pref` using *⟨code⟩*.

```
\gtrset{database/.cd,name={\pref{Elizabeth} \nick{Liz} \surn{Smith}}}  
\gtrset{pref code={\textcolor{blue}{\bfseries #1}}}  
%...  
\gtrPrintName
```

Elizabeth “Liz” SMITH

`/gtr/surn code={⟨code⟩}` (no default)

Redefines `\surn` using *⟨code⟩*.

```
\gtrset{database/.cd,name={\pref{Elizabeth} \nick{Liz} \surn{Smith}}}  
\gtrset{surn code={\textcolor{blue}{\bfseries #1}}}  
%...  
\gtrPrintName
```

Elizabeth “Liz” **Smith**

`/gtr/nick code={⟨code⟩}` (no default)

Redefines `\nick` using *⟨code⟩*.

```
\gtrset{database/.cd,name={\pref{Elizabeth} \nick{Liz} \surn{Smith}}}  
\gtrset{nick code={\textcolor{blue}{\bfseries #1}}}  
%...  
\gtrPrintName
```

Elizabeth **Liz** SMITH

`/gtr/name=full|short` (no default, initially full)

Controls, if `\gtrPrintName` should preferably use the **full** version (`/gtr/database/name`^{→ P. 165}) or the **short** version (`/gtr/database/shortname`^{→ P. 165}) of a name. If the preferred version is not available, the other version is used.

`/gtr/name font={⟨code⟩}` (no default)

Sets the font (and/or color) for `\gtrPrintName`^{→ P. 184}.

```
\gtrset{database/.cd,name={\pref{Elizabeth} \nick{Liz} \surn{Smith}}}
\gtrset{name font=\fontfamily{ptm}\selectfont\color{green!50!black}}
%...
\gtrPrintName
```

Elizabeth “Liz” SMITH

`/gtr/empty name text={⟨text⟩}` (no default, initially ??)

Sets the text to be print by `\gtrPrintName`^{→ P. 184}, if `/gtr/database/name`^{→ P. 165} and `/gtr/database/shortname`^{→ P. 165} were not set.

```
\gtrPrintName

\gtrset{empty name text={N.N.}}
\gtrPrintName
```

??
N.N.

`/gtr/name code={⟨code⟩}` (no default)

Defines `⟨code⟩` to be executed by `\gtrPrintName`^{→ P. 184}. Use this, if `/gtr/name`^{→ P. 184} and `/gtr/name font` are not flexible enough.

```
\gtrset{database/.cd,name={\pref{Elizabeth} \nick{Liz} \surn{Smith}},female}
\gtrset{name code={\gtrPrintSex~\gtrDBname}}
%...
\gtrPrintName
```

♀ *Elizabeth “Liz” SMITH*

7.7 Formatting Dates

`\gtrPrintDate{⟨name⟩}`

Used to insert a formatted date referred by `⟨name⟩`. This `⟨name⟩` is an event name like *birth*, see Section 7.3 on page 165, or any other name used by `\gtrParseDate`^{→P.173}. The output format of the date is controlled by `/gtr/date format` and other following options.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
%...
The birth was \gtrPrintDate{birth}.
The death was \gtrPrintDate{death}.
```

The birth was February 9, 1354. The death was ??.

`\gtrifdatedefined{⟨name⟩}{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩`, if a date with the given `⟨name⟩` is defined, and to `⟨false⟩` otherwise.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
%...
\gtrifdatedefined{birth}{The birth was \gtrPrintDate{birth}.}{}
\gtrifdatedefined{death}{The death was \gtrPrintDate{death}.}{}

```

The birth was February 9, 1354.

`/gtr/date format={⟨format⟩}`

(no default, initially **typical**)

[U 2017-12-07](#)

This option controls how day, month, and year of a date are formatted when using `\gtrPrintDate`. This setting is *not* `/gtr/language`^{→P.247} dependent, but month names are. One exception to this rule is

- **typical** *A typical format for the language, here: February 9, 1354*

Further feasible `⟨format⟩` values are

- `dd.mm.yyyy` 09.02.1354
- `d.m.yyyy` 9.2.1354
- `d.M.yyyy` 9.II.1354
- `d.month yyyy` 9. February 1354
- `dd.mon.yyyy` 09. Feb. 1354
- `d.mon.yyyy` 9. Feb. 1354
- `dd mon.yyyy` 09 Feb. 1354
- `d mon.yyyy` 9 Feb. 1354
- `dd/mm/yyyy` 09/02/1354
- `d/m/yyyy` 9/2/1354
- `d/m yyyy` 9/2 1354
- `d/M/yyyy` 9/II/1354
- `dd/month/yyyy` 09/February/1354
- `d/month/yyyy` 9/February/1354
- `dd/mon/yyyy` 09/Feb/1354
- `d/mon/yyyy` 9/Feb/1354
- `dd/mm yyyy` 09/02 1354
- `dd mm yyyy` 09 02 1354
- `d M yyyy` 9 II 1354
- `d month yyyy` 9 February 1354
- `dd mon yyyy` 09 Feb 1354
- `d mon yyyy` 9 Feb 1354
- `dd-mm-yyyy` 09-02-1354

• d-m-yyyy	9-2-1354
• d-M-yyyy	9-II-1354
• dd-month-yyyy	09-February-1354
• d-month-yyyy	9-February-1354
• dd-mon-yyyy	09-Feb-1354
• d-mon-yyyy	9-Feb-1354
• ddmonyyyy	09Feb1354
• yyyy.mm.dd	1354.02.09
• yyyy.m.d	1354.2.9
• yyyy.m.d.	1354. 2. 9.
• yyyy.M.d.	1354. II. 9.
• yyyy.month d.	1354. February 9.
• yyyy.mon.d.	1354. Feb. 9.
• yyyy/mm/dd	1354/02/09
• yyyy/m/d	1354/2/9
• yyyy d/m	1354 9/2
• yyyy mm dd	1354 02 09
• yyyy month d	1354 February 9
• yyyy mon dd	1354 Feb 09
• yyyy-mm-dd	1354-02-09
• yyyy-mon-dd	1354-Feb-09
• yyyy-mon-d	1354-Feb-9
• yyyymondd	1354Feb09
• yyyymmdd	13540209
• mm.dd.yyyy	02.09.1354
• m.d.yyyy	2.9.1354
• mm/dd/yyyy	02/09/1354
• m/d/yyyy	2/9/1354
• mm-dd-yyyy	02-09-1354
• m-d-yyyy	2-9-1354
• month d yyyy	February 9, 1354
• mon.d yyyy	Feb. 9, 1354
• mon d yyyy	Feb 9, 1354
• yyyy	1354

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
\gtrset{date format=month d yyyy}
%...
The birth was \gtrPrintDate{birth}.
```

The birth was February 9, 1354.

`/gtr/date code={⟨code⟩}` (no default)

Defines `⟨code⟩` to be executed by `\gtrPrintDate`^{→ P. 186}. Use this, if `/gtr/date format`^{→ P. 186} is not flexible enough.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
\gtrset{date code={%
  \ifcsdef{#1month}{%
    \ifcsdef{#1day}{\csuse{#1day}}{%
      (\csuse{#1month})%
    }{%
      \csuse{#1year}%
    }%
  }%
}%...
The birth was \gtrPrintDate{birth}.
```

The birth was 09(02)1354.

`/gtr/calendar text for=⟨calendar⟩ is {⟨prefix⟩}{⟨postfix⟩}` (no default)

Defines a `⟨prefix⟩` and a `⟨postfix⟩` text for a `⟨calendar⟩`. This setting is `/gtr/language`^{→ P. 247} dependent for known calendars. This option also allows to set up new `⟨calendar⟩` entries.

```
\gtrset{database/.cd,birth={(AUC)2107-02-09}{Rome}}
\gtrset{calendar text for=AUC is {}{ a.u.c.}}
%...
The birth was \gtrPrintDate{birth}.
```

The birth was February 9, 2107 a.u.c..

`/gtr/calendar print={⟨option⟩}` (no default, initially `all` but `AD`)

Defines, if the calendar setting is used for formatting. Feasible `⟨option⟩` values are

- `all`: all calendar settings, including `AD`.
- `none`: no calendar settings.
- `all but AD`: all calendar settings, but excluding `AD`.

```
\gtrset{database/.cd,birth={(BC)63-09-23}{Rome},death={(AD)14-08-19}{Nola}}
%...
Augustus was born \gtrPrintDate{birth} and died \gtrPrintDate{death}.
\par\gtrset{calendar print=none}
Augustus was born \gtrPrintDate{birth} and died \gtrPrintDate{death}.
\par\gtrset{calendar print=all}
Augustus was born \gtrPrintDate{birth} and died \gtrPrintDate{death}.
```

Augustus was born September 23, 63 BC and died August 19, 14.

Augustus was born September 23, 63 and died August 19, 14.

Augustus was born September 23, 63 BC and died AD August 19, 14.

U 2015-06-16 `/gtr/date range full={⟨pre⟩}{⟨mid⟩}{⟨app⟩}` (no default, initially `{ }{ to }{ }`)

If the date is a *date range* with a start date and an end date, the `⟨pre⟩`, `⟨mid⟩`, and `⟨app⟩` texts are placed appropriately. This setting is `/gtr/language`^{→ P. 247} dependent.

```
\gtrset{database/.cd,birth={1354-02-09/1355-07-20}{Rome}}
\gtrset{date range full={between }{ and }{ }}
%...
The birth was \gtrPrintDate{birth}.
```

The birth was between February 9, 1354 and July 20, 1355.

U 2020-07-22 `/gtr/date range before={⟨pre⟩}{⟨app⟩}` (no default, initially `{before }{ }`)

If the date is a *date range* an end date, but without start date, the `⟨pre⟩` and `⟨app⟩` texts are placed around the end date. This setting is `/gtr/language`^{→ P. 247} dependent.

```
\gtrset{database/.cd,birth={/1355-07-20}{Rome}}
\gtrset{date range before={\textless\,}{ }}
%...
The birth was \gtrPrintDate{birth}.
```

The birth was < July 20, 1355.

U 2020-07-22 `/gtr/date range after={⟨pre⟩}{⟨app⟩}` (no default, initially `{after }{ }`)

If the date is a *date range* a start date, but without end date, the `⟨pre⟩` and `⟨app⟩` texts are placed around the start date. This setting is `/gtr/language`^{→ P. 247} dependent.

```
\gtrset{database/.cd,birth={1354-02-09/}{Rome}}
\gtrset{date range after={\textgreater\,}{ }}
%...
The birth was \gtrPrintDate{birth}.
```

The birth was > February 9, 1354.

U 2015-06-16 `/gtr/date range separator={⟨text⟩}` (style, default `--`, initially unset)

Sets the same separator *text* for `/gtr/date range full`, `/gtr/date range before`, `/gtr/date range after`. Use this for shortened range printing.

```
\gtrset{database/.cd,birth={1354-02-09/}{Rome}}
\gtrset{date range separator={--}}
%...
The birth was \gtrPrintDate{birth}.
```

The birth was February 9, 1354--.

7.8 Formatting Places

`\gtrPrintPlace{⟨name⟩}`

Used to insert a formatted place referred by `⟨name⟩`. This `⟨name⟩` is an event name like *birth*, see Section 7.3 on page 165. The output format of the place is controlled by `/gtr/place text`.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
%...
The birth was \gtrPrintDate{birth} \gtrPrintPlace{birth}.
```

The birth was February 9, 1354 in Rome.

`\gtrifplacedefined{⟨name⟩}{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩`, if a place with the given `⟨name⟩` is defined, and to `⟨false⟩` otherwise.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
%...
The birth was \gtrPrintDate{birth}%
\gtrifplacedefined{birth}{ \gtrPrintPlace{birth}}{ }.
```

The birth was February 9, 1354 in Rome.

`/gtr/place text={⟨pre⟩}{⟨app⟩}` (no default, initially `{in }{ }`) [U 2020-07-22](#)

The `⟨pre⟩` and `⟨app⟩` texts are placed around the place text. This setting is `/gtr/language`^{→ P. 247} dependent.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
\gtrset{place text={({}){}}
%...
The birth was \gtrPrintDate{birth}%
\gtrifplacedefined{birth}{ \gtrPrintPlace{birth}}{ }.
```

The birth was February 9, 1354 (Rome).

7.9 Formatting Events

`\gtrPrintEvent{⟨name⟩}`

Used to insert a formatted event referred by `⟨name⟩`. This `⟨name⟩` is an event name like *birth*, see Section 7.3 on page 165. The output format of the event is controlled by `/gtr/event text`^{→ P. 192}, `\gtrPrintEventPrefix`, `\gtrPrintDate`^{→ P. 186}, and `\gtrPrintPlace`^{→ P. 190}.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
%...
\gtrPrintEvent{birth}
```

★ February 9, 1354 in Rome

`\gtrifeventdefined{⟨name⟩}{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩`, if an event with the given `⟨name⟩` is defined, and to `⟨false⟩` otherwise. This is an alias for `\gtrifdatedefined`^{→ P. 186}.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
%...
\gtrifeventdefined{birth}{\gtrPrintEvent{birth}}{}
```

★ February 9, 1354 in Rome

N 2026-04-30

`\gtrifnativitydefined{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩` if at least one of the events `/gtr/database/birth`^{→ P. 169} or `/gtr/database/baptism`^{→ P. 169} is defined; otherwise, it expands to `⟨false⟩`.

N 2026-04-30

`\gtrifwedlockdefined{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩` if at least one of the events `/gtr/database/marriage`^{→ P. 170}, `/gtr/database/engagement`^{→ P. 170}, or `/gtr/database/divorce`^{→ P. 170} is defined; otherwise, it expands to `⟨false⟩`.

N 2026-04-30

`\gtrifdeceaseddefined{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩` if at least one of the events `/gtr/database/death`^{→ P. 170} or `/gtr/database/burial`^{→ P. 171} is defined; otherwise, it expands to `⟨false⟩`.

`\gtrPrintEventPrefix{⟨name⟩}`

Used to insert an event prefix like a symbol. The prefix depends upon the `⟨name⟩` of the event and upon an optional modifier. The output format of the prefix is controlled by the following options with the `/gtr/event prefix` path.

```
Birth: \gtrPrintEventPrefix{birth}
\par\gtrset{/gtr/event prefix/birth=(b)}
Birth: \gtrPrintEventPrefix{birth}
```

Birth: ★

Birth: (b)

`/gtr/event prefix/birth=⟨text⟩` (no default, initially `\gtrsymBorn`^{→ P. 239})

Prefix `⟨text⟩` for a normal birth.

`/gtr/event prefix/birth/out of wedlock=⟨text⟩` (no default, initially `\gtrsymBornoutofwedlock`^{→ P. 239})

Prefix `⟨text⟩` for a birth out of wedlock.

`/gtr/event prefix/birth/stillborn=<text>` (no default, initially `\gtrsymStillborn`^{→ P. 239})

Prefix *<text>* for a birth of a stillborn child.

`/gtr/event prefix/birth/died=<text>` (no default, initially `\gtrsymDiedonbirthday`^{→ P. 239})

Prefix *<text>* for a birth if a child who died on birthday.

`/gtr/event prefix/baptism=<text>` (no default, initially `\gtrsymBaptized`^{→ P. 239})

Prefix *<text>* for a baptism.

`/gtr/event prefix/engagement=<text>` (no default, initially `\gtrsymEngaged`^{→ P. 240})

Prefix *<text>* for an engagement.

`/gtr/event prefix/marriage=<text>` (no default, initially `\gtrsymMarried`^{→ P. 240})

Prefix *<text>* for a normal marriage.

`/gtr/event prefix/marriage/other=<text>` (no default, initially `\gtrsymPartnership`^{→ P. 240})

Prefix *<text>* for another partnership.

`/gtr/event prefix/divorce=<text>` (no default, initially `\gtrsymDivorced`^{→ P. 240})

Prefix *<text>* for a divorce.

`/gtr/event prefix/floruit=<text>` (no default, initially `\gtrsymFloruit`^{→ P. 241})

Prefix *<text>* for a floruit event.

N 2017-07-18

`/gtr/event prefix/death=<text>` (no default, initially `\gtrsymDied`^{→ P. 240})

Prefix *<text>* for a normal death.

`/gtr/event prefix/death/killed=<text>` (no default, initially `\gtrsymKilled`^{→ P. 240})

Prefix *<text>* for a death in war.

`/gtr/event prefix/burial=<text>` (no default, initially `\gtrsymBuried`^{→ P. 241})

Prefix *<text>* for a normal burial.

`/gtr/event prefix/burial/cremated=<text>` (no default, initially `\gtrsymFuneralurn`^{→ P. 241})

Prefix *<text>* for a cremation.

`/gtr/event format={<format>}` (no default, initially d.M.yyyy)

This option controls how events are formatted when using `\gtrPrintEvent`^{→ P. 191}.

Feasible *<format>* values are

- `prefix date place` ★ February 9, 1354 in Rome
- `prefix date` ★ February 9, 1354
- `date` February 9, 1354

`/gtr/event text={<pre>}{<sep date>}{<sep place>}{<app>}` (no default, initially `{ }{~}{ }{ }`)

The four text pieces are placed inside `\gtrPrintEvent`^{→ P. 191} as follows:

*<pre>*prefix*<sep date>*date*<sep place>*place*<app>*

This setting is *not* `/gtr/language`^{→ P. 247} dependent.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
\gtrset{event text={[]{: }{ }{[]}}
%...
\gtrPrintEvent{birth}
```

[★: February 9, 1354 in Rome]

`/gtr/event code={<code>}` (no default)

Defines $\langle code \rangle$ to be executed by `\gtrPrintEvent`^{P.191}. Use this, if `/gtr/event format` and `/gtr/event text` are not flexible enough.

```
\gtrset{database/.cd,birth={1354-02-09}{Rome}}
\gtrset{event code={%
  \gtrPrintEventPrefix{#1}
  \gtrifplacedefined{#1}{(\gtrPrintPlace{#1}) }{}%
  \gtrPrintDate{#1}%
}}
%...
\gtrPrintEvent{birth}
```

★ (in Rome) February 9, 1354

7.10 Formatting Lists of Events

```
\begin{gtrprintlist}{\langle first \rangle}{\langle middle \rangle}{\langle last \rangle}{\langle empty \rangle}
  \langle environment content \rangle
\end{gtrprintlist}
```

This environment is intended for automatically generated content. Inside this environment, a macro `\gtrlistseparator` is defined.

- `\gtrlistseparator` expands to $\langle first \rangle$, when it is called the first time.
- `\gtrlistseparator` expands to $\langle middle \rangle$, when it is called later.
- $\langle last \rangle$ is used at the end of the environment, if `\gtrlistseparator` was called at least once.
- $\langle empty \rangle$ is used at the end of the environment, if `\gtrlistseparator` was never called.

```
\begin{gtrprintlist}{\unskip}%
  {\unskip,\ }{\unskip.}{\unskip}
  \gtrlistseparator One
  \gtrlistseparator Two
  \gtrlistseparator Three
  \gtrlistseparator Four
\end{gtrprintlist}
```

One, Two, Three, Four.

```
\begin{gtrprintlist}%
  {\begin{itemize}\item}{\item}%
  {\end{itemize}}{\unskip}
  \gtrlistseparator One
  \gtrlistseparator Two
  \gtrlistseparator Three
  \gtrlistseparator Four
\end{gtrprintlist}
```

- One
- Two
- Three
- Four

```
\begin{gtreventlist}
  \langle environment content \rangle
\end{gtreventlist}
```

This is a `gtrprintlist` environment with parameters specified by `/gtr/list separators` ^{→ P. 195}. This environment is used internally by most `/gtr/database format` ^{→ P. 174} settings to print event lists.

```
\gtrset{list separators=
  {\unskip}{\unskip,\ }%
  {\unskip.}{\unskip}}


\begin{gtreventlist}%
  \gtrlistseparator One
  \gtrlistseparator Two
  \gtrlistseparator Three
  \gtrlistseparator Four
\end{gtreventlist}
```

One, Two, Three, Four.

`/gtr/list separators={\langle first\rangle}{\langle middle\rangle}{\langle last\rangle}{\langle empty\rangle}` (no default, initially `{\par}{\par}{\par}{\par}`)

Defines `gtreventlist`^{→ P. 194} as a `gtrprintlist`^{→ P. 194} with the given parameters. This is used to list events.


```
\begin{genealogypicture}[
  processing=database,database format=full,
  node size=4cm,level size=2cm,
  name code={\gtrDBname.},
  list separators={ }, { }, { }, { },
  info separators={ }, { }, { }, { },
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```



`/gtr/list separators hang=\langle length\rangle` (style, default `\tcbfidim`)

Defines `gtreventlist`^{→ P. 194} as a `gtrprintlist`^{→ P. 194} where the items hang with `\langle length\rangle` after the first line.

```
\begin{genealogypicture}[
  processing=database,database format=full,
  node size=3cm,level size=3.2cm,
  list separators hang=2mm,place text={\newline}{ },
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```



7.11 Formatting Comments

`\gtrPrintComment`

Used to insert the formatted comment. May be redefined directly or using `/gtr/comment code`.

```
\gtrset{database/.cd,comment={Had a store in Boston}}  
%...  
\gtrPrintComment
```

Had a store in Boston

`\gtrifcommentdefined{<true>}{<false>}`

Expands to `<true>`, if a comment is defined, and to `<false>` otherwise.

```
\gtrset{database/.cd,comment={Had a store in Boston}}  
%...  
\gtrifcommentdefined{\gtrPrintComment}{}  

```

Had a store in Boston

`/gtr/comment code={<code>}` (no default, initially `{\itshape\gtrDBcomment}`)

Redefines `\gtrPrintComment` using `<code>`.

```
\gtrset{database/.cd,comment={Had a store in Boston}}  
\gtrset{comment code={(\gtrDBcomment)}}  
%...  
\gtrPrintComment
```

(Had a store in Boston)

7.12 Formatting Professions

N 2017-01-27

`\gtrPrintProfession`

Used to insert the formatted profession. May be redefined directly or using `/gtr/profession code`.

```
\gtrset{database/.cd,profession={Copper smith, soldier}}
%...
```

```
\gtrPrintProfession
```

Copper smith, soldier

N 2017-01-27

`\gtrifprofessiondefined{<true>}{<false>}`

Expands to `<true>`, if a profession is defined, and to `<false>` otherwise.

```
\gtrset{database/.cd,profession={Copper smith, soldier}}
%...
```

```
\gtrifprofessiondefined{\gtrPrintProfession}{}
```

Copper smith, soldier

N 2017-01-27

`/gtr/profession code={<code>}` (no default, initially `{\itshape\gtrDBprofession}`)

Redefines `\gtrPrintProfession` using `<code>`.

```
\gtrset{database/.cd,profession={Copper smith, soldier}}
\gtrset{profession code={(\gtrDBprofession)}}
%...
```

```
\gtrPrintProfession
```

(Copper smith, soldier)

7.13 Formatting Lists of Information

```
\begin{gtrinfo list}
  <environment content>
\end{gtrinfo list}
```

N 2017-01-27


This is a `gtrprintlist`^{→P.194} environment with parameters specified by `/gtr/info separators`. This environment is used internally by most `/gtr/database format`^{→P.174} settings to print information lists consisting of `/gtr/database/profession`^{→P.166} and `/gtr/database/comment`^{→P.165} entries.

```
/gtr/info separators={\langle first\rangle}{\langle middle\rangle}{\langle last\rangle}{\langle empty\rangle}
                                                                (no default,
                                                                initially {\par}{. }{\.}{})
```

N 2017-01-27

Defines `gtrinfo list` as a `gtrprintlist`^{→P.194} with the given parameters. This is used to list informations.

```
\begin{genealogypicture}[
  processing=database,database format=full,
  node size=4cm,level size=4cm,
  info separators={\tcbline}{\tcbline}{\tcbline},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=left,before upper=\parskip1pt,\gtrDBsex } ]
  input{example.database.graph}
\end{genealogypicture}
```



7.14 Formatting Sex

`\gtrPrintSex`

Used to insert a symbolic sign for the sex.

```
\gtrset{database/.cd,sex=female}  
%...  
\gtrPrintSex
```

♀

`\gtriffemale{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩`, if `\gtrDBsex` holds `female`, and to `⟨false⟩` otherwise.

`\gtrifmale{⟨true⟩}{⟨false⟩}`

Expands to `⟨true⟩`, if `\gtrDBsex` holds `male`, and to `⟨false⟩` otherwise.

Note that the content of the data key `/gtr/database/sex→P.165` is accessible by `\gtrDBsex`. Since `/tcb/female→P.101`, `/tcb/male→P.101`, `/tcb/neuter→P.101`, and `/gtr/female→P.101`, `/gtr/male→P.101`, `/gtr/neuter→P.101` are defined, `\gtrDBsex` can be used directly as a formatting option, see Section 7.2 on page 163 and the examples in Section 7.5 on page 174.

7.15 Formatting Images

`\gtrifimagedefined{<true>}{<false>}`

Expands to `<true>`, if an image is defined, and to `<false>` otherwise.

```
\gtrset{database/.cd,image=Carl_Friedrich_Gauss.jpg}
%...
\gtrifimagedefined{\includegraphics[width=3cm]{\gtrDBImage}}{no image}
```



`\gtrincludeDBImage{<options>}`

Includes a database image with the given `<options>`. These options are added to any options given by `/gtr/database/imageopt` ^{→ P. 166}.

```
\gtrset{database/.cd,image=Carl_Friedrich_Gauss.jpg}
%...
\gtrifimagedefined{\gtrincludeDBImage{width=3cm}}{no image}
```



`/tcb/if image defined={<true>}{<false>}` (style, no value)

Sets `<true>` `tcolorbox` options, if an image is defined, and sets `<false>` `tcolorbox` options otherwise. This key is intended to be used inside `/gtr/box` ^{→ P. 98} constructs.

```
\gtrset{
  options for node={mynode}{
    box={if image defined={watermark graphics=\gtrDBImage}{}}
  }
}
%...
```

N 2018-04-16
U 2023-03-06

U 2020-07-22

/tcb/image prefix= $\{\langle text \rangle\}$

(no default, initially empty)

Add a prefix $\langle text \rangle$ to every image file name.

```
\gtrset{image prefix=picturedir/}  
\gtrset{database/.cd,image=mytest.jpg}  
%...  
Picture file: \texttt{\gtrDBimage}
```

Picture file: picturedir/mytest.jpg

N 2018-04-16
U 2023-03-06

/tikz/fill zoom DBimage

(no value, initially unset)

Fills the current path with the current database image. The image is zoomed such that it fits inside the path area. Typically, some parts of the path area will stay unfilled.

```
\gtrset{database/.cd,image=Carl_Friedrich_Gauss.jpg,viewport=30pt 50pt 150pt 180pt}  
%...  
\gtrifimagedefined{%  
  \tikz\path[draw=red,fill zoom DBimage] (0,0) rectangle (2,3);  
  \tikz\path[draw=red,fill zoom DBimage] (0,0) rectangle (3,3);  
  \tikz\path[draw=red,fill zoom DBimage] (0,0) rectangle (3,2);  
}{no image}
```



N 2018-04-16
U 2023-03-06

/tikz/fill overzoom DBimage

(no value, initially unset)

Fills the current path with the current database image. The image is zoomed such that the path area fills the image.

```
\gtrset{database/.cd,image=Carl_Friedrich_Gauss.jpg,viewport=30pt 50pt 150pt 180pt}  
%...  
\gtrifimagedefined{%  
  \tikz\path[draw=red,fill overzoom DBimage] (0,0) rectangle (2,3);  
  \tikz\path[draw=red,fill overzoom DBimage] (0,0) rectangle (3,3);  
  \tikz\path[draw=red,fill overzoom DBimage] (0,0) rectangle (3,2);  
}{no image}
```



7.16 Formatting Ages

`\gtrPrintAge`

N 2020-05-28

Used to insert the formatted age. May be redefined directly or using `/gtr/age code`.

```
\gtrset{database/.cd,age={87}}  
%...  
\gtrPrintAge
```

```
[87]
```

`\gtrifagedefined{<true>}{<false>}`

N 2020-05-28

Expands to `<true>`, if an age is defined, and to `<false>` otherwise.

```
\gtrset{database/.cd,age={87}}  
%...  
\gtrifagedefined{\gtrPrintAge}{}  

```

```
[87]
```

`/gtr/age code={<code>}`

(no default, initially `[\gtrDBage]`)

N 2020-05-28

Redefines `\gtrPrintAge` using `<code>`.

```
\gtrset{database/.cd,age={87}}  
\gtrset{age code={died aged-\gtrDBage}}  
%...  
\gtrPrintAge
```

```
died aged 87
```

8

Edges

Edges are drawn between all nodes of a *family*. For the auto-layout algorithm, the edges are opaque. Space is reserved for the edges according to the various distance settings for nodes, but the edge dimensions themselves are not considered during layout. The following settings and options influence the visual appearance of the edges.


Edges are drawn in two steps: a `/gtr/edge/background`^{P.214} followed by a `/gtr/edge/foreground`^{P.213}. After all edges are drawn, the nodes are drawn (possibly over the edges).

8.1 Edge Settings

`/gtr/edges={⟨edge options⟩}` (style, no default, initially perpendicular)

Defines the *⟨edge options⟩* for drawing the edges between the nodes of a family. Normally, an edge is drawn with a `/gtr/edge/background`^{P.214} graph and a `/gtr/edge/foreground`^{P.213} graph to allow visual separation of superposed edges. This setting may be given globally, as option of `\genealogytree`^{P.55} or locally wrapped by `/gtr/family`^{P.105}. Also see Section 5.1.2 on page 79.


```
\begin{tikzpicture}
\genealogytree[template=signpost,edges=rounded]
{
  parent[id=SmithDoe]{
    g[id=Arth2008,male]{Arthur\\gtrsymBorn\\,2008}
    c[id=Bert2010,female]{Berta\\gtrsymBorn\\,2010}
    c[id=Char2014,male]{Charles\\gtrsymBorn\\,2014}
    parent[id=Smith,family={edges={foreground={blue!50,line width=2mm}}}]{
      g[id=John1980,male]{John Smith\\gtrsymBorn\\,1980}
      p[id=GpSm1949,male]{Grandpa Smith\\gtrsymBorn\\,1949}
      p[id=GmSm1952,female]{Grandma Smith\\gtrsymBorn\\,1952}
    }
    p[id=Jane1982,female]{Jane Doe\\gtrsymBorn\\,1982}
  }
}
\end{tikzpicture}
```



`/gtr/family edges={\langle edge options \rangle}` (style, no default)

This is a shortcut for embedding `/gtr/edges`^{→ P. 204} into `/gtr/family`^{→ P. 105}.


```
\begin{tikzpicture}
\genealogytree[template=signpost,edges={rounded}]
{
  parent[id=SmithDoe]{
    g[id=Arth2008,male]{Arthur\\gtrsymBorn\\,2008}
    c[id=Bert2010,female]{Berta\\gtrsymBorn\\,2010}
    c[id=Char2014,male]{Charles\\gtrsymBorn\\,2014}
    parent[id=Smith,family edges={foreground=red!50,line width=2mm}]{
      g[id=John1980,male]{John Smith\\gtrsymBorn\\,1980}
      p[id=GpSm1949,male]{Grandpa Smith\\gtrsymBorn\\,1949}
      p[id=GmSm1952,female]{Grandma Smith\\gtrsymBorn\\,1952}
    }
    p[id=Jane1982,female]{Jane Doe\\gtrsymBorn\\,1982}
  }
}
\end{tikzpicture}
```



`/gtr/edges for family={\family}}{\edge options}` (style, no default)

This is a shortcut for embedding `/gtr/edges`^{→ P. 204} into `/gtr/options for family`^{→ P. 104}.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges for family={SmithDoe}{
foreground={red,line width=2pt},background={yellow,line width=3pt}},
]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/subtree edges={\edge options}` (style, no default)

This is a shortcut for embedding `/gtr/edges`^{→ P. 204} into `/gtr/subtree`^{→ P. 108}.


`/gtr/edges for subtree={\family}}{\edge options}` (style, no default)

This is a shortcut for embedding `/gtr/edges`^{→ P. 204} into `/gtr/options for subtree`^{→ P. 107}.

`\gtredgeset{⟨options⟩}`

Sets $\langle options \rangle$ for the `/gtr/edge` key subtree. Mainly, this macro is intended to easily set up styles for edges.

```
\begin{tikzpicture}
\gtredgeset{myedges/.style={rounded=6pt,
  foreground={blue!50!black},background={blue!20!white}}}
%...
\genealogytree[template=signpost,edges=myedges]
{input{example.option.graph}}
\end{tikzpicture}
```



`/tikz/genealogytree edges scope`

(style, initially empty)

This style is used to scope the drawing of the edges. It may be redefined e.g. to draw edges on a certain layer.

```
% draw edges on the background layer
\usetikzlibrary{backgrounds}
\tikzset{genealogytree edges scope/.style={on background layer}}
```

Note that edges are drawn before nodes. Typically, the setting to draw on the background layer is not necessary. If two genealogy trees are merged, this additional setting may be useful.


8.2 Edge Types

`/gtr/edge/perpendicular`

(no value, initially set)

The edges are drawn in a perpendicular style.

```
\begin{tikzpicture}
\genealogytree[template=signpost,edges={perpendicular}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/rounded= $\langle length \rangle$`

(default 6pt)

The edges are drawn in a perpendicular but rounded style. The $\langle length \rangle$ describes the size of the rounding.

```
\begin{tikzpicture}
\genealogytree[template=signpost,edges={rounded=6pt}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/swing= $\langle length \rangle$`

(default 12pt)

The edges are drawn in a swinging style. The $\langle length \rangle$ describes the control parameter of the underlying curved path.

```
\begin{tikzpicture}
\genealogytree[template=signpost,edges={swing=12pt}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/mesh={⟨options⟩}`

(default empty)


The edges are drawn meshed between parents and children. The `⟨options⟩` are TikZ to `path` options.

- For a family without children or without parents, no edge will be drawn.
- For a family with at least two parents and at least two children, a mesh is drawn. The intended use case is for families with just one parent or just one child, i.e. for ordinary trees.

```
\begin{tikzpicture}
\genealogytree[template=signpost,edges=mesh]
{input{example.option.graph}}
\end{tikzpicture}
```



```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges={mesh={%
to path={.. controls +(270:0.5) and +(90:0.5) .. (\tikztotarget)}}
}]{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/edge/custom={\langle down\rangle}{\langle up\rangle}{\langle left\rangle}{\langle right\rangle}` (no default)


The edges are drawn in a custom style. This option takes four mandatory parameters $\langle down \rangle$, $\langle up \rangle$, $\langle left \rangle$, and $\langle right \rangle$, each of which is a macro. The $\langle down \rangle$ macro is used to draw edges for `/gtr/timeflow→P.80=down`, etc.

Every macro has to take four mandatory parameters:

1. An etoolbox $\langle listmacro \rangle$ which contains the list of anchor positions for the parents.
2. An etoolbox $\langle listmacro \rangle$ which contains the list of anchor positions for the children.
3. A TikZ node name which denotes the family core (center).
4. A TikZ style which should be applied to draw the edges.

```
\newcommand{\myedgedraw}[4]{%
  % parents (#1):
  \ifdef{#1}{%
    \renewcommand*\do{[1]{
      \draw[#4] (##1)--(##3);
      \path[draw=green!50!black,fill=green!30] (##1) circle (3pt);}
    \dolistloop{#1}%
  }{}%
  % children (#2):
  \ifdef{#2}{%
    \renewcommand*\do{[1]{
      \draw[#4] (##1)--(##3);
      \path[draw=yellow!50!black,fill=yellow!50] (##1) circle (3pt);}
    \dolistloop{#2}%
  }{}%
  % family core (#3):
  \path[draw=purple!50!black,fill=purple!50] (##3) circle (3pt);
}

\begin{tikzpicture}
\genealogytree[template=signpost,
  box={enhanced jigsaw,opacityback=0.75},
  edges={
    custom={\myedgedraw}{\myedgedraw}{\myedgedraw}{\myedgedraw},
  ]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/none`

(no value)

This is a special `/gtr/edge/custom`^{P. 211} style which simply draws nothing. May be used for just this purpose or to replace automatic edge drawing by manual edge drawing.

```
\usetikzlibrary{quotes}
\begin{tikzpicture}
\genealogytree[template=signpost,edges=none]
{input{example.option.graph}}

\draw[-Latex,green!50!black,thick]
  (GpSm1949) edge[out=270,in=270,"husband"] (GmSm1952)
  edge[out=225,in=180,"father"] (John1980)
  edge[out=180,in=180,"grandfather"] (Arth2008)
  (Bert2010) edge[out=90,in=270,"daughter"] (Jane1982)
  (Jane1982) edge[out=90,in=270,"daughter"] (GmDo1956);
\end{tikzpicture}
```




8.3 Edge Parameters


`/gtr/edge/foreground={\tikz options}` (style, no default)

Defines the foreground `\tikz options` for drawing the edges between the nodes.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges={foreground={line width=2pt,red,dashed,line cap=butt},no background}]
{input{example.option.graph}}
\end{tikzpicture}
```



```
\begin{tikzpicture}
\genealogytree[template=signpost,level distance=1.7cm,
edges={rounded,foreground={line width=2pt,red,Circle-LaTeX,shorten <=-4pt},
background={line width=3pt,yellow}}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/no foreground` (style, no value)

Removes the `/gtr/edge/foreground` edges.

`/gtr/edge/background={\tikz options}` (style, no default)

Defines the background `\tikz options` for drawing the edges between the nodes.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges={foreground={line width=0.5pt,red},
background={line width=2pt,yellow}}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/no background` (style, no value)

Removes the `/gtr/edge/background` edges.

`/gtr/edge/anchoring=periphery|center` (no default, initially periphery)

Defines anchoring points for the edges. Feasible value are `periphery` and `center`.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges={swing=5mm,anchoring=center,
foreground={line width=4mm},background={line width=5mm}}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/hide single leg=true|false` (default `true`, initially `true`)

If set to `true`, the orphan leg of a family with just one member is hidden.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges={hide single leg}]
{
parent{ g{Orphan} }
}
\end{tikzpicture}
```




```
\begin{tikzpicture}
\genealogytree[template=signpost,
edges={hide single leg=false}]
{
parent{ g{Orphan} }
}
\end{tikzpicture}
```



`/gtr/edge/xshift=<length>` (no default, in initially `0pt`)

Shifts the edge core position horizontally by `<length>`.

```
\begin{tikzpicture}
\genealogytree[template=signpost,edges={swing,xshift=5mm}]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/edge/yshift=<length>`

(no default, in initially `0pt`)

Shifts the edge core position vertically by `<length>`.

```
\begin{tikzpicture}
\genealogytree[template=signpost,edges={swing,yshift=-3mm}]
{input{example.option.graph}}
\end{tikzpicture}
```




8.4 Edge Labels


`/gtr/label={⟨text⟩}` (style, no default)

Adds a label *⟨text⟩* to the current family. This is realized by a TikZ node with `/gtr/label options`. The current family is determined by a surrounding `/gtr/family`^{P.105} or `/gtr/options for family`^{P.104}.

```
\begin{genealogypicture}[template=signpost,
  label options={fill=white,node font=\footnotesize},
  options for family={SmithDoe}{label={\gtrsymMarried-2006}} ]
  input{example.option.graph}
\end{genealogypicture}
```



```
\begin{genealogypicture}[template=signpost,
  label options={fill=green!20,node font=\footnotesize},
  label={\gtrsymMarried} ]
  input{example.option.graph}
\end{genealogypicture}
```



`/gtr/label options={⟨options⟩}` (style, no default)


Sets TikZ node *⟨options⟩* to be used for `/gtr/label`. See `/gtr/label` for an example.

`/gtr/family label={\langle text \rangle}`

(style, no default)

Shortcut for using `/gtr/label`^{P. 217} inside `/gtr/family`^{P. 105}.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
  label options={fill=white,node font=\footnotesize},
]{
  parent[id=SmithDoe,family label={\gtrsymMarried~2006}]{
    g[id=Arth2008,male]{Arthur\\gtrsymBorn\,2008}
    c[id=Bert2010,female]{Berta\\gtrsymBorn\,2010}
    c[id=Char2014,male]{Charles\\gtrsymBorn\,2014}
    parent[id=Smith,family label={\gtrsymMarried~1976}]{
      g[id=John1980,male]{John Smith\\gtrsymBorn\,1980}
      p[id=GpSm1949,male]{Grandpa Smith\\gtrsymBorn\,1949}
      p[id=GmSm1952,female]{Grandma Smith\\gtrsymBorn\,1952}
    }
  }
  parent[id=Doe,family label={\gtrsymMarried~1980}]{
    g[id=Jane1982,female]{Jane Doe\\gtrsymBorn\,1982}
    c[id=Harr1987,male]{Uncle Harry\\gtrsymBorn\,1987}
    p[id=GpDo1955,male]{Grandpa Doe\\gtrsymBorn\,1955}
    p[id=GmDo1956,female]{Grandma Doe\\gtrsymBorn\,1956}
  }
}
\end{tikzpicture}
```



`/gtr/subtree label={\langle text \rangle}`

(style, no default)

Shortcut for using `/gtr/label`^{P. 217} inside `/gtr/subtree`^{P. 108}.

8.5 Edge Labels Database

Analog to database processing for nodes, see Chapter 7 on page 161, the edge labels can be formatted by database style entries.

The database content for edge labels has to be given inside the option list for a **parent** or **child** using `/gtr/family database`.

`/gtr/family database={⟨data keys⟩}` (no default, initially empty)

Sets `⟨data keys⟩` for the edge labeling of the current family. For `⟨data keys⟩`, any setting from Section 7.3 on page 165 can be used, but only marriage information or similar may be reasonable.

```
%...
child[id=SmitBowd1742,family database={marriage={1742-03-02}{London}}]{
%...
```

`/gtr/label database options={⟨options⟩}` (no default)

The `⟨options⟩` settings define how the `/gtr/family database` values are used to create label content. The default operations are `/gtr/use family database` and `/gtr/database format`^{P.174}=**marriage**. Note that setting `/gtr/database format`^{P.174} inside `/gtr/label database options` does only change the format for edge labels, but not for nodes.

```
%...
label database options={
  database format=marriage, % that is the default value
  place text={({})}        % changed only for labels
},
%...
```

`/gtr/ignore family database` (no value)

If set, then all `/gtr/family database` values are simply ignored. This has to be used inside `/gtr/label database options` to have an effect.

```
%...
label database options={ignore family database},
%...
```


`/gtr/use family database` (no value)

If set, then all `/gtr/family database` values are processed to generate label content. This has to be used inside `/gtr/label database options` to have an effect.

```

\begin{genealogypicture}[
  processing=database,database format=medium no marriage,
  node size=3cm,level size=3.2cm,level distance=1cm,
  list separators hang,place text={\newline}{},
  box={fit basedim=9pt,boxsep=2pt,segmentation style=solid,
    halign=left,before upper=\parskip1pt,\gtrDBsex },
  label database options={place text={({})}},
  label options={fill=white,node font=\footnotesize,inner sep=0.5mm,draw=green!30!black},
]
child[id=SmitBowd1742,family database={marriage={1742-03-02}{London}}]{
  g[id=SmitChar1722]{
    male,
    name      = {\pref{Charles} \surn{Smith}},
    birth     = {(caAD)1722}{London},
    baptism   = {1722-04-13}{London},
    death+    = {1764-10-12}{killed},
    comment   = {Copper smith, soldier},
  }
  p[id=BowdJane1724]{
    female,
    name      = {\pref{Jane} \surn{Bowden}},
    birth-    = {(caAD)1724},
    death     = {1802-07-07}{New York},
  }
  c[id=BowdAbra1740]{
    male,
    name      = {\pref{Abraham} \surn{Bowden}},
    birth+    = {1740-01-04}{London}{out of wedlock},
    death     = {1740-02-23}{London}
  }
  c[id=SmitEliz1744]{
    female,
    name      = {\pref{Elizabeth} \nick{Liz} \surn{Smith}},
    birth     = {1744-02-02}{London},
    death     = {1812-04-12}{Boston},
    comment   = {Had a store in Boston},
  }
  c[id=SmitMich1758]{
    male,
    name      = {\pref{Michael} \surn{Smith}},
    birth+    = {1758-03-01}{died},
  }
}
\end{genealogypicture}

```




8.6 Adding and Removing Nodes from Edge Drawing

`/gtr/add child=<child> to <family>` (style, no default)

Connect a node of an existing graph as *<child>* to a *<family>* of the current graph. The auto-layout algorithm is not aware of this addition.

```
\begin{tikzpicture}[scale=0.9,transform shape]
\gtrset{template=signpost}
\genealogytree[
  edges={foreground={red!50!blue,line width=2pt},
    background={red!50!blue!15!white,line width=3pt}},
  options for node={GmDo1956}{box={colback=red!30!white}} ]
{input{example.option.graph}}

\genealogytree[
  edges={foreground={green!50!blue,line width=2pt},
    background={green!50!blue!15!white,line width=3pt}},
  box={colback=green!30!white},
  adjust node=PhDo1982 right of Harr1987 distance 3mm,
  add child=GmDo1956 to GreatDoe ]
{
  child[id=GreatDoe,pivot shift=1.7cm]{
    g[id=GgpDo1910,male]{Great-Grandpa Doe\\gtrsymBorn\,1910}
    p[id=GgmDo1918,female]{Great-Grandma Doe\\gtrsymBorn\,1918}
    child{
      g[id=JaDo1957,male]{Jack Doe\\gtrsymBorn\,1957}
      p[id=MaJo1960,female]{Mary Jones\\gtrsymBorn\,1960}
      child{
        g[id=PhDo1982,male]{Phil Doe\\gtrsymBorn\,1982}
        p[id=SyPo1982,female]{Sybil Porter\\gtrsymBorn\,1982}
        c[id=Will2005,male]{Will\\gtrsymBorn\,2005}
        c[id=Xave2005,male]{Xaver\\gtrsymBorn\,2005}
        c[id=Zeb2010,male]{Zeb\\gtrsymBorn\,2010}
      }
      c[id=AnDo1984,female]{Anne Doe\\gtrsymBorn\,1984}
    }
  }
}
\end{tikzpicture}
```




`/gtr/add parent=<parent> to <family>` (style, no default)

Connect a node of an existing graph as *<parent>* to a *<family>* of the current graph. The auto-layout algorithm is not aware of this addition.

```
\begin{tikzpicture}
\gtrset{template=signpost}
\genealogytree[
  edges={foreground={red!50!blue,line width=2pt},
    background={red!50!blue!15!white,line width=3pt}},
  options for node={Harr1987}{distance=1.6cm,box={colback=red!30!white}} ]
{input{example.option.graph}}


\genealogytree[
  edges={foreground={green!50!blue,line width=2pt},
    background={green!50!blue!15!white,line width=3pt}},
  box={colback=green!30!white},
  adjust node=JimJ1944 right of GmDo1956 distance 3mm,
  add parent=Harr1987 to DoeJones ]
{
  parent[id=DoeJones,pivot shift=-1.4cm]{
    g[id=Deir2012,female]{Deirdre\\gtrsymBorn\,2012}
    parent[id=Jones]{
      g[id=Mary1988,female]{Aunt Mary\\gtrsymBorn\,1988}
      p[id=JimJ1944,male]{Jim Jones\\gtrsymBorn\,1944}
      p[id=Jenn1949,female]{Jenny Jones\\gtrsymBorn\,1949}
    }
  }
}
\end{tikzpicture}
```



An alternative approach to `/gtr/add child→P.221` and `/gtr/add parent→P.222` is to draw the interconnecting node twice (the first one could be drawn as `/gtr/phantom*→P.127`). The second instance is drawn over the first instance using `/gtr/set position→P.111`. Both instances need to have different `/gtr/id→P.92` values. Note that both parts of the graph can still be overlapping and may have to be adjusted manually, since the auto-layout algorithms handles each `\genealogytree→P.55` separately. The second tree gets an `/gtr/id prefix→P.94` of 2: to address the second Uncle Harry by 2:Harr1987.

```
\begin{tikzpicture}
\gtrset{template=signpost}
\genealogytree[
  edges={foreground={red!50!blue,line width=2pt},
    background={red!50!blue!15!white,line width=3pt}},
]
{input{example.option.graph}}


\genealogytree[id prefix=2:,
  edges={foreground={green!50!blue,line width=2pt},
    background={green!50!blue!15!white,line width=3pt}},
  box={colback=green!30!white},
  set position=2:Harr1987 at Harr1987,
]
{
  parent[id=DoeJones]{
    g[id=Deir2012,female]{Deirdre\\gtrsymBorn\,2012}
    p[id=Harr1987,male,box={colback=red!30!white}]{Uncle Harry\\gtrsymBorn\,1987}
    parent[id=Jones]{
      g[id=Mary1988,female,distance=1.4cm]{Aunt Mary\\gtrsymBorn\,1988}
      p[id=JimJ1944,male]{Jim Jones\\gtrsymBorn\,1944}
      p[id=Jenn1949,female]{Jenny Jones\\gtrsymBorn\,1949}
    }
  }
}
\end{tikzpicture}
```



`/gtr/remove child=<child> from <family>` (style, no default)

Removes a node as *<child>* from a *<family>* of the current graph. The auto-layout algorithm is not aware of this removal.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for node={Jane1982}{pivot=child},% make Jane the pivot child
remove child=Harr1987 from Doe,% remove Harry
extra edges prepend for family=% add Harry again with dots
{Doe}{GmDo1956}{Harr1987}{foreground={dotted,line cap=round},
no background}
]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/remove parent=<parent> from <family>` (style, no default)

Removes a node as *<parent>* from a *<family>* of the current graph. The auto-layout algorithm is not aware of this removal.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
remove parent=GpSm1949 from Smith ]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/disconnect=<value>` (default `both`, initially unset)


Using this option inside node options disconnects the current node from the edges of the current graph. Using this option elsewhere may cause unwanted side effects. The auto-layout algorithm is not aware of this removal. Depending of the given *<value>*, the node is disconnected as parent or child or both.

Feasible values are

- `child`: disconnect the node as child of a family.
- `parent`: disconnect the node as parent of a family. Note that a `g` node is only removed from its primary family, but not from connected `union` families.
- `both`: disconnect the node as child and as parent.

`/gtr/remove child`^{P.224} and `/gtr/remove parent`^{P.224} allow more precise control, but `/gtr/disconnect` needs no `/gtr/id`^{P.92} values.

```
\begin{tikzpicture}
\genealogytree[template=formal graph]
{
  parent{
    g{A}
    c{B}
    c[disconnect,box={colback=blue!10}]{C}
    parent{
      g[disconnect,box={colback=red!10}]{D}
      p{F}
      p{G}
    }
    parent{
      g{E}
      p[disconnect,box={colback=green!10}]{H}
      p{I}
    }
  }
}
\end{tikzpicture}
```




8.7 Extra Edges

`/gtr/extra edges={⟨parents⟩}{⟨children⟩}{⟨edge options⟩}` (style, no default)

Appends an extra set of edges to the current family. The edges are drawn between the given *⟨parents⟩* list and the given *⟨children⟩* list using the *⟨edge options⟩*. Note that parents and children are defined by their `/gtr/id`^{P.92} values. They do not necessarily have to be *real* members of the current family. The current family is given by a surrounding `/gtr/family`^{P.105} or `/gtr/options for family`^{P.104}.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for family={SmithDoe}{extra edges={Jane1982}{Arth2008,Char2014}{
foreground={red,line width=2pt,-Latex},background={yellow,line width=3pt}}},
]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/family extra edges={⟨parents⟩}{⟨childs⟩}{⟨edge options⟩}` (style, no default)

This is a shortcut for embedding `/gtr/extra edges` into `/gtr/family`^{P.105}.

`/gtr/extra edges for family={⟨family⟩}{⟨parents⟩}{⟨childs⟩}{⟨edge options⟩}` (style, no default)

This is a shortcut for embedding `/gtr/extra edges`^{→ P.226} into `/gtr/options for family`^{→ P.104}.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
  extra edges for family={SmithDoe}{Jane1982}{Arth2008,Char2014}{
    foreground={red,line width=2pt,-Latex},background={yellow,line width=3pt}},
]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/extra edges for families={⟨family list⟩}{⟨edge options⟩}` (style, no default)

This allows to set `/gtr/extra edges for family` for multiple families. Therefore, the `⟨family list⟩` is a comma separated list of entries of type `x={⟨family⟩}{⟨parents⟩}{⟨children⟩}`


```
\begin{tikzpicture}
\genealogytree[template=signpost,
  extra edges for families={x={Doe}{GmDo1956}{Jane1982},
    x={SmithDoe}{Jane1982}{Arth2008,Char2014}}{
    foreground={red,line width=2pt,-Latex},background={yellow,line width=3pt}},
]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/extra edges prepend={⟨parents⟩}{⟨children⟩}{⟨edge options⟩}` (style, no default)

Appends an extra set of edges to the current family. The edges are drawn between the given `⟨parents⟩` list and the given `⟨children⟩` list using the `⟨edge options⟩`. This is identical to `/gtr/extra edges`^{P. 226}, but the drawing lies under the normal edges.

```
\begin{tikzpicture}
\genealogytree[template=signpost,
options for family={SmithDoe}{extra edges prepend={Jane1982}{Arth2008}{
foreground={red!25!yellow,line width=5pt},no background}},
]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/family extra edges prepend={⟨parents⟩}{⟨children⟩}{⟨edge options⟩}` (style, no default)

This is a shortcut for embedding `/gtr/extra edges prepend` into `/gtr/family`^{P. 105}.

`/gtr/extra edges prepend for family={⟨family⟩}{⟨parents⟩}{⟨children⟩}{⟨edge options⟩}` (style, no default)

This is a shortcut for embedding `/gtr/extra edges prepend`^{P.228} into `/gtr/options for family`^{P.104}.


```
\begin{tikzpicture}
\genealogytree[template=signpost,
  extra edges prepend for family={SmithDoe}{Jane1982}{Arth2008}{
    foreground={red!25!yellow,line width=5pt},no background},
]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/extra edges prepend for families={⟨family list⟩}{⟨edge options⟩}` (style, no default)

This allows to set `/gtr/extra edges prepend for family` for multiple families. Therefore, the `⟨family list⟩` is a comma separated list of entries of type `x={⟨family⟩}{⟨parents⟩}{⟨children⟩}`

```
\begin{tikzpicture}
\genealogytree[template=signpost,
  extra edges prepend for families={x={Doe}{GmDo1956}{Jane1982},
    x={SmithDoe}{Jane1982}{Arth2008}}{
    foreground={red!25!yellow,line width=5pt},no background}
]
{input{example.option.graph}}
\end{tikzpicture}
```



This style is used to scope the drawing of extra edges. It may be redefined e.g. to draw edges on a certain layer. This scope is embedded into the general scope of `/tikz/genealogytree edges scope`^{→ P. 207}.


```
% draw extra edges on the background layer
\usetikzlibrary{backgrounds}
\tikzset{genealogytree extra edges scope/.style={on background layer}}
```

Note that changing the drawing layer for extra edges applies to all extra edges, but does not change the drawing layer for *normal* edges. Therefore, *all* extra edges would be drawn behind *normal* edges, if the example above is used.

8.8 Edge Shifting


Typically, the edge core position of a family is located on half the way between the parents and the children. But, this is true only, if no **union** constructs are used, where a man or woman has two or more relationships with or without children. For e.g. two relationships, the edge core positions are located on one-third and on two-thirds of the way between the parents and the children. This edge shift is computed automatically.

```
\begin{genealogypicture}[template=signpost]
  child{
    p{Husband1}
    g{Wife} c{Child1} c{Child2}
    union{ p{Husband2} c{Child3} c{Child4} c{Child5} c{Child6} }
  }
\end{genealogypicture}
```



Depending on the situation, the edges may cross or not.


```
\begin{genealogypicture}[template=signpost]
  child{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c{Child4}
    union{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```



The automatic shift does not prevent edge crossing, but ensures to a certain degree that one edge does not hide another edge.

Nodes could be shifted inside their level (here horizontally) to influence the edge drawing, see `/gtr/pivot→P.97`, `/gtr/pivot shift→P.106`, `/gtr/distance→P.96`, etc.

```
\begin{genealogypicture}[template=signpost]
  child{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c[pivot]{Child4}
    union{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```



In the following, options for manual edge shifting to avoid edge crossings are described.


`/gtr/edges shift=<length>`

(style, no default)

N 2017-12-08

Shifts the edge core position by `<length>` towards the parents. In contrast to `/gtr/edge/xshift→P.215` and `/gtr/edge/yshift→P.216`, the `/gtr/timeflow→P.80` is automatically respected. Also note that this is a `/gtr/family edges→P.205` option, i.e. it can be applied directly inside the option list of a family.


```
\begin{genealogypicture}[template=signpost]
  child[edges shift=-3mm]{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c{Child4}
    union[edges shift=3mm]{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```



N 2017-12-08 `/gtr/edges up by=<number> of <parts>` (style, no default)

Shifts the edge core position by fraction $\langle number \rangle / \langle parts \rangle$ of the `/gtr/level distance`^{→P.83} towards the parents. This is a style which uses `/gtr/edges shift`^{→P.232}.

```
\begin{genealogypicture}[template=signpost]
  child[edges down by=2 of 4]{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c{Child4}
    union[edges up by=1 of 4]{ p{Husband2} }
    union[edges up by=1 of 4]{ p{Husband3} }
  }
\end{genealogypicture}
```




N 2017-12-08 `/gtr/edges down by=<number> of <parts>` (style, no default)

Shifts the edge core position by fraction $\langle number \rangle / \langle parts \rangle$ of the `/gtr/level distance`^{→P.83} towards the children. This is a style which uses `/gtr/edges shift`^{→P.232}.

N 2017-12-08 `/gtr/edges up` (no value)

Shifts the edge core position by one third of the `/gtr/level distance`^{→P.83} towards the parents. This is a special case of `/gtr/edges up by` usable for two relationships.

```
\begin{genealogypicture}[template=signpost]
  child[edges down]{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c{Child4}
    union[edges up]{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```



N 2017-12-08 `/gtr/edges down` (no value)

Shifts the edge core position by one third of the `/gtr/level distance`^{→P.83} towards the children. This is a special case of `/gtr/edges up by` usable for two relationships.

The following options can only be applied globally for a graph or the whole document. They cannot be applied locally to influence just one family.


`/gtr/reset edge level shift`

(no value, initially set)

N 2017-12-08

This sets the default algorithm for the automatic level shift. The first relationship is closest to the parents while the last relationship is closest to the children.

```
\begin{genealogypicture}[template=signpost,reset edge level shift]
  child{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c[pivot]{Child4}
    union{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```




`/gtr/switch edge level shift`

(no value, initially set)

N 2017-12-08


This switches the algorithm for the automatic level shift. The first relationship is closest to the children while the last relationship is closest to the parents.

```
\begin{genealogypicture}[template=signpost,switch edge level shift]
  child{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c[pivot]{Child4}
    union{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```



Sets all edge core positions to be on half the way between the parents and the children. Note that edge overlapping has to be prevented *manually* for all families. Use this option only, if you are really sure about that.

```
\begin{genealogypicture}[template=signpost,nullify edge level shift]
  child{
    p{Husband1}
    g{Wife} c{Child1} c{Child2} c{Child3} c[pivot]{Child4}
    union{ p{Husband2} c{Child5} }
  }
\end{genealogypicture}
```



9

Genealogy Symbols

9.1 Symbol Color Settings

If the genealogy symbols are only needed in black color, there is nothing special to consider. Currently, the symbols are drawn as pictures and saved in boxes for efficiency. If different colors are needed, the symbols have to be redrawn. The named color `gtrsymbol` holds the (current) symbol color.

9.1.1 Global Color Settings

In the preamble, the color of all genealogy symbols can be set by redefining the color `gtrsymbol`. For example, if all symbols should be created in blue, one can use:

```
% ...  
\colorlet{gtrsymbol}{blue}  
% ...  
\begin{document}  
% ...  
\end{document}
```

Note that this setting has to be given inside the preamble *after* the package is loaded and *before* `\begin{document}`.

9.1.2 Local Color Settings

If symbols with a color different from the global symbol color should be used inside the document, one of the following commands can be used.

`\gtrSymbolsSetCreate{<color>}`

Recreates all symbols for the current T_EX group with the given <color>. The named color `gtrsymbol` will also be set to <color>. Use this macro, if it is expected that many symbols of this color will be used inside the current T_EX group.

```
\gtrsymBorn\,14.XI.1475
{
  \gtrSymbolsSetCreate{red}
  \gtrsymMarried\,22.II.1502,
  \gtrsymDied\,8.X.1553,
}
\gtrsymBuried\,10.X.1553
```

★ 14.XI.1475 ♂ 22.II.1502, † 8.X.1553, ☠ 10.X.1553

`\gtrSymbolsSetCreateSelected{<color>}{<list>}`

[U 2020-07-27](#)

Recreates all symbols from the given comma separated <list> for the current T_EX group with the given <color>. The named color `gtrsymbol` will also be set to <color>. The <list> contains the base names of the selected symbols, e.g. Born for `\gtrsymBorn`^{→ P. 239}. Symbols which are not present in this list, will keep their old color. Use this macro, if it is expected that many symbols of this color will be used inside the current T_EX group.

```
\gtrSymbolsSetCreateSelected{blue}{Male}
\gtrSymbolsSetCreateSelected{red}{Female}
\gtrSymbolsSetCreateSelected{yellow!50!black}{Born,Died}

\gtrsymBorn, \gtrsymMale, \gtrsymFemale, \gtrsymNeuter, \gtrsymDied.
```

★, ♂, ♀, ♀, †.

`\gtrSymbolsSetDraw{<color>}`

Inside the current T_EX group, every symbol is drawn with the given <color> when it is used. It is drawn again, if it is used again. The named color `gtrsymbol` will also be set to <color>. Use this macro, if it is expected that only few symbols of this color will be used inside the current T_EX group or if colors constantly change.

```
\gtrsymBorn\,14.XI.1475
{
  \gtrSymbolsSetDraw{red}
  \gtrsymMarried\,22.II.1502,
  \gtrSymbolsSetDraw{blue}
  \gtrsymDied\,8.X.1553,
}
\gtrsymBuried\,10.X.1553
```

★ 14.XI.1475 ♂ 22.II.1502, † 8.X.1553, ☠ 10.X.1553

9.2 List of Symbols

`\gtrsymBorn` ★

Birth / born (Unicode U+2A).



Johann Maier `\gtrsymBorn\`,14.XI.1475

Johann Maier ★ 14.XI.1475

`\gtrsymBornoutofwedlock` (★)

Born out of wedlock / illegitimate.



Johann Maier `\gtrsymBornoutofwedlock\`,14.XI.1475

Johann Maier (★) 14.XI.1475

`\gtrsymStillborn` †★

Stillborn.



`\textit{Anonymus}` Maier `\gtrsymStillborn\`,14.XI.1475

Anonymus Maier †★ 14.XI.1475

`\gtrsymDiedonbirthday` ★†

Died on the birthday.



Johann Maier `\gtrsymDiedonbirthday\`,14.XI.1475

Johann Maier ★† 14.XI.1475

`\gtrsymBaptized` ≈

Baptism / baptized (Unicode U+2248).




Johann Maier `\gtrsymBaptized\`,14.XI.1475

Johann Maier ≈ 14.XI.1475

\gtrsymEngaged ○

Engagement / engaged (Unicode U+26AC).



Johann Maier **\gtrsymEngaged**\,14.XI.1475

Johann Maier ○ 14.XI.1475

\gtrsymMarried ∞

Marriage / married (Unicode U+26AD).



Johann Maier **\gtrsymMarried**\,14.XI.1475

Johann Maier ∞ 14.XI.1475

\gtrsymDivorced ○∅

Divorce / divorced (Unicode U+26AE).




Johann Maier **\gtrsymDivorced**\,14.XI.1475

Johann Maier ○∅ 14.XI.1475

\gtrsymPartnership ○—○

Partnership / unmarried (Unicode U+26AF).



Johann Maier **\gtrsymPartnership**\,14.XI.1475

Johann Maier ○—○ 14.XI.1475

\gtrsymDied †

Death / died (Unicode U+2020, U+271D).



Johann Maier **\gtrsymDied**\,14.XI.1475

Johann Maier † 14.XI.1475

\gtrsymKilled ✖

Killed in action / fallen (Unicode U+2694).



Johann Maier \gtrsymKilled\,14.XI.1475

Johann Maier ✕ 14.XI.1475

\gtrsymBuried ☩

Burial / buried (Unicode U+26B0).



Johann Maier \gtrsymBuried\,14.XI.1475

Johann Maier ☩ 14.XI.1475

\gtrsymFuneralurn ☩

Funeral urn / cremated (Unicode U+26B1).



Johann Maier \gtrsymFuneralurn\,14.XI.1475

Johann Maier ☩ 14.XI.1475

N 2017-07-18

\gtrsymFloruit ❀

Floruit / flourished.



Johann Maier \gtrsymFloruit\,1475--1503

Johann Maier ❀ 1475–1503

\gtrsymFemale ♀

Female (Unicode U+2640).



Maria Maier \gtrsymFemale

Maria Maier ♀

\gtrsymMale ♂

Male (Unicode U+2642).




Johann Maier \gtrsymMale

Johann Maier ♂

`\gtrsymNeuter` ♀

Neuter / Unknown sex (Unicode U+26B2).



`\textit{Anonymus}` Maier `\gtrsymNeuter`

Anonymus Maier ♀

9.3 Legend to Symbols

The further macros and options allow to create a legend to symbols. This legend contains either all symbols or only the currently used symbols. Also, the description texts can be adapted to different languages or individual settings.

9.3.1 Printing a Legend

`\gtrSymbolsRecordReset`

The occurrence of a symbol inside the document text is recorded. `\gtrSymbolsLegend`^{P. 244} prints all recorded symbols. To clear the current recording (locally), `\gtrSymbolsRecordReset` can be used. Note that records are taken globally, but resets are local to the current TeX group.

```
\gtrSymbolsRecordReset
Use symbol: \gtrsymBorn\par
{
  \gtrSymbolsRecordReset
  Use symbol inside group: \gtrsymMarried\par
  {
    Use symbol further inside: \gtrsymDied\par
  }
  Local legend inside group: \gtrSymbolsLegend\par
}
Global legend: \gtrSymbolsLegend
```

Use symbol: ★
Use symbol inside group: ♂
Use symbol further inside: †
Local legend inside group: ♂=married, †=died.
Global legend: ★=born, ♂=married, †=died.

`/gtr/symbols record reset` (no value)

Identical to `\gtrSymbolsRecordReset`. This option is useful for application inside `\genealogytree`^{P. 55} or `genealogypicture`^{P. 57}. See `\gtrSymbolsLegend`^{P. 244} for an example.

U 2017-07-18

`\gtrSymbolsFullLegend[⟨language⟩]`

Prints a full unabridged legend to symbols according to `/gtr/language`^{P. 247} or optionally according to `⟨language⟩`.


```
\textsl{\gtrSymbolsFullLegend[english]}
```

★=born, (★)=born out of wedlock, †★=stillborn, ★†=died on the birthday,
≈=baptized, ○=engaged, ♂=married, ♂○=divorced, ○-○=unmarried partnership,
✱=floruit, †=died, ✕=killed in action, ☩=buried, ☩=cremated, ♀=female, ♂=male,
♀=neuter.

`\gtrSymbolsLegend[⟨language⟩]`

Prints a legend to symbols according to `/gtr/language`^{→ P. 247} or optionally according to `⟨language⟩`. The legend only contains these symbols which were actually used inside the document so far or since the last call to `\gtrSymbolsRecordReset`^{→ P. 243} or `/gtr/symbols record reset`^{→ P. 243}.

```
\begin{genealogypicture}[node size=3.2cm,level size=2.5cm,
  box={fit basedim=9pt,boxsep=2pt,colback=red!10,segmentation style={solid}},
  symbols record reset,code={\gtrSymbolsSetCreate{blue}},
  after tree={\node[font=\scriptsize\itshape,text width=3cm,above right,
    fill=blue!5] at ([xshift=1cm]Michael.south east) {\gtrSymbolsLegend};},
]
child{
  g[id=Charles]{Charles Smith\par\gtrsymBorn~1722 London\par
    \gtrsymBaptized~13.IV.1722\ London\par
    \gtrsymKilled~12.X.1764}
  p{Jane Bowden\par\gtrsymBorn~1724\par
    \gtrsymDied~7.VII.1802\ New York
    \tcblne
    \gtrsymMarried~2.III.1742\ London
  }
  c{Abraham Bowden\par
    \gtrsymBornoutofwedlock~4.I.1740 London\par
    \gtrsymDied~23.II.1740 London}
  c{Elizabeth Smith\par
    \gtrsymBorn~2.II.1742 London\par
    \gtrsymFloruit~1780--1805 New York\par
    \gtrsymDied~12.IV.1812 Boston}
  c[id=Michael]{Michael Smith\par\gtrsymDiedonbirthday~1.III.1761}
}
\end{genealogypicture}
```



9.3.2 Description Texts and Language Settings

The following options of the key family `/gtr/symlang/` are language dependent and can be set globally by `/gtr/language`^{→ P. 247}.

english

```
\gtrset{language=english}
% ...
\gtrSymbolsFullLegend
```

★ = born, (★) = born out of wedlock, †★ = stillborn, ★† = died on the birthday, ≈ = baptized, ○ = engaged, ⚭ = married, ⚭ = divorced, ○○ = unmarried partnership, ✧ = floruit, † = died, ✕ = killed in action, ☩ = buried, ☩ = cremated, ♀ = female, ♂ = male, ♀ = neuter.


```
\gtrset{language=german}
% ...
\gtrSymbolsFullLegend
```

★=geboren, (★)=außerehelich geboren, †★=tot geboren,
 ★†=am Tag der Geburt gestorben, ≈=getauft, ○=verlobt,
 ⊕=verheiratet, ⊙=geschieden, ○○=außerehelich ver-
 bunden, ✨=blühte, †=gestorben, ✕=gefallen, ☿=begraben,
 ♀=eingäschert, ♀=weiblich, ♂=männlich, ♀=Geschlecht un-
 bekannt.

`/gtr/symlang/Born=<text>` (no default, initially born)

Legend `<text>` used for ★.

`/gtr/symlang/Bornoutofwedlock=<text>` (no default, initially born out of wedlock)

Legend `<text>` used for (★).

`/gtr/symlang/Stillborn=<text>` (no default, initially stillborn)

Legend `<text>` used for †★.

`/gtr/symlang/Diedonbirthday=<text>` (no default, initially died on the birthday)

Legend `<text>` used for ★†.

`/gtr/symlang/Baptized=<text>` (no default, initially baptized)

Legend `<text>` used for ≈.

`/gtr/symlang/Engaged=<text>` (no default, initially engaged)

Legend `<text>` used for ○.

`/gtr/symlang/Married=<text>` (no default, initially married)

Legend `<text>` used for ⊕.

`/gtr/symlang/Divorced=<text>` (no default, initially divorced)

Legend `<text>` used for ⊙.

`/gtr/symlang/Partnership=<text>` (no default, initially unmarried partnership)

Legend `<text>` used for ○○.

`/gtr/symlang/Floruit=<text>` (no default, initially floruit)

Legend `<text>` used for ✨.

`/gtr/symlang/Died=<text>` (no default, initially died)

Legend `<text>` used for †.

`/gtr/symlang/Killed=<text>` (no default, initially killed in action)

Legend `<text>` used for ✕.

`/gtr/symlang/Buried=<text>` (no default, initially buried)

Legend `<text>` used for ☿.

`/gtr/symlang/Funeralurn=<text>` (no default, initially cremated)

Legend `<text>` used for ☿.

`/gtr/symlang/Female=<text>` (no default, initially female)

Legend `<text>` used for ♀.

`/gtr/symlang/Male=<text>` (no default, initially male)

Legend `<text>` used for ♂.

`/gtr/symlang/Neuter=<text>` (no default, initially neuter)

Legend `<text>` used for ♀.

10

Language and Text Settings

The document [genealogytree-languages.pdf](#) displays the effects of language specific settings.

10.1 Preamble Settings

U 2023-03-09

`/gtr/language=<language>` (no default, initially **english**)

Sets the `<language>` for the description texts of the package. Typically, this option should be used inside the preamble, but it may also be used inside the document to switch between languages.

- If this option is used inside the preamble, the corresponding language library is loaded automatically.
- If this option is used inside the document, the corresponding language library has to be loaded separately inside the preamble by `\gtrloadlanguage` ^{P. 248}.
- If this option is not used at all, the **english** language is set.

Feasible values for `<language>` are:

- **catalan** (Translation provided by Josep Tebé i Cetó)
- **chinese** (Translation¹ provided by Chen Yanzheng)
- **danish** (Translation provided by Mikkel Eide Eriksen)
- **dutch** (Translation provided by Dirk Bosmans)
- **english**
- **french** (Translation provided by Denis Bitouzé)
- **german** with variants:
 - **german-german**
 - **german-austrian**
- **italian** (Translation provided by Andrea Vaccari)
- **portuguese** (Translation provided by Natan de Almeida Laverde)
- **spanish** (Translation provided by Francisco G. Pérez Sánchez)
- **swedish** (Translation provided by Per Starbäck)

```
\documentclass{...}
%...
\gtrset{language=german-austrian}
%...
\begin{document}
%...
\end{document}
```

The current language name is stored inside `\gtrlanguage`.

¹ **chinese** needs the CJK package and its CJK or CJK* environment.

The current language is '`\gtrlanguage`'.

The current language is 'english'.

The `/gtr/language`^{→ P. 247} option sets various keys for description texts. These texts can be customized selectively, if needed.

```
\gtrset{language=german}
\gtrSymbolsRecordReset
\gtrsymBorn\ 1775, \gtrsymDied\ 1832.
\hfill(\gtrSymbolsLegend)
```

```
\gtrset{symlang/Born=geb.}
\gtrSymbolsRecordReset
\gtrsymBorn\ 1775, \gtrsymDied\ 1832.
\hfill(\gtrSymbolsLegend)
```

```
\gtrset{language=english}
\gtrSymbolsRecordReset
\gtrsymBorn\ 1775, \gtrsymDied\ 1832.
\hfill(\gtrSymbolsLegend)
```

★ 1775, † 1832.	(★=geboren, †=gestorben.)
★ 1775, † 1832.	(★=geb., †=gestorben.)
★ 1775, † 1832.	(★=born, †=died.)

`\gtrloadlanguage{⟨list of languages⟩}`

[U 2020-07-27](#)

Loads a comma separated *⟨list of languages⟩*. This has to be given inside the preamble, if more than one language should be used in the document. Every loaded language can be used by `/gtr/language`^{→ P. 247} inside the document. For a list of feasible language names, see `/gtr/language`^{→ P. 247}.

```
\documentclass{...}
%...
\gtrloadlanguage{english,german}
%...
\begin{document}
%...
\end{document}
```

10.2 Document Settings

Switching between languages inside the document is done by setting `/gtr/language`^{→ P. 247}. Note that every language to be used has to be loaded inside the preamble by `\gtrloadlanguage`.

11

Debugging: Library debug

The library is loaded by a package option or inside the preamble by:

```
\gtruselibrary{debug}
```

This also loads the packages `array` and `tabularx` and the `breakable` library of `tcolorbox`

11.1 Parser Debugging

The debugger for the parser can be used to check a manually or automatically generated tree source code to be well-formed. In this context, well-formedness means correct (L^AT_EX) grouping and correct nesting with subgraph elements following the given graph grammar, see Chapter 4. It is not checked, if all mandatory graph elements are present or if too many elements are given.

Also, the debugger gives a formal structured view of the given data which is useful to search for input errors if the graphical representation fails.

`\gtrparserdebug[<options>]{<graph content>}`

Parses the given *<graph content>*. If the content is well-formed, a structured list of the given data is produced. The families are automatically colored in the list. Any *<options>* are checked by setting them and they are logged in the produced list.

```
\gtrparserdebug{
  parent{%
    c[id=pB]{B\\(child)}%
    g[id=pA]{A\\(proband)}%
    c[id=pC]{C\\(child)}%
    c[id=pD]{D\\(child)}%
    p[id=pE]{E\\(parent)}%
    p[id=pF]{F\\(parent)}%
  }
}
```

Genealogytree Parser Debugger	
	Start: Parent Family 1, Level 1
↓	Child: Individual 1, Family 1, Level 0
	c Options: id=pB Content: B\\(child)
	Child: Individual 2, Family 1, Level 0
	g Options: id=pA Content: A\\(proband)
	Child: Individual 3, Family 1, Level 0
	c Options: id=pC Content: C\\(child)
	Child: Individual 4, Family 1, Level 0
	c Options: id=pD Content: D\\(child)
	Parent: Individual 5, Family 1, Level 1
	p Options: id=pE Content: E\\(parent)
	Parent: Individual 6, Family 1, Level 1
	p Options: id=pF Content: F\\(parent)
↑	End: Parent Family 1, Level 1
	End of Genealogytree Parser Debugger

```
\gtrparserdebuginput[⟨options⟩]{⟨file name⟩}
```

Loads the file denoted by *⟨file name⟩* and parses its content. If the content is well-formed, a structured list of the given data is produced. The families are automatically colored in the list. Any *⟨options⟩* are checked by setting them and they are logged in the list.

The following example uses the graph from Section 15.1 on page 359.

```
\gtrparserdebuginput{example.option.graph}
```

	Genealogytree Parser Debugger
	Start: Parent Family 1, Level 1
	Options: id=SmithDoe
	Child: Individual 1, Family 1, Level 0
g	Options: id=Arth2008,male
	Content: Arthur\\\gtrsymBorn \,2008
c	Child: Individual 2, Family 1, Level 0
	Options: id=Bert2010,female
	Content: Berta\\\gtrsymBorn \,2010
c	Child: Individual 3, Family 1, Level 0
	Options: id=Char2014,male
	Content: Charles\\\gtrsymBorn \,2014
	Start: Parent Family 2, Level 2
	Options: id=Smith
	Child: Individual 4, Family 2, Level 1
g	Options: id=John1980,male
	Content: John Smith\\\gtrsymBorn \,1980
	Parent: Individual 5, Family 2, Level 2
p	Options: id=GpSm1949,male
	Content: Grandpa Smith\\\gtrsymBorn \,1949
	Parent: Individual 6, Family 2, Level 2
p	Options: id=GmSm1952,female
	Content: Grandma Smith\\\gtrsymBorn \,1952
	End: Parent Family 2, Level 2
	Start: Parent Family 3, Level 2
	Options: id=Doe
	Child: Individual 7, Family 3, Level 1
g	Options: id=Jane1982,female
	Content: Jane Doe\\\gtrsymBorn \,1982
	Child: Individual 8, Family 3, Level 1
c	Options: id=Harr1987,male
	Content: Uncle Harry\\\gtrsymBorn \,1987
	Parent: Individual 9, Family 3, Level 2
p	Options: id=GpDo1955,male
	Content: Grandpa Doe\\\gtrsymBorn \,1955
	Parent: Individual 10, Family 3, Level 2
p	Options: id=GmDo1956,female
	Content: Grandma Doe\\\gtrsymBorn \,1956
	End: Parent Family 3, Level 2
	End: Parent Family 1, Level 1
	End of Genealogytree Parser Debugger

11.2 Processor Debugging

`\gtrprocessordebug[⟨options⟩]{⟨graph content⟩}`

Processes the given *⟨graph content⟩*. If the content can be processed without error, a structured list of the processed data is produced. The families are automatically colored in the list. Any *⟨options⟩* are set for processing.

```
\gtrprocessordebug{
  parent{%
    c[id=pB]{B\\(child)}%
    g[id=pA]{A\\(proband)}%
    c[id=pC]{C\\(child)}%
    c[id=pD]{D\\(child)}%
    p[id=pE]{E\\(parent)}%
    p[id=pF]{F\\(parent)}%
  }
}
```

Genealogytree Processor Debugger

Family 1

type: par	<i>type of family</i>
id: ⟨none⟩	<i>identifier</i>
fam: ⟨none⟩	<i>enclosing family</i>
offset: 0.0pt	<i>x (or y) offset relative to enclosing family</i>
pos: 7.11319pt	<i>y (or x) absolute position</i>
cwest@anchor: 1	<i>west contour starting node</i>
ceast@anchor: 4	<i>east contour starting node</i>
g: 2	<i>g-node of the family</i>
par: 5, 6	<i>parent nodes</i>
chi: 1, 2, 3, 4	<i>child nodes</i>
patpar: 5, 6	<i>patchwork parent nodes</i>
patchi: 1, 2, 3, 4	<i>patchwork child nodes</i>
union: ⟨none⟩	<i>further partner families</i>
ps: 0pt	<i>pivot shift length (parents vs childs)</i>
x: 0.0pt	<i>x anchor</i>
y: ⟨none⟩	<i>y anchor</i>
frac: 0.5	<i>line positioning fraction</i>
opt@family: ⟨none⟩	<i>options for the family</i>
opt@subtree: ⟨none⟩	<i>options for the subtree</i>

Parents of Family 1

Person 5

id: pE	identifier (also node alias)
fam: 1	enclosing family
chiof: <none>	child of family
parof: 1	parent of family
x: 0.0pt	x anchor
y: 113.811pt	y anchor
dim: 71.13188pt	width (or height)
cwest@val: 0.0pt	west contour value
cwest@next: <none>	west contour successor
cwest@thread: <none>	west contour thread
cwest@tgap: <none>	west contour thread gap
ceast@val: 71.13188pt	east contour value
ceast@next: <none>	east contour successor
ceast@thread: <none>	east contour thread
ceast@tgap: <none>	east contour thread gap

E
(parent)

Person 6

id: pF	identifier (also node alias)
fam: 1	enclosing family
chiof: <none>	child of family
parof: 1	parent of family
x: 76.82242pt	x anchor
y: 113.811pt	y anchor
dim: 71.13188pt	width (or height)
cwest@val: 76.82242pt	west contour value
cwest@next: <none>	west contour successor
cwest@thread: <none>	west contour thread
cwest@tgap: <none>	west contour thread gap
ceast@val: 147.9543pt	east contour value
ceast@next: <none>	east contour successor
ceast@thread: <none>	east contour thread
ceast@tgap: <none>	east contour thread gap

F
(parent)

Childs of Family 1

Person 1

id: pB	identifier (also node alias)
fam: 1	enclosing family
chiof: 1	child of family
parof: <none>	parent of family
x: -72.5545pt	x anchor
y: 0.0pt	y anchor
dim: 71.13188pt	width (or height)
cwest@val: -72.5545pt	west contour value
cwest@next: 5	west contour successor
cwest@thread: <none>	west contour thread
cwest@tgap: <none>	west contour thread gap
ceast@val: -1.42262pt	east contour value
ceast@next: 6	east contour successor
ceast@thread: <none>	east contour thread
ceast@tgap: <none>	east contour thread gap

B
(child)

Person 2

id: pA	<i>identifier (also node alias)</i>
fam: 1	<i>enclosing family</i>
chiof: 1	<i>child of family</i>
parof: <none>	<i>parent of family</i>
x: 1.42264pt	<i>x anchor</i>
y: 0.0pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 1.42264pt	<i>west contour value</i>
cwest@next: <none>	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 72.55452pt	<i>east contour value</i>
ceast@next: 6	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

A
(proband)

Person 3

id: pC	<i>identifier (also node alias)</i>
fam: 1	<i>enclosing family</i>
chiof: 1	<i>child of family</i>
parof: <none>	<i>parent of family</i>
x: 75.39978pt	<i>x anchor</i>
y: 0.0pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 75.39978pt	<i>west contour value</i>
cwest@next: <none>	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 146.53166pt	<i>east contour value</i>
ceast@next: 6	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

C
(child)

Person 4

id: pD	<i>identifier (also node alias)</i>
fam: 1	<i>enclosing family</i>
chiof: 1	<i>child of family</i>
parof: <none>	<i>parent of family</i>
x: 149.37692pt	<i>x anchor</i>
y: 0.0pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 149.37692pt	<i>west contour value</i>
cwest@next: <none>	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 220.5088pt	<i>east contour value</i>
ceast@next: 6	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

D
(child)

End of Genealogytree Processor Debugger

`\gtrprocessordebuginput[⟨options⟩]{⟨file name⟩}`

Loads the file denoted by `⟨file name⟩` and processes its content. If the content can be processed without error, a structured list of the processed data is produced. The families are automatically colored in the list. Any `⟨options⟩` are set for processing.

The following example uses the graph from Section 15.1 on page 359.

`\gtrprocessordebuginput{example.option.graph}`

Genealogytree Processor Debugger

Family 1

<code>type: par</code>	<i>type of family</i>
<code>id: SmithDoe</code>	<i>identifier</i>
<code>fam: ⟨none⟩</code>	<i>enclosing family</i>
<code>offset: 0.0pt</code>	<i>x (or y) offset relative to enclosing family</i>
<code>pos: 7.11319pt</code>	<i>y (or x) absolute position</i>
<code>cwest@anchor: 1</code>	<i>west contour starting node</i>
<code>ceast@anchor: 3</code>	<i>east contour starting node</i>
<code>g: 1</code>	<i>g-node of the family</i>
<code>par: 4, 7</code>	<i>parent nodes</i>
<code>chi: 1, 2, 3</code>	<i>child nodes</i>
<code>patpar: 4, 7</code>	<i>patchwork parent nodes</i>
<code>patchi: 1, 2, 3</code>	<i>patchwork child nodes</i>
<code>union: ⟨none⟩</code>	<i>further partner families</i>
<code>ps: 0pt</code>	<i>pivot shift length (parents vs childs)</i>
<code>x: 0.0pt</code>	<i>x anchor</i>
<code>y: ⟨none⟩</code>	<i>y anchor</i>
<code>frac: 0.5</code>	<i>line positioning fraction</i>
<code>opt@family: ⟨none⟩</code>	<i>options for the family</i>
<code>opt@subtree: ⟨none⟩</code>	<i>options for the subtree</i>

Parents of Family 1

Person 4

<code>id: John1980</code>	<i>identifier (also node alias)</i>
<code>fam: 2</code>	<i>enclosing family</i>
<code>chiof: 2</code>	<i>child of family</i>
<code>parof: 1</code>	<i>parent of family</i>
<code>x: 38.41121pt</code>	<i>x anchor</i>
<code>y: 113.811pt</code>	<i>y anchor</i>
<code>dim: 71.13188pt</code>	<i>width (or height)</i>
<code>cwest@val: 38.41121pt</code>	<i>west contour value</i>
<code>cwest@next: 5</code>	<i>west contour successor</i>
<code>cwest@thread: ⟨none⟩</code>	<i>west contour thread</i>
<code>cwest@tgap: ⟨none⟩</code>	<i>west contour thread gap</i>
<code>ceast@val: 109.54309pt</code>	<i>east contour value</i>
<code>ceast@next: 6</code>	<i>east contour successor</i>
<code>ceast@thread: ⟨none⟩</code>	<i>east contour thread</i>
<code>ceast@tgap: ⟨none⟩</code>	<i>east contour thread gap</i>

John Smith
★ 1980

Person 7		
id: Jane1982	<i>identifier (also node alias)</i>	<div>Jane Doe ★ 1982</div>
fam: 3	<i>enclosing family</i>	
chiof: 3	<i>child of family</i>	
parof: 1	<i>parent of family</i>	
x: 157.91275pt	<i>x anchor</i>	
y: 113.811pt	<i>y anchor</i>	
dim: 71.13188pt	<i>width (or height)</i>	
cwest@val: 1.42264pt	<i>west contour value</i>	
cwest@next: 9	<i>west contour successor</i>	
cwest@thread: <none>	<i>west contour thread</i>	
cwest@tgap: <none>	<i>west contour thread gap</i>	
ceast@val: 72.55452pt	<i>east contour value</i>	
ceast@next: 10	<i>east contour successor</i>	
ceast@thread: <none>	<i>east contour thread</i>	
ceast@tgap: <none>	<i>east contour thread gap</i>	
Childs of Family 1		
Person 1		
id: Arth2008	<i>identifier (also node alias)</i>	<div>Arthur ★ 2008</div>
fam: 1	<i>enclosing family</i>	
chiof: 1	<i>child of family</i>	
parof: <none>	<i>parent of family</i>	
x: 24.18484pt	<i>x anchor</i>	
y: 0.0pt	<i>y anchor</i>	
dim: 71.13188pt	<i>width (or height)</i>	
cwest@val: 24.18484pt	<i>west contour value</i>	
cwest@next: 4	<i>west contour successor</i>	
cwest@thread: <none>	<i>west contour thread</i>	
cwest@tgap: <none>	<i>west contour thread gap</i>	
ceast@val: 95.31673pt	<i>east contour value</i>	
ceast@next: 8	<i>east contour successor</i>	
ceast@thread: <none>	<i>east contour thread</i>	
ceast@tgap: <none>	<i>east contour thread gap</i>	
Person 2		
id: Bert2010	<i>identifier (also node alias)</i>	<div>Berta ★ 2010</div>
fam: 1	<i>enclosing family</i>	
chiof: 1	<i>child of family</i>	
parof: <none>	<i>parent of family</i>	
x: 98.16199pt	<i>x anchor</i>	
y: 0.0pt	<i>y anchor</i>	
dim: 71.13188pt	<i>width (or height)</i>	
cwest@val: 98.16199pt	<i>west contour value</i>	
cwest@next: <none>	<i>west contour successor</i>	
cwest@thread: <none>	<i>west contour thread</i>	
cwest@tgap: <none>	<i>west contour thread gap</i>	
ceast@val: 169.29387pt	<i>east contour value</i>	
ceast@next: 8	<i>east contour successor</i>	
ceast@thread: <none>	<i>east contour thread</i>	
ceast@tgap: <none>	<i>east contour thread gap</i>	

Person 3		
id: Char2014	<i>identifier (also node alias)</i>	<div>Charles ★ 2014</div>
fam: 1	<i>enclosing family</i>	
chiof: 1	<i>child of family</i>	
parof: <none>	<i>parent of family</i>	
x: 172.13913pt	<i>x anchor</i>	
y: 0.0pt	<i>y anchor</i>	
dim: 71.13188pt	<i>width (or height)</i>	
cwest@val: 172.13913pt	<i>west contour value</i>	
cwest@next: <none>	<i>west contour successor</i>	
cwest@thread: <none>	<i>west contour thread</i>	
cwest@tgap: <none>	<i>west contour thread gap</i>	
ceast@val: 243.27101pt	<i>east contour value</i>	
ceast@next: 8	<i>east contour successor</i>	
ceast@thread: <none>	<i>east contour thread</i>	
ceast@tgap: <none>	<i>east contour thread gap</i>	

Family 2		
type: par	<i>type of family</i>	
id: Smith	<i>identifier</i>	
fam: 1	<i>enclosing family</i>	
offset: 0pt	<i>x (or y) offset relative to enclosing family</i>	
pos: 120.9242pt	<i>y (or x) absolute position</i>	
cwest@anchor: 4	<i>west contour starting node</i>	
ceast@anchor: 4	<i>east contour starting node</i>	
g: 4	<i>g-node of the family</i>	
par: 5, 6	<i>parent nodes</i>	
chi: 4	<i>child nodes</i>	
patpar: 5, 6	<i>patchwork parent nodes</i>	
patchi: 4	<i>patchwork child nodes</i>	
union: <none>	<i>further partner families</i>	
ps: 0pt	<i>pivot shift length (parents vs childs)</i>	
x: 0.0pt	<i>x anchor</i>	
y: <none>	<i>y anchor</i>	
frac: 0.5	<i>line positioning fraction</i>	
opt@family: <none>	<i>options for the family</i>	
opt@subtree: <none>	<i>options for the subtree</i>	
Parents of Family 2		

Person 5

id: GpSm1949	<i>identifier (also node alias)</i>
fam: 2	<i>enclosing family</i>
chiof: <none>	<i>child of family</i>
parof: 2	<i>parent of family</i>
x: 0.0pt	<i>x anchor</i>
y: 227.62201pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 0.0pt	<i>west contour value</i>
cwest@next: <none>	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 71.13188pt	<i>east contour value</i>
ceast@next: <none>	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

Grandpa
Smith
★ 1949

Person 6

id: GmSm1952	<i>identifier (also node alias)</i>
fam: 2	<i>enclosing family</i>
chiof: <none>	<i>child of family</i>
parof: 2	<i>parent of family</i>
x: 76.82242pt	<i>x anchor</i>
y: 227.62201pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 76.82242pt	<i>west contour value</i>
cwest@next: <none>	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 147.9543pt	<i>east contour value</i>
ceast@next: <none>	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

Grandma
Smith
★ 1952

Childs of Family 2

Person 4

id: John1980	<i>identifier (also node alias)</i>
fam: 2	<i>enclosing family</i>
chiof: 2	<i>child of family</i>
parof: 1	<i>parent of family</i>
x: 38.41121pt	<i>x anchor</i>
y: 113.811pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 38.41121pt	<i>west contour value</i>
cwest@next: 5	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 109.54309pt	<i>east contour value</i>
ceast@next: 6	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

John Smith
★ 1980

Family 3

type: par	<i>type of family</i>
id: Doe	<i>identifier</i>
fam: 1	<i>enclosing family</i>
offset: 156.49011pt	<i>x (or y) offset relative to enclosing family</i>
pos: 120.9242pt	<i>y (or x) absolute position</i>
cwest@anchor: 7	<i>west contour starting node</i>
ceast@anchor: 8	<i>east contour starting node</i>
g: 7	<i>g-node of the family</i>
par: 9, 10	<i>parent nodes</i>
chi: 7, 8	<i>child nodes</i>
patpar: 9, 10	<i>patchwork parent nodes</i>
patchi: 7, 8	<i>patchwork child nodes</i>
union: <none>	<i>further partner families</i>
ps: 0pt	<i>pivot shift length (parents vs childs)</i>
x: 156.49011pt	<i>x anchor</i>
y: <none>	<i>y anchor</i>
frac: 0.5	<i>line positioning fraction</i>
opt@family: <none>	<i>options for the family</i>
opt@subtree: <none>	<i>options for the subtree</i>

Parents of Family 3

Person 9

id: GpDo1955	identifier (also node alias)	Grandpa Doe ★ 1955
fam: 3	enclosing family	
chiof: <none>	child of family	
parof: 3	parent of family	
x: 156.49011pt	x anchor	
y: 227.62201pt	y anchor	
dim: 71.13188pt	width (or height)	
cwest@val: 0.0pt	west contour value	
cwest@next: <none>	west contour successor	
cwest@thread: <none>	west contour thread	
cwest@tgap: <none>	west contour thread gap	
ceast@val: 71.13188pt	east contour value	
ceast@next: <none>	east contour successor	
ceast@thread: <none>	east contour thread	
ceast@tgap: <none>	east contour thread gap	

Person 10

id: GmDo1956	identifier (also node alias)	Grandma Doe ★ 1956
fam: 3	enclosing family	
chiof: <none>	child of family	
parof: 3	parent of family	
x: 233.31253pt	x anchor	
y: 227.62201pt	y anchor	
dim: 71.13188pt	width (or height)	
cwest@val: 76.82242pt	west contour value	
cwest@next: <none>	west contour successor	
cwest@thread: <none>	west contour thread	
cwest@tgap: <none>	west contour thread gap	
ceast@val: 147.9543pt	east contour value	
ceast@next: <none>	east contour successor	
ceast@thread: <none>	east contour thread	
ceast@tgap: <none>	east contour thread gap	

Childs of Family 3

Person 7

id: Jane1982	<i>identifier (also node alias)</i>
fam: 3	<i>enclosing family</i>
chiof: 3	<i>child of family</i>
parof: 1	<i>parent of family</i>
x: 157.91275pt	<i>x anchor</i>
y: 113.811pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 1.42264pt	<i>west contour value</i>
cwest@next: 9	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 72.55452pt	<i>east contour value</i>
ceast@next: 10	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

Jane Doe
★ 1982

Person 8

id: Harr1987	<i>identifier (also node alias)</i>
fam: 3	<i>enclosing family</i>
chiof: 3	<i>child of family</i>
parof: <none>	<i>parent of family</i>
x: 231.8899pt	<i>x anchor</i>
y: 113.811pt	<i>y anchor</i>
dim: 71.13188pt	<i>width (or height)</i>
cwest@val: 75.39978pt	<i>west contour value</i>
cwest@next: <none>	<i>west contour successor</i>
cwest@thread: <none>	<i>west contour thread</i>
cwest@tgap: <none>	<i>west contour thread gap</i>
ceast@val: 146.53166pt	<i>east contour value</i>
ceast@next: 10	<i>east contour successor</i>
ceast@thread: <none>	<i>east contour thread</i>
ceast@tgap: <none>	<i>east contour thread gap</i>

Uncle Harry
★ 1987

End of Genealogytree Processor Debugger


11.3 Graphical Debugging

`\gtrdebugdrawcontour`{*⟨options⟩*}{*⟨path options⟩*}

After a `\genealogytree`^{P.55} is drawn inside a `tikzpicture` environment, the auto-layout contour lines of a family can be displayed with this macro. For *⟨options⟩*, the keys `/gtr/debug/family number`^{P.262}, `/gtr/debug/family id`^{P.262}, `/gtr/debug/contour`^{P.263} may be used to specify the family and the contour lines to draw. The *⟨path options⟩* are used to draw a TikZ path.

- Contour lines for the root family should always be displayed correctly.
- Contour lines for embedded families may be displayed prolonged, because these are used to build the contour lines of their embedding families. Note that `\gtrdebugdrawcontour` shows the remains of the building process, but not the dynamics of the process.
- Contour lines for **union** families are not displayed, since they are melted to their embedding **child** family.


```
\begin{tikzpicture}
\genealogytree[template=formal graph]
{
  child{
    g{P_1} p{P_2} c{C_1} c{C_2}
    child{
      g{C_3} p{P_3} c{C_4} c{C_5} c{C_6}
    }
  }
}
\gtrdebugdrawcontour{}{draw=blue,line width=2pt}
\end{tikzpicture}
```



`/gtr/debug/family number=<number>` (no default, initially 1)

Selects a family by $\langle number \rangle$ inside the option list of `\gtrdebugdrawcontour` ^{→ P. 261}.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,show family]
{
  child{
    g{P_1} p{P_2} c{C_1} c{C_2}
    child{
      g{C_3} p{P_3} c{C_4} c{C_5} c{C_6}
    }
  }
}
\gtrdebugdrawcontour{family number=2}{draw=blue,line width=2pt}
\end{tikzpicture}
```



`/gtr/debug/family id=<id>` (no default, initially unset)

Selects a family by $\langle id \rangle$ inside the option list of `\gtrdebugdrawcontour` ^{→ P. 261}.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
options for family={fam_a}{box={colback=red!50}}]
{
  child{
    g{P_1} p{P_2} c{C_1} c{C_2}
    child[id=fam_a]{
      g{C_3} p{P_3} c{C_4} c{C_5} c{C_6}
    }
  }
}
\gtrdebugdrawcontour{family id=fam_a}{draw=blue,line width=2pt}
\end{tikzpicture}
```



`/gtr/debug/contour=west|east|both|none` (no default, initially both)

The two contour lines are always referred to as **west** and **east** contour lines independent of the `/gtr/timeflow→P.80` setting. With this option, a partial contour drawing can be used.


```
\begin{tikzpicture}
\genealogytree[template=formal graph,
options for family={fam_a}{box={colback=blue!30}},
options for family={fam_b}{box={colback=red!30}},
]
{
child{
g{P_1} p{P_2} c{C_1} c{C_2}
child[id=fam_a]{
g{C_3} p{P_3} c{C_4} c{C_5} c{C_6}
}
child[id=fam_b]{
g{C_7} p{P_4} c{C_8}
}
}
}
\gtrdebugdrawcontour{}{draw=green,line width=2pt}
\gtrdebugdrawcontour{contour=east,family id=fam_a}{draw=blue,line width=2pt}
\gtrdebugdrawcontour{contour=west,family id=fam_b}{draw=red,line width=2pt}
\end{tikzpicture}
```



```

\begin{tikzpicture}
\genealogytree[template=signpost]{
  parent[id=myid]{
    c[id=pB]{B\\(child)}
    g[id=pA,box={colback=red!20!white}]{A\\(proband)}
    c[id=pC]{C\\(child)}
    c[id=pD]{D\\(child)}
    parent[id=partial,family={box={colback=red!5}}]{
      g[id=pX]{X\\(parent)}
      p{A} p{B} c{C} c{D} c{E}
    }
    parent[id=partial2,family={box={colback=green!5}}]{
      g[id=pY]{Y\\(parent)}
      p{U} p{V}
    }
  }
}
\gtrdebugdrawcontour{family id=partial}
  {preaction={draw=red,line width=1mm,opacity=.5},draw=red,line width=0.4pt}
\gtrdebugdrawcontour{family id=partial2}
  {preaction={draw=green,line width=1mm,opacity=.5},draw=green,line width=0.4pt}
\gtrdebugdrawcontour{family id=myid}
  {preaction={draw=blue,line width=1mm,opacity=.5,dashed},draw=blue,line width=0.4pt}
\end{tikzpicture}

```




11.4 Show Information

Note that most options in this section only work, if a `/gtr/processing`^{P.138} based on a box from the `tcolorbox` package is chosen (this is the default setting).

`/gtr/show=<text>` (style, no default)

Shows a `<text>` overlay for each node of the tree.


```
\begin{tikzpicture}
\genealogytree[template=signpost,show={Test}]
{input{example.option.graph}}
\end{tikzpicture}
```



`/gtr/show id` (style, no value)

Shows the `/gtr/id`^{P.92} values of every node and every family. This can be very valuable not only for debugging, but also for visual identification of nodes to manipulate.

```
\begin{tikzpicture}
\genealogytree[template=signpost,show id]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/show level`

(style, no value)

Shows the level numbers of every node. This information can be used for setting `/gtr/level` → P. 109 and `/gtr/level n` → P. 110.

```
\begin{tikzpicture}
\genealogytree[template=signpost,show level]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/show number`

(style, no value)

Shows the internal numbers of every node and every family. It is strongly recommended to reference a node by a chosen `/gtr/id` → P. 92 and not by its internal number, because numbers may easily change when editing the tree.

```
\begin{tikzpicture}
\genealogytree[template=signpost,show number]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/show family`

(style, no value)

Shows the internal family numbers each node belongs to. A **g** node can be part of many families, but only one family is the *enclosing* family. For a **union** family, the family number is displayed, but the *enclosing* family is the family of the **g** node.

```
\begin{tikzpicture}
\genealogytree[template=signpost,show family]
{input{example.option.graph}}
\end{tikzpicture}
```




`/gtr/show type`

(style, no value)

Show the node type for every node.

```
\begin{tikzpicture}
\genealogytree[template=signpost,show type]
{input{example.option.graph}}
\end{tikzpicture}
```



12

Templates: Library LIB templates

The library is loaded by a package option or inside the preamble by:

```
\gtruselibrary{templates}
```

12.1 Using Templates

`/gtr/template=<name>` (style, no default)


Sets a predefined style $\langle name \rangle$ for a genealogytree graph. A template does not provide new functionality, but combines various options for specific trees, e.g., used inside this documentation. It serves as a shortcut. If a template is used, it is recommended to apply it as very first option.

12.2 Template 'formal graph'

```
template=formal graph
```

This style is based on `/gtr/processing`^{P.138}=`tcbox*`. The box content is set as formula in mathematical mode. For further examples, see Section 5.3 on page 83.

```
\begin{tikzpicture}
\genealogytree[template=formal graph]{
  child{
    g{P_1}
    p{P_2}
    c{C_1}
    c{C_2}
    c{C_3}
  }
}
\end{tikzpicture}
```




12.3 Template 'signpost'

template=signpost

This style is based on `/gtr/processing`^{P.138}=`fit`. For further examples, see Section 5.2 on page 80 and many more.

```
\begin{tikzpicture}
\genealogytree[template=signpost]{
  child{
    g{Father}
    p{Mother}
    c{Child 1}
    c{Child 2}
    c{Child 3}
  }
}
\end{tikzpicture}
```




12.4 Template 'symbol nodes'

template=symbol nodes

This style is based on `/gtr/processing`^{P.138}=`tcbox*`. For the content, a single token `m` selects a male node (also `male`), a single token `f` selects a female node (also `female`), and every other token selects a neuter node. The symbol coloring with `\gtrSymbolsSetCreateSelected`^{P.238} has to be done *before* entering a `tikzpicture` environment.

```
\gtrSymbolsSetCreateSelected{blue}{Male}
\gtrSymbolsSetCreateSelected{red}{Female}
\gtrSymbolsSetCreateSelected{black}{Neuter}
\begin{tikzpicture}
\genealogytree[template=symbol nodes]{
  child{
    gm pf cf
    child{gm pf cf cm}
    child{gm pf cm c- cm}
  }
}
\end{tikzpicture}
```




12.5 Template 'tiny boxes'

```
template=tiny boxes
```

This style is based on `/gtr/processing→P.138=tcbbox*`. The content of all boxes is removed. Therefore, a single token like `'-`' is enough to declare the content. For further examples, see Chapter 14 on page 349.

```
\begin{tikzpicture}
\genealogytree[template=tiny boxes]{
  child{
    g-p-c-
    child{g-p-c-c-}
    child{g-p-c-c-c-}
  }
}
\end{tikzpicture}
```




12.6 Template 'tiny circles'

```
template=tiny circles
```

This style is based on `/gtr/processing→P.138=tcbbox*`. The content of all boxes is removed. Therefore, a single token like `'` is enough to declare the content. All distances are set equally and edges are drawn meshed. For further examples, see Chapter 14 on page 349.

```
\begin{tikzpicture}
\genealogytree[template=tiny circles]{
  child{
    g-c-
    child{g-c-c-}
    child{g-c-c-c-}
  }
}
\end{tikzpicture}
```



12.7 Template 'medical'


This medical-style template was proposed by Alexis Praga.

`template=medical`

N 2026-05-06

This style is based on `/gtr/processing→P.138=tcbox*` and sets `/gtr/timeflow→P.80=down`. The box contents are moved into annotations on the left-hand side of the displayed nodes. These annotations are arranged as centered tables, and the autolayout algorithm adapts to their width; however, their height is not taken into account.

```
\begin{tikzpicture}
  \genealogytree[template=medical]
  {
    child{
      p[female]{I-1}
      g[male,deceased]{I-2}
      c[male,carrier,deceased]{}
      child{
        p[male]{}
        g[female,affected,deceased]{II-1\\d.79}
        c[female,affected]{III-1}
        c[male]{III-2}
        c[male,carrier]{}
      }
    }
    union[id=fam2]{
      p[female]{}
      c[female,carrier]{II-2}
      c[male,carrier]{}
      c[neuter,deceased]{}
    }
  }
\end{tikzpicture}
```



Feasible node options are `/gtr/male→P.101`, `/gtr/female→P.101`, and `/gtr/neuter→P.101`. In addition, the following special options are available:

`/gtr/carrier`

(style, no value, initially unset)

N 2026-05-06

This option applies a solid fill to one half of the node.

`/gtr/affected`

(style, no value, initially unset)

N 2026-05-06

This option applies a solid fill to the entire node.

`/gtr/deceased`

(style, no value, initially unset)


N 2026-05-06

This option adds a strikeout line across the node.

```

\begin{tikzpicture}
\genealogytree[template=medical]
{
  child{
    p[female,carrier,deceased]{I-1\\d.58}
    g[male,deceased]{I-2\\d.75}
    child{
      p[female]{}
      g[male,affected,deceased]{II-1\\d.37}
      c[male]{}
      c[male]{}
      c[female,carrier,box={halo}]{III-1\\proband}
    }
    c[male]{}
    c[female]{}
    child{
      g[female,affected,deceased]{II-2\\d.45}
      p[male]{}
      c[male]{}
      c[female]{}
      child{
        g[female,carrier]{III-2}
        p[male,affected]{III-3}
        c[male]{IV-1}
        c[male,affected]{IV-2}
        c[female,carrier]{IV-3}
        c[female,affected,deceased]{IV-4\\d.3}
      }
    }
  }
}
\end{tikzpicture}

```



This template allows a certain degree of customization:


- Adjust `/gtr/level size`^{→P.84} and `/gtr/node size`^{→P.85} to the same value in order to change the node size.
- Adjust the colors `gtr_Female_Background`, `gtr_Female_Frame`, `gtr_Male_Background`, `gtr_Male_Frame`, `gtr_Neuter_Background`, and `gtr_Neuter_Frame` to customize the node coloring.
- The color and font of the annotation can be customized using the `tcolorbox`^{→CTAN} keys `colupper` and `fontupper` via `/gtr/box`^{→P.98}.

12.8 Template 'directory'

template=directory

This style is based on `/gtr/processing`^{→P.138}=`tcbox*` and sets `/gtr/timeflow`^{→P.80}=`right`. Note that optimal level sizes have to be set manually.

```
\begin{genealogypicture}[template=directory,
  level 0/.style={level size=11mm},
  level -1/.style={level size=11mm},
  level -2/.style={level size=15mm},
  level -3/.style={level size=31mm},
  level -4/.style={level size=62mm},
]
child{ g{tds}
  child[subtree box={colback=green!20}]{ g{doc}
    child{ g{latex}
      child{ g{genealogytree}
        c{genealogytree.pdf}
        c{genealogytree.doc.sources.zip}
        c{README}
      }
    }
  }
  child[subtree box={colback=red!15}]{ g{tex}
    child{ g{latex}
      child{ g{genealogytree}
        c{genealogytree.sty}
        c{gtrcore.*.code.tex}
        c{gtrlang.*.code.tex}
        c{gtrlib.*.code.tex}
      }
    }
  }
}
\end{genealogypicture}
```



12.9 Template 'database pole'


```
template=database pole
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage above`.

The boxes are quite small for placing many nodes horizontally. Also, many settings are adapted for this style.

The following example uses a file documented in Section 15.2 on page 360.

```
\begin{genealogypicture}
[template=database pole]
input{example.database.graph}
\end{genealogypicture}
```




The next example uses the graph data from Section 2.3.5 on page 39.

```

\begin{genealogypicture}[template=database pole,tikzpicture={scale=0.9,transform shape}]
  input{example.gauss.graph}
\end{genealogypicture}

```



12.10 Template 'database pole reduced'

N 2017-09-15


template=database pole reduced

This style is identical to **database pole** (Section 12.9 on page 275), but every size property is scaled by factor $\frac{1}{10}$. Therefore, the resulting graphs are only 10 percent of width and height of corresponding graphs made with **database pole**.

- T_EX/L_AT_EX length values are limited by about 575cm. Due to internal calculations, the maximum width and height of a graph may even be smaller. Using this *reduced* layout size, this limit is avoided to a certain degree.
- For virtual PDF 'paper' on a computer screen, the tiny layout irrelevant, since this vector format can be zoomed without loss.
- For printing, the PDF also can be zoomed or cut into several pages which can be zoomed.
- Note that a freely scalable text font is needed for the *reduced* layout size! The standard L_AT_EX font is not scalable.
- Examples with more than 1500 nodes compiled successfully. Note that the compiler memory settings may have to be set to increased values for graphs with many nodes.

The following example uses the graph data from Section 2.3.5 on page 39.

```
\begin{tikzpicture}[
  spy using outlines={circle, magnification=10, size=5cm, connect spies}]
  \genealogytreeinput[template=database pole reduced]{example.gauss.graph}
  \spy on (0.6,-0.1) in node [left] at (7,1);
\end{tikzpicture}
```



12.11 Template 'database poleportrait'


template=database poleportrait

N 2017-09-15

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage above`.


In contrast to `database pole` (Section 12.9 on page 275), portraits are drawn, if present.

```
\begin{genealogypicture}
[template=database poleportrait]
input{example.database.graph}
\end{genealogypicture}
```



The next example uses the graph data from Section 2.3.5 on page 39.

```
\begin{genealogypicture}[template=database poleportrait,
tikzpicture={scale=0.8,transform shape}]
input{example.gauss.graph}
\end{genealogypicture}
```



12.12 Template 'database poleportrait reduced'


```
template=database poleportrait reduced
```

N 2017-09-15

This style is identical to `database poleportrait` (Section 12.11 on page 278), but every size property is scaled by factor $\frac{1}{10}$. See Section 12.10 on page 277 for more explanations.

The following example uses the graph data from Section 2.3.5 on page 39.

```
\begin{tikzpicture}[
  spy using outlines={circle, magnification=10, size=5cm, connect spies}]
  \genealogytreeinput[template=database poleportrait reduced]{example.gauss.graph}
  \spy on (0.6,-0.1) in node [left] at (7,1);
\end{tikzpicture}
```




12.13 Template 'database portrait'

```
template=database portrait
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=short no marriage`.

The boxes are quite small for placing many nodes horizontally. Also, many settings are adapted for this style. If `/gtr/database/image→P.166` is present, the corresponding image is inserted. Otherwise, a symbolic portrait is drawn.

```
\begin{genealogypicture}  
[template=database portrait]  
child{  
  g{male,name=Hans Test,  
    birth={1520-02-17}{Footown},  
    death={1588-12-12}{Footown}}  
  p{female,name=Berta,  
    death={1592-03-02}{Footown}}  
  c{name=Unknown,  
    birth+={1553-01-12}{Footown}  
    {stillborn}}  
}  
\end{genealogypicture}
```




The next example uses the graph data from Section 2.3.5 on page 39.

```

\begin{genealogypicture}[template=database portrait]
  input{example.gauss.graph}
\end{genealogypicture}

```



12.14 Template 'database portrait reduced'


N 2017-09-15

template=database portrait reduced

This style is identical to `database portrait` (Section 12.13 on page 281), but every size property is scaled by factor $\frac{1}{10}$. See Section 12.10 on page 277 for more explanations.

The following example uses the graph data from Section 2.3.5 on page 39.

```
\begin{tikzpicture}[
  spy using outlines={circle, magnification=10, size=5cm, connect spies}]
  \genealogytreeinput[template=database portrait reduced]{example.gauss.graph}
  \spy on (0.6,-0.1) in node [left] at (7,1);
\end{tikzpicture}
```



12.15 Template 'database traditional'

```
template=database traditional
```


This style is based on `/gtr/processing→P.138=database`, sets `/gtr/database format→P.174=short no marriage` and `/gtr/timeflow→P.80=down`.

Using this template, a sober black-and-white drawing with only short information is created. The box content is not framed.

- For **p** nodes, the content is bottom aligned.
- For **c** nodes, the content is top aligned.
- For **g** nodes, the content is center aligned. While this is usually reasonable, **g** nodes in families without childs or parents may have to be adapted manually. The root node is treated automatically.


The following example uses a file documented in Section 15.2 on page 360.

```
\begin{genealogypicture}[
  template=database traditional,
  level size=1.3cm ]
input{example.database.graph}
\end{genealogypicture}
```



The next example uses the graph data from Section 2.3.5 on page 39.

```
\begin{genealogypicture}[template=database traditional,
  level size=1.2cm,node size=2.2cm,date format=yyyy,list separators={\par}{ }{}{}]
input{example.gauss.graph}
\end{genealogypicture}
```



12.16 Template 'database traditional reduced'


N 2017-09-15

template=database traditional reduced

This style is identical to `database traditional` (Section 12.15 on page 284), but every size property is scaled by factor $\frac{1}{10}$. See Section 12.10 on page 277 for more explanations.

The following example uses the graph data from Section 2.3.5 on page 39.

```
\begin{tikzpicture}[
  spy using outlines={circle, magnification=10, size=5cm, connect spies}]
  \genealogytreeinput[template=database traditional reduced]{example.gauss.graph}
  \spy on (0.6,-0.1) in node [left] at (7,1);
\end{tikzpicture}
```



12.17 Template 'database sideways'


```
template=database sideways
```

This style is based on `/gtr/processing→P.138=database`, sets `/gtr/database format→P.174=medium` and `/gtr/timeflow→P.80=left`.

Here, the boxes are positioned sideways and have a large variety of height. Therefore, the content will seldom be resized.


The following example uses a file documented in Section 15.2 on page 360.

```
\begin{genealogypicture}[template=database sideways]
  input{example.database.graph}
\end{genealogypicture}
```



The next example uses the graph data from Section 2.3.5 on page 39.


```
\begin{genealogypicture}[template=database sideways,
  level size=3.2cm,ignore level=3,database format=name]
  input{example.gauss.graph}
\end{genealogypicture}
```



```

\begin{genealogypicture}[template=database sideways,
  level size=3.2cm,ignore level=3]
  input{example.gauss.graph}
\end{genealogypicture}

```



12.18 Template 'database sideways reduced'


template=database sideways reduced

N 2017-09-15

This style is identical to `database sideways` (Section 12.17 on page 286), but every size property is scaled by factor $\frac{1}{10}$. See Section 12.10 on page 277 for more explanations.

The following example uses the graph data from Section 2.3.5 on page 39.

```
\begin{tikzpicture}[
  spy using outlines={circle, magnification=10, size=5cm, connect spies}
  \genealogytreeinput[template=database sideways reduced]{example.gauss.graph}
  \spy on (0.6,-0.5) in node [left] at (7,1);
\end{tikzpicture}
```



12.19 Template 'database sidewaysportrait'


N 2017-09-15

template=database sidewaysportrait

This style is based on `/gtr/processing`^{→P.138}=database, sets `/gtr/database format`^{→P.174}=medium and `/gtr/timeflow`^{→P.80}=left.


In contrast to **database sideways** (Section 12.17 on page 286), portraits are drawn, if present.

```
\begin{genealogypicture}
[template=database sidewaysportrait]
input{example.database.graph}
\end{genealogypicture}
```



The next example uses the graph data from Section 2.3.5 on page 39.

```
\begin{genealogypicture}[template=database sidewaysportrait,
tikzpicture={scale=0.4,transform shape}]
input{example.gauss.graph}
\end{genealogypicture}
```



12.20 Template 'database sidewaysportrait reduced'


```
template=database sidewaysportrait reduced
```

N 2017-09-15

This style is identical to `database sidewaysportrait` (Section 12.19 on page 289), but every size property is scaled by factor $\frac{1}{10}$. See Section 12.10 on page 277 for more explanations.

The following example uses the graph data from Section 2.3.5 on page 39.

```
\begin{tikzpicture}[
  spy using outlines={circle, magnification=10, size=5cm, connect spies}]
  \genealogytreeinput[template=database sidewaysportrait reduced]{example.gauss.graph}
  \spy on (-0.2,-0.5) in node [left] at (7,1);
\end{tikzpicture}
```



12.21 Template 'database relationship'

template=database relationship

This style is based on `/gtr/processing→P.138=database`, sets `/gtr/database format→P.174=medium no marriage` and `/gtr/timeflow→P.80=down`.

This template is intended to be used for diagrams which show the relationship of a person X to a person Y with common ancestors. If `/gtr/database/image→P.166` is present, the corresponding image is inserted.

```
\begin{genealogypicture}[ template=database relationship, node size=7cm ]
child{
  g{male,
    name={\pref{Johann} \pref{Carl Friedrich} \surn{Gau\ss{}}},
    birth={1777-04-30}{Braunschweig (Niedersachsen)},
    death={1855-02-23}{G\"ottingen (Niedersachsen)},
    profession={Mathematiker, Astronom, Geod\"at und Physiker},
    image={Carl_Friedrich_Gauss.jpg},
  }
  p{female,
    name={\pref{Johanna} Elisabeth Rosina \surn{Osthoff}},
    birth={1780-05-08}{Braunschweig (Niedersachsen)},
    marriage={1805-10-09}{Braunschweig (Niedersachsen)},
    death={1809-10-11}{G\"ottingen (Niedersachsen)},
    comment={Wei\ss{gerberstochter}},
  }
  child{
    g{male,
      name={\pref{Carl} Joseph \surn{Gau\ss{}}},
      birth={1806-08-21}{Braunschweig (Niedersachsen)},
      death={1873-07-04}{Hannover (Niedersachsen)},
    }
    c{ female, name={Person X} }
  }
  c{ female, name={Person Y} }
}
\end{genealogypicture}
```



Johann Carl Friedrich Gauß
 ★ 30. Apr. 1777 in Braunschweig (Niedersachsen)
 † 23. Feb. 1855 in Göttingen (Niedersachsen)
Mathematiker, Astronom, Geodät und Physiker.

Johanna Elisabeth Rosina Osthoff
 ★ 8. May 1780 in Braunschweig (Niedersachsen)
 † 11. Oct. 1809 in Göttingen (Niedersachsen)
Weißgerberstochter.

Carl Joseph Gauß
 ★ 21. Aug. 1806 in Braunschweig (Niedersachsen)
 † 4. Jul. 1873 in Hannover (Niedersachsen)

Person Y

Person X

12.22 Template 'ahnentafel 3'

template=ahnentafel 3

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/timeflow→P.80=left`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with three generations of ancestors. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

```
\begin{genealogypicture}[template=ahnentafel 3,empty name text={},
autofill parents male female=3,
date format=d mon yyyy
]
parent{
  g{male,name=\pref{Frederik} \surn{Smith},
    birth={1900-01-01}{New York},death={1970-01-01}{New York},
    marriage={1929-01-01}{New York},comment={Used Cars Salesman}}
  parent{
    g{male,name=\pref{Ernest} \surn{Smith},
      birth={1870-02-02}{London},death={1940-02-02}{London},
      marriage={1899-02-02}{London},comment={Milkman}}
    parent{
      g{male,name=\pref{Dominik} \surn{Schmidt},
        birth={1840-03-03}{Berlin},death={1910-03-03}{London},
        marriage={1869-03-03}{Berlin},comment={Baker}}
      p{male,name=\pref{Christian} \surn{Schmied},
        birth={1810-04-04}{Vienna},death={1870-04-04}{Vienna},
        marriage={1839-04-04}{Vienna},comment={Blacksmith}}
    }
  }
}
\end{genealogypicture}
```


Frederik SMITH
★ 1 Jan 1900 in New York
⌘ 1 Jan 1929 in New York
† 1 Jan 1970 in New York
Used Cars Salesman.

Ernest SMITH
★ 2 Feb 1870 in London
⌘ 2 Feb 1899 in London
† 2 Feb 1940 in London
Milkman.

Dominik SCHMIDT
★ 3 Mar 1840 in Berlin
⌘ 3 Mar 1869 in Berlin
† 3 Mar 1910 in London
Baker.

Christian SCHMIED
★ 4 Apr 1810 in Vienna
⌘ 4 Apr 1839 in Vienna
† 4 Apr 1870 in Vienna
Blacksmith.


12.23 Template 'ahnentafel 4'

template=ahnentafel 4

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/timeflow→P.80=left`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with four generations of ancestors. One should apply only **parent**, **p**, and **g** constructs which gives a binary tree. Since the first parent generation is shifted, the diagram should always contain mother and father of the proband to avoid overlapping.

```
\begin{genealogypicture}[template=ahnentafel 4,empty name text={},
  autofill parents male female=4,
  date format=d mon yyyy
]
  parent{
    g{male,name=\pref{Frederik} \surn{Smith},
      birth={1900-01-01}{New York},death={1970-01-01}{New York},
      marriage={1929-01-01}{New York},comment={Used Cars Salesman}}
    parent{
      g{male,name=\pref{Ernest} \surn{Smith},
        birth={1870-02-02}{London},death={1940-02-02}{London},
        marriage={1899-02-02}{London},comment={Milkman}}
      parent{
        g{male,name=\pref{Dominik} \surn{Schmidt},
          birth={1840-03-03}{Berlin},death={1910-03-03}{London},
          marriage={1869-03-03}{Berlin},comment={Baker}}
        parent{
          g{male,name=\pref{Christian} \surn{Schmied},
            birth={1810-04-04}{Vienna},death={1870-04-04}{Vienna},
            marriage={1839-04-04}{Vienna},comment={Blacksmith}}
          p{male,name=\pref{Bartholom"aus} \surn{Schmid},
            birth={1780-05-05}{Eger},death={1840-05-05}{Eger},
            marriage={1809-05-05}{Eger},comment={Blacksmith}}
        }
      }
    }
  }
\end{genealogypicture}
```



12.24 Template 'ahnentafel 5'

template=ahnentafel 5

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/timeflow→P.80=left`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with five generations of ancestors. One should apply only **parent**, **p**, and **g** constructs which gives a binary tree. Since the first parent generation is shifted, the diagram should always contain mother and father of the proband to avoid overlapping.

```
\begin{genealogypicture}[template=ahnentafel 5,empty name text={},
autofill parents male female=5,
date format=d mon yyyy
]
parent{
  g{male,name=\pref{Frederik} \surn{Smith},
    birth={1900-01-01}{New York},death={1970-01-01}{New York},
    marriage={1929-01-01}{New York},comment={Used Cars Salesman}}
  parent{
    g{male,name=\pref{Ernest} \surn{Smith},
      birth={1870-02-02}{London},death={1940-02-02}{London},
      marriage={1899-02-02}{London},comment={Milkman}}
    parent{
      g{male,name=\pref{Dominik} \surn{Schmidt},
        birth={1840-03-03}{Berlin},death={1910-03-03}{London},
        marriage={1869-03-03}{Berlin},comment={Baker}}
      parent{
        g{male,name=\pref{Christian} \surn{Schmied},
          birth={1810-04-04}{Vienna},death={1870-04-04}{Vienna},
          marriage={1839-04-04}{Vienna},comment={Blacksmith}}
        parent{
          g{male,name=\pref{Bartholom\"aus} \surn{Schmid},
            birth={1780-05-05}{Eger},death={1840-05-05}{Eger},
            marriage={1809-05-05}{Eger},comment={Blacksmith}}
          p{male,name=\pref{Abraham} \surn{Schmid},
            birth={1750-06-06}{St. Joachimsthal},death={1810-06-06}{Eger},
            marriage={1779-06-06}{Eger},comment={Miner}}
        }
      }
    }
  }
}
\end{genealogypicture}
```

Frederik SMITH
★ 1 Jan 1900 in New York
⌘ 1 Jan 1929 in New York
† 1 Jan 1970 in New York
Used Cars Salesman.

Ernest SMITH
★ 2 Feb 1870 in London
⌘ 2 Feb 1899 in London
† 2 Feb 1940 in London
Milkman.

Dominik SCHMIDT
★ 3 Mar 1840 in Berlin
⌘ 3 Mar 1869 in Berlin
† 3 Mar 1910 in London
Baker.

Christian SCHMIED
★ 4 Apr 1810 in Vienna
⌘ 4 Apr 1839 in Vienna
† 4 Apr 1870 in Vienna
Blacksmith.

Bartholomäus SCHMID
★ 5 May 1780 in Eger,
⌘ 5 May 1809 in Eger,
† 5 May 1840 in Eger.
Blacksmith.

Abraham SCHMID, ★ 6 Jun 1750 in St. Joachimsthal, ⌘ 6 Jun 1779 in Eger, † 6 Jun 1810 in Eger.

12.25 Template 'a4paper 3'

N 2022-03-16


```
template=a4paper 3
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with three generations of ancestors to be printed on landscape A4 paper. One should apply only **parent**, **p**, and **g** constructs which gives a binary tree.

The graph is automatically filled to three generations by `/gtr/autofill parents male female*`^{P.133} and also pruned to three generations. The total size is 283 mm:196 mm with intended use to be centered on a 297 mm:210 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable when printed on A4 sized paper.

```
\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[a4paper,landscape]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\genealogytreeinput[template=a4paper 3]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}
```



12.26 Template 'a4paper 4'

N 2022-03-16


template=a4paper 4

This style is based on `/gtr/processing`^{→P.138}=`database` and sets `/gtr/database format`^{→P.174}=`full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with four generations of ancestors to be printed on landscape A4 paper. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to four generations by `/gtr/autofill parents male female*`^{→P.133} and also pruned to four generations. The total size is 283 mm : 196 mm with intended use to be centered on a 297 mm : 210 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable when printed on A4 sized paper.

```
\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[a4paper,landscape]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\genealogytreeinput[template=a4paper 4]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}
```



12.27 Template 'a3paper 5'

N 2022-03-16


template=a3paper 5

This style is based on `/gtr/processing`^{→P.138}=`database` and sets `/gtr/database format`^{→P.174}=`full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with five generations of ancestors to be printed on landscape A3 paper. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to five generations by `/gtr/autofill parents male female*`^{→P.133} and also pruned to five generations. The total size is 406 mm:283 mm with intended use to be centered on a 420 mm:297 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable when printed on A3 sized paper.

```
\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[a3paper,landscape]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\genealogytreeinput[template=a3paper 5]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}
```



12.28 Template 'letterpaper 3'

N 2022-03-16

```
template=letterpaper 3
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with three generations of ancestors to be printed on landscape letter paper. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to three generations by `/gtr/autofill parents male female*→P.133` and also pruned to three generations. The total size is 10.5in:8in with intended use to be centered on a 11in:8.5in paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable when printed on letter sized paper.

12.29 Template 'letterpaper 4'

N 2022-03-16

```
template=letterpaper 4
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with four generations of ancestors to be printed on landscape A4 paper. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to four generations by `/gtr/autofill parents male female*→P.133` and also pruned to four generations. The total size is 10.5in:8in with intended use to be centered on a 11in:8.5in paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable when printed on letter sized paper.

12.30 Template 'display 16:9 3'

N 2022-03-16


template=display 16:9 3

This style is based on `/gtr/processing`^{→P.138}=`database` and sets `/gtr/database format`^{→P.174}=`full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with three generations of ancestors to be shown on a 16:9 display. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to three generations by `/gtr/autofill parents male female*`^{→P.133} and also pruned to three generations. The total size is 316 mm : 176 mm with intended use to be centered on a 320 mm : 180 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable on a Full HD screen with 1920×1080 pixels.

```
\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[paperwidth=320mm,paperheight=180mm]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\genealogytreeinput[template=display 16:9 3]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}
```



12.31 Template 'display 16:9 4'

N 2022-03-16


template=display 16:9 4

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with four generations of ancestors to be shown on a 16:9 display. One should apply only **parent**, **p**, and **g** constructs which gives a binary tree.

The graph is automatically filled to four generations by `/gtr/autofill parents male female*`^{→P.133} and also pruned to four generations. The total size is 316 mm : 176 mm with intended use to be centered on a 320 mm : 180 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable on a Full HD screen with 1920×1080 pixels.

```
\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[paperwidth=320mm,paperheight=180mm]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\genealogytreeinput[template=display 16:9 4]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}
```



12.32 Template 'display 16:9 5'

N 2022-03-16


template=display 16:9 5

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with five generations of ancestors to be shown on a 16:9 display. One should apply only **parent**, **p**, and **g** constructs which gives a binary tree.

The graph is automatically filled to five generations by `/gtr/autofill parents male female→P.133` and also pruned to five generations. The total size is 316 mm:176 mm with intended use to be centered on a 320 mm:180 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable on a UHD screen with 3840×2180 pixels (4K).

```
\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[paperwidth=320mm,paperheight=180mm]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\genealogytreeinput[template=display 16:9 5]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}
```



12.33 Template 'display 16:10 3'

N 2022-03-16

```
template=display 16:10 3
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with three generations of ancestors to be shown on a 16:10 display. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to three generations by `/gtr/autofill parents male female→P.133` and also pruned to three generations. The total size is 316 mm : 196 mm with intended use to be centered on a 320 mm : 200 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable on a WUXGA screen with 1920×1200 pixels.

12.34 Template 'display 16:10 4'

N 2022-03-16

```
template=display 16:10 4
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with four generations of ancestors to be shown on a 16:9 display. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to four generations by `/gtr/autofill parents male female→P.133` and also pruned to four generations. The total size is 316 mm : 196 mm with intended use to be centered on a 320 mm : 200 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable on a WUXGA screen with 1920×1200 pixels.

12.35 Template 'display 16:10 5'

N 2022-03-16

```
template=display 16:10 5
```

This style is based on `/gtr/processing→P.138=database` and sets `/gtr/database format→P.174=full marriage below`.

Note that this style is very restrictive and its sole intended use is to easily set up predefined ancestor tables with five generations of ancestors to be shown on a 16:10 display. One should apply only `parent`, `p`, and `g` constructs which gives a binary tree.

The graph is automatically filled to five generations by `/gtr/autofill parents male female→P.133` and also pruned to five generations. The total size is 316 mm : 196 mm with intended use to be centered on a 320 mm : 200 mm paper (border adaption see Section 12.36 on page 306). Typically, the content should be readable on a QWUXGA screen with 3840×2400 pixels.

12.36 Border Size Options

The following border size options can be used to adapt the templates which are listed below. Setting `/gtr/template horizontal border` and `/gtr/template vertical border` to 0 mm means that, e.g. `a4paper 4` fills the complete area of an A4 sized paper. The options also accept negative lengths which leads to a magnification.

`/gtr/template horizontal border=<length>` (template specific)

N 2022-03-16

For the preceding templates which target a fixed size on paper or screen, the horizontal border `<length>` can be changed *after* the template is selected. Applicable templates with their default values are:

<code>a4paper 3</code>	7 mm
<code>a4paper 4</code>	7 mm
<code>a3paper 5</code>	7 mm
<code>letterpaper 3</code>	0.25 in
<code>letterpaper 4</code>	0.25 in
<code>display 16:9 3</code>	2 mm
<code>display 16:9 4</code>	2 mm
<code>display 16:9 5</code>	2 mm
<code>display 16:10 3</code>	2 mm
<code>display 16:10 4</code>	2 mm
<code>display 16:10 5</code>	2 mm

`/gtr/template vertical border=<length>` (template specific)

N 2022-03-16


For the preceding templates which target a fixed size on paper or screen, the vertical border `<length>` can be changed *after* the template is selected. Applicable templates with their default values are:

<code>a4paper 3</code>	7 mm
<code>a4paper 4</code>	7 mm
<code>a3paper 5</code>	7 mm
<code>letterpaper 3</code>	0.25 in
<code>letterpaper 4</code>	0.25 in
<code>display 16:9 3</code>	2 mm
<code>display 16:9 4</code>	2 mm
<code>display 16:9 5</code>	2 mm
<code>display 16:10 3</code>	2 mm
<code>display 16:10 4</code>	2 mm
<code>display 16:10 5</code>	2 mm

```


\documentclass{article}
\usepackage{notocondensed}
\usepackage[ngerman]{babel}
\usepackage[a4paper,landscape]{geometry}
\usepackage[all]{genealogytree}
\gtrset{language=german,date format=d.m.yyyy}
\pagestyle{empty}
\begin{document}
\begin{tcolorbox}[blanker,spread,halign=center,valign=center]
\begin{tikzpicture}
\colorlet{gtr_Male_Frame}{black}
\colorlet{gtr_Male_Background}{white}
\colorlet{gtr_Female_Frame}{black}
\colorlet{gtr_Female_Background}{white}
\genealogytreeinput[
  template = a4paper 3,
  template horizontal border = 60mm,
  template vertical border = 1mm
]{example.neumann.graph}
\end{tikzpicture}
\end{tcolorbox}
\end{document}

```



12.37 Predefined Colors of the Library

The following colors are predefined. They are used as default colors in some templates.




12.38 Auxiliary Control Sequences

Also see Section 5.15 on page 132 for adding ancestors automatically.

`\gtrparent1`

This control sequence inserts a pair of parents with content male and female.


```
\begin{genealogypicture}
[template=symbol nodes]
parent{
  g{male}
  insert{\gtrparent1}
}
\end{genealogypicture}
```



`\gtrparent2`

This control sequence inserts two generations of parents with content male and female.


```
\begin{genealogypicture}
[template=symbol nodes]
parent{
  g{male}
  insert{\gtrparent2}
}
\end{genealogypicture}
```



`\gtrparent3`

This control sequence inserts three generations of parents with content male and female.


```
\begin{genealogypicture}
[template=symbol nodes]
parent{
  g{male}
  insert{\gtrparent3}
}
\end{genealogypicture}
```



`\gtrparent4`

This control sequence inserts four generations of parents with content `male` and `female`.

```
\begin{genealogypicture}
[template=symbol nodes]
parent{
g{male}
insert{gtrparent4}
}
\end{genealogypicture}
```



`\gtrparent5`

This control sequence inserts five generations of parents with content `male` and `female`.

`\gtrparent6`

This control sequence inserts six generations of parents with content `male` and `female`.


`\gtrparent7`

This control sequence inserts seven generations of parents with content `male` and `female`.

`\gtrDrawSymbolicPortrait`

Inserts TikZ code to draw a symbolic portrait. The colors are frame and back color of a `tcolorbox`. Therefore, the intended application is inside a `tcolorbox`.

```
\begin{tcolorbox}[enhanced,width=2.5cm,height=4cm,
title=Test,halign title=center,
colframe=green!25!black,colback=yellow!50,
underlay={\begin{tcbclipinterior}%
\path[fill overzoom picture=\gtrDrawSymbolicPortrait]
(interior.south west) rectangle (interior.north east);
\end{tcbclipinterior}} ]
\end{tcolorbox}
```



13

Fancharts: Library LIB fanchart

The library is loaded by a package option or inside the preamble by:

```
\gtruselibrary{fanchart}
```

13.1 Fan Chart Diagrams

A *fan chart* is a specialized diagram which differs in many ways from all other graphs of the package. Especially, the the autolayout algorithm is replaced by another fixed layout algorithm. Thus, most geometry related options are also replaced by special ones for the fan chart.

- Only **parent** trees without children can be used as $\langle tree\ contents \rangle$ for a fan chart. Nevertheless, children (**c**) may be present inside the graph, but are not displayed.
- The nodes are displayed as segments of a circle, but the node text still is set inside a rectangular (invisible) box which is fitted to a segment of circle. The box dimensions are computed automatically to inscribe the box with maximum area. See Section 13.2 on page 314 for segment dimensions.
- Node data processing is limited to database processing, see Chapter 7 on page 161. Other processings are not supported.
- All customization options for database nodes are feasible. Only the node background settings are ignored and are replaced by segment coloring, see Section 13.4 on page 322.
- Templates from the LIB **templates** library are not applicable for obvious reasons, but there are some fan chart templates instead, see Section 13.5 on page 335.


`\gtrfanchart` [*options*] {*tree contents*}

Draws a fan chart diagram according to the given *tree contents* controlled by the given *options*.

Note that *tree contents* has to be a **parent** tree (without children). `\gtrfanchart` corresponds to `\genealogytree`^{→ P.55} and has to be placed into a **tikzpicture** environment or a derived environment like `autosizetikzpicture`^{→ P.61}.

Database processing for the nodes is present.

```
\begin{autosizetikzpicture}{\linewidth}{}
\gtrfanchart[
  autofill parents male female=3,
  fanchart template=malefemale sober,
]
{
  parent{
    g{male,name=Proband}
    parent{
      g{male,name=Father}
      p{male,name=Grandfather}
      p{female,name=Grandmother}
    }
    p{female,name=Mother}
  }
}
\end{autosizetikzpicture}
```



Uses the content of the file denoted by `⟨file name⟩` to create a `\gtrfanchart`^{P.312} with the given `⟨options⟩`. See Section 15.4 on page 362 for the file of the following example.


```
\begin{autosizepicture}{\linewidth}{}
\gtrfanchartinput[
  autofill parents male female=3,
  fanchart template=colorwheel serious,
  fanchart text portrait=inwards,
  complemented phantom,
]
{example.neumann.graph}
\end{autosizepicture}
```



Steps for setting up a fan chart:

1. Decide on the number n of displayed generations (levels). In theory, the library supports up to 24 generations which means 16777216 segments on the outermost ring. In reality, \TeX memory limitations will force a distinct smaller number n .
2. Always use `/gtr/autofill parents male female`^{P.133} $=n$ or `/gtr/autofill parents female male`^{P.134} $=n$ to auto fill and restrict the number of generations to the desired level n , if your graph is not without gap. Expect deviations in placing male/female nodes otherwise. If visible gaps are preferred, an added `/gtr/complemented phantom`^{P.135} does the trick.
3. If a `/gtr/fanchart template`^{P.335} is to be used, it should be applied before other customization options, because a template sets a lot of options itself.
4. Adapt the geometry of the fan chart to your liking, see Section 13.2 on page 314. This also determines the size for the node text.
5. Possibly adapt the `/gtr/database format`^{P.174} in dependency of the `/gtr/level`^{P.109}, if outer nodes should contain more concise information than inner nodes.

13.2 Geometry Options



A (full) segment is shown inside a red frame above. It decomposes into a *core segment*, an optional *marker* area and an optional *gap*. The actual node box containing the node text is inscribed into the (core) segment.

/gtr/fanchart radii={ $\langle radius1 \rangle$, $\langle radius2 \rangle$,...} (initially 2.5cm,3.5cm,3cm) N 2020-06-05

Defines the radii of the fan chart rings as comma separated list of length values $\langle radius1 \rangle$, $\langle radius2 \rangle$, ... The last value of this list is taken for all following radii.

/gtr/fanchart inner offset={ $\langle offset1 \rangle$, $\langle offset2 \rangle$,...} (no default, initially 0mm) N 2020-06-05

Defines the inner offset values as comma separated list of length values $\langle offset1 \rangle$, $\langle offset2 \rangle$, ... The last value of this list is taken for all following inner offsets. For standard fan charts, the inner offset describes the *gap* between two rings.

/gtr/fanchart outer offset={ $\langle offset1 \rangle$, $\langle offset2 \rangle$,...} (no default, initially 0mm) N 2020-06-05

Defines the outer offset values as comma separated list of length values $\langle offset1 \rangle$, $\langle offset2 \rangle$, ... The last value of this list is taken for all following outer offsets. For standard fan charts, the outer offset describes the *marker* area of a segment.

/gtr/fanchart minor angle= $\langle angle \rangle$ (no default, initially -20) N 2020-06-05

Defines the minor $\langle angle \rangle$ of a fan chart. **/gtr/fanchart minor angle** has to be smaller than **/gtr/fanchart major angle**.

/gtr/fanchart major angle= $\langle angle \rangle$ (no default, initially 200) N 2020-06-05


Defines the major $\langle angle \rangle$ of a fan chart. **/gtr/fanchart major angle** has to be greater than **/gtr/fanchart minor angle**.

`/gtr/fanchart angles= $\langle \text{minor angle} \rangle : \langle \text{major angle} \rangle$`

(style, no default)

Style to set `/gtr/fanchart minor angle→P.314= $\langle \text{minor angle} \rangle$` and `/gtr/fanchart major angle→P.314= $\langle \text{major angle} \rangle$` .

```
\begin{autosize tikzpicture}{\linewidth}{6cm}
\gtrfanchart[
  fanchart angles=-20:80,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




`/gtr/fanchart open full`

(style)

Style to set `/gtr/fanchart minor angle→P.314=-180` and `/gtr/fanchart major angle→P.314=180` (full circle).

```
\begin{autosize tikzpicture}{\linewidth}{6cm}
\gtrfanchart[
  fanchart open full,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




`/gtr/fanchart open up= $\langle angle \rangle$`

(style, default 220)

N 2020-06-05

Style to set `/gtr/fanchart minor angle`^{→ P.314} and `/gtr/fanchart major angle`^{→ P.314} such that the fan chart opens direction up with the given opening $\langle angle \rangle$.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[
  fanchart open up=150,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




`/gtr/fanchart open down= $\langle angle \rangle$`

(style, default 220)

N 2020-06-05


Style to set `/gtr/fanchart minor angle`^{→ P.314} and `/gtr/fanchart major angle`^{→ P.314} such that the fan chart opens direction down with the given opening $\langle angle \rangle$.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[
  fanchart open down=270,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




Style to set `/gtr/fanchart minor angle`^{→ P. 314} and `/gtr/fanchart major angle`^{→ P. 314} such that the fan chart opens direction left with the given opening $\langle angle \rangle$.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[
  fanchart open left=200,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```



Style to set `/gtr/fanchart minor angle`^{→ P. 314} and `/gtr/fanchart major angle`^{→ P. 314} such that the fan chart opens direction right with the given opening $\langle angle \rangle$.


```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[
  fanchart open right=120,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




Style to set `/gtr/fanchart minor angle`^{→P.314} and `/gtr/fanchart major angle`^{→P.314} such that the width and height of the fan chart diagram has the same ratio as the given `<width>` and `<height>`. The result is either `/gtr/fanchart open up`^{→P.316} or `/gtr/fanchart open right`^{→P.317}. Also, `/gtr/fanchart text portrait`^{→P.321} or `/gtr/fanchart text landscape`^{→P.321} are adapted automatically.

- The graph is not resized, but the ratio is adapted.
- The root circle is *not* considered, but the outermost arc only.

```
\fbxsep0pt\fbx{\begin{autosizektikzpicture}{9cm}{6cm}
\gtrfanchart[
  fanchart open for=9 x 6,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosizektikzpicture}}
```



```
\fbxsep0pt\fbx{\begin{autosizektikzpicture}{4cm}{6cm}
\gtrfanchart[
  fanchart open for=4 x 6,
  autofill parents male female=3,
  fanchart template=wave opulent,
]
{ parent{ g{} } }
\end{autosizektikzpicture}}
```




When TikZ calculates the bounding box for an arc, it takes the start, end and control points of the Bezier curves into account. Since the control points usually lie outside the arc, the resulting bounding box may be too large for some situations. To avoid the problem, `/gtr/fanchart reset bounds` removes the summarized TikZ bounding box after drawing the fan chart and computes a new bounding box.

This removes the mentioned problem but introduces new caveats:

- The computed bounding box presumes a full outermost arc of the fan chart. If some parts are missing, their space is taken into account however. You may call this a drawback or you may call this a feature.
- The draw line width of the outermost arc is not considered. But the resulting bounding box is extended in all directions by `/gtr/fanchart bounds border` to cope with the missing half line width.
- Every bounding box share of any TikZ path element *before* `\gtrfanchart`^{P.312} is also removed.
- TikZ path elements *after* `\gtrfanchart`^{P.312} are added as usually to the TikZ bounding box.

```
Note the white space left and right.\par
\fbboxsep0pt\fbbox{\begin{autosizetikzpicture}{9cm}{6cm}
\gtrfanchart[
  fanchart open for=9 x 6,
  autofill parents male female=3,
  fanchart template=wave opulent,
  fanchart reset bounds=false,
]
{ parent{ g{} } }
\end{autosizetikzpicture}}
```

Note the white space left and right.



If `/gtr/fanchart reset bounds` is true, the resulting bounding box is extended in all directions by `<length>`.


13.3 Segment Text Options

`/gtr/fanchart landscape from level=<number>` (no default, initially 5)

N 2020-06-05

The node text boxes are fitted into the (core) segments in portrait orientation (seen from the center) for inner rings (lower levels) and in landscape orientation for outer rings (higher levels). The given `<number>` denotes the first level for landscape orientation.


```
\begin{autosize tikzpicture}{\linewidth}{}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=colorwheel serious,
  fanchart text portrait=inwards,
  fanchart landscape from level=2
]
{example.neumann.graph}
\end{autosize tikzpicture}
```



Feasible values for `<selection>` are

- `inwards`: Textflow for portrait in direction of the center.
- `outwards`: Textflow for portrait in direction of the rim.
- `auto`: Upper half `inwards`, lower half `outwards`.


```
\begin{autosizepicture}{\linewidth}{6cm}
\gtrfanchartinput[
  autofill parents male female=2, fanchart template=colorwheel serious,
  fanchart text portrait=outwards,
]
{example.neumann.graph}
\end{autosizepicture}
```



Feasible values for `<selection>` are

- `clockwise`: Textflow for landscape clockwise.
- `counterclockwise`: Textflow for landscape counterclockwise.
- `auto`: Left half `counterclockwise`, right half `clockwise`.

```
\begin{autosizepicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=2,
  fanchart template=colorwheel serious,
  fanchart open full, fanchart landscape from level=2,
  fanchart text landscape=clockwise,
]
{example.neumann.graph}
\end{autosizepicture}
```




13.4 Color and Style Options

`/gtr/fanchart boundary color=<color>` (no default, initially gray!50)

N 2020-06-05

All fan chart segments are framed with a line in the given *<color>*. This color is also available with the name `gtrfanchartboundary`.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=3,
  fanchart template      = spartan,
  fanchart boundary color = red,
]
{ parent{ g{} } }
\end{autosizetikzpicture}
```




`/gtr/fanchart boundary width=<length>` (no default, initially 0.4pt)

N 2020-06-16


Sets the (base) line width for the boundary line of each segment. This line width is reduced by some heuristic algorithm for very small outer segments.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=3,
  fanchart template      = wave opulent,
  fanchart boundary width = 2mm,
]
{ parent{ g{} } }
\end{autosizetikzpicture}
```




Sets TikZ *⟨options⟩* for the root circle path.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=1,
  fanchart template = spartan,
  fanchart root style = {inner color=red!20,outer color=blue!20},
]
{ parent{ g{name=root} } }
\end{autosizetikzpicture}
```



Sets root to display a male or female style according to */gtr/fanchart male style*^{→ P. 334}, etc.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=1,
  fanchart template = spartan,
  fanchart root malefemale,
]
{ parent{ g{female,name=root} } }
\end{autosizetikzpicture}
```




`/gtr/fanchart segment style={\options}`

(no default)

N 2020-06-05

Sets TikZ *\options* for a (core) segment path.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template      = spartan,
  fanchart segment style = {top color=red!20,bottom color=blue!20},
]
{ parent{ g{} } }
\end{autosizetikzpicture}
```




`/gtr/fanchart segment malefemale`

(style, initially set)

N 2020-06-05


Sets segment to display a male or female style according to `/gtr/fanchart male style`^{→P.334}, etc.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template      = spartan,
  fanchart segment malefemale,
]
{ parent{ g{} } }
\end{autosizetikzpicture}
```




Sets segment to display a color depending on the relation status of a person set by /gtr/database/relation^{→P.167}. The colors are defined by /gtr/fanchart ancestor style^{→P.334}, etc.

```
\begin{autosizepicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart text portrait = inwards,
  fanchart segment relation,
]
{example.neumann.graph}
\end{autosizepicture}
```




Sets segment to display a brightened wave spectrum color depending on the angle of the segment. See [2] for the wave color model.

```
\begin{autosizepicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart segment wave,
]
{ parent{ g{} } }
\end{autosizepicture}
```




Sets segment to display a brightened color wheel color depending on the angle of the segment. See [2] for the `tHsb` color model and its customization by changing `\rangeHsb`.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart segment colorwheel,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




Sets segment to display a brightened color series color depending on the level of the current segment. The color is taken from a predefined color series `fanchart` which can be redefined. See [2] for defining color series.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[ autofill parents male female=6,
  fanchart template = spartan,
  fanchart segment radial,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




Sets TikZ $\langle options \rangle$ for a marker path.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template      = spartan,
  fanchart outer offset  = {5mm},
  fanchart marker style  = {top color=red!20,bottom color=blue!20},
]
{ parent{ g{} } }
\end{autosizetikzpicture}
```




Sets marker to display a male or female style according to `/gtr/fanchart male style→P.334`, etc.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template      = spartan,
  fanchart outer offset = {5mm}, fanchart text portrait=inwards,
  fanchart male style={fill=blue!50}, fanchart female style={fill=red!50},
  fanchart marker malefemale, ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




Sets marker to display a color depending on the relation status of a person set by /gtr/database/relation^{→P.167}. The colors are defined by /gtr/fanchart ancestor style^{→P.334}, etc.

```
\begin{autosizepicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart outer offset = {5mm}, fanchart text portrait = inwards,
  fanchart marker relation, ]
{example.neumann.graph}
\end{autosizepicture}
```




Sets marker to display a wave spectrum color depending on the angle of the segment. See [2] for the wave color model.

```
\begin{autosizepicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart outer offset = {5mm},
  fanchart marker wave,
]
{ parent{ g{} } }
\end{autosizepicture}
```




Sets marker to display a color wheel color depending on the angle of the segment. See [2] for the tHsb color model and its customization by changing `\rangeHsb`.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart outer offset = {5mm},
  fanchart marker colorwheel,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```



Sets marker to display a color series color depending on the level of the current segment. The color is taken from a predefined color series `fanchart` which can be redefined. See [2] for defining color series.

```
\begin{autosize tikzpicture} {\linewidth} {6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart outer offset = {5mm},
  fanchart marker radial,
]
{ parent{ g{} } }
\end{autosize tikzpicture}
```




`/tikz/gtr set color wave=<name>`

(no default)

N 2020-06-05

Defines the color $\langle name \rangle$ to store the wave spectrum color depending on the angle of the current segment. This option can be used inside `/gtr/fanchart segment style`^{P.324} or `/gtr/fanchart marker style`^{P.327}. See [2] for the wave color model.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart segment style =
  {
    gtr set color wave = mycolor,
    top color           = mycolor!50!white,
    bottom color        = mycolor!50!gray,
  },
]
{ parent{ g{} } }
\end{autosizetikzpicture}
```



`/tikz/gtr set color colorwheel=<name>`

(no default)

N 2020-06-05

Defines the color $\langle name \rangle$ to store the color wheel color depending on the angle of the current segment. This option can be used inside `/gtr/fanchart segment style`^{P.324} or `/gtr/fanchart marker style`^{P.327}. See [2] for the `tHsb` color model and its customization by changing `\rangeHsb`. This also includes reduction to e.g. two or four colors for branches:

```
% example for a color wheel definition with 2 colors
\def\rangetHsb{0.05,240;179.95,240;180.05,0;359.95,0}
```

```
% example for a color wheel definition with 4 colors
\def\rangetHsb{0.05,240;89.95,240;90.05,120;179.95,120;180.05,60;
269.95,60;270.05,0;359.95,0}
```

`/tikz/gtr set color series=<name>`

(no default)


N 2020-06-18

Defines the color $\langle name \rangle$ to store the color wheel color depending on the level of the current segment. This option can be used inside `/gtr/fanchart segment style`^{P.324} or `/gtr/fanchart marker style`^{P.327}. The color is taken from a predefined color series `fanchart` which can be redefined. See [2] for defining color series.

/gtr/fanchart complemented segment style={⟨options⟩} (no default, initially empty)

The given TikZ ⟨options⟩ are added to the options given by **/gtr/fanchart segment style**^{→P.324}, if the current segment is a complemented segment (by autofill).


```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=2,
  fanchart template = malefemale sober,
  fanchart complemented segment style = { shade=none, fill=gtrfanchartboundary!5 },
]
{ parent{ g{male,name=A}
  parent{ g{female,name=B} p{male,name=C} } } }
\end{autosizetikzpicture}
```



/gtr/fanchart complemented marker style={⟨options⟩} (no default, initially empty)

The given TikZ ⟨options⟩ are added to the options given by **/gtr/fanchart marker style**^{→P.327}, if the current segment is a complemented segment (by autofill).

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchart[ autofill parents male female=2,
  fanchart template = colorwheel serious,
  fanchart complemented marker style = { fill=gtrfanchartboundary!20 },
]
{ parent{ g{male,name=A}
  parent{ g{female,name=B} p{male,name=C} } } }
\end{autosizetikzpicture}
```




`/gtr/fanchart segment style for levels={⟨level list⟩}{⟨options⟩}` (no default)

N 2020-06-18

The given TikZ `⟨options⟩` are added to the options given by `/gtr/fanchart segment style`^{→P.324}, if the current level is inside the given comma separated `⟨level list⟩`.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart text portrait = inwards,
  fanchart segment style for levels = {2,4}{fill=red!10},
]
{example.neumann.graph}
\end{autosizetikzpicture}
```




`/gtr/fanchart marker style for levels={⟨level list⟩}{⟨options⟩}` (no default)

N 2020-06-18


The given TikZ `⟨options⟩` are added to the options given by `/gtr/fanchart marker style`^{→P.327}, if the current level is inside the given comma separated `⟨level list⟩`.

```
\begin{autosizetikzpicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart outer offset = {5mm}, fanchart text portrait = inwards,
  fanchart marker style for levels = {2,4}{fill=red!50!gray!50},
]
{example.neumann.graph}
\end{autosizetikzpicture}
```




The given TikZ `⟨options⟩` are added to the options given by `/gtr/fanchart segment style`^{→P.324}, if the current node `/gtr/id`^{→P.92} is inside the given comma separated `⟨id list⟩`.

```
\begin{autosizeetikzpicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart text portrait = inwards,
  fanchart segment style for ids = {NeumAndr1605,MichNikl1530}{fill=blue!10} ]
{example.neumann.graph}
\end{autosizeetikzpicture}
```



The given TikZ `⟨options⟩` are added to the options given by `/gtr/fanchart marker style`^{→P.327}, if the current node `/gtr/id`^{→P.92} is inside the given comma separated `⟨id list⟩`.

```
\begin{autosizeetikzpicture}{\linewidth}{6cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart template = spartan,
  fanchart outer offset = {5mm}, fanchart text portrait = inwards,
  fanchart marker style for ids = {NeumAndr1605,MichNikl1530}
  {fill=blue!50!gray!50} ]
{example.neumann.graph}
\end{autosizeetikzpicture}
```



<code>/gtr/fanchart male style={\langle options \rangle}</code>	(no default, initially top color=blue!1!white,bottom color=blue!6!white)	N 2020-06-05
<code>/gtr/fanchart female style={\langle options \rangle}</code>	(no default, initially top color=red!1!white,bottom color=red!6!white)	N 2020-06-05
<code>/gtr/fanchart neuter style={\langle options \rangle}</code>	(no default, initially top color=gray!1!white,bottom color=gray!6!white)	N 2020-06-05

Define the styles used by `/gtr/fanchart segment malefemale`^{→P.324} and `/gtr/fanchart marker malefemale`^{→P.327} with the given TikZ $\langle options \rangle$.

<code>/gtr/fanchart ancestor style={\langle options \rangle}</code>	(no default, initially fill=red!50!gray!50)	N 2020-06-05
<code>/gtr/fanchart descendant style={\langle options \rangle}</code>	(no default, initially fill=red!50!gray!50)	N 2020-06-05
<code>/gtr/fanchart sibling style={\langle options \rangle}</code>	(no default, initially fill=blue!50!gray!50)	N 2020-06-05
<code>/gtr/fanchart unrelated style={\langle options \rangle}</code>	(no default, initially fill=gray!15)	N 2020-06-05

Define the styles used by `/gtr/fanchart marker relation`^{→P.328} and `/gtr/fanchart segment relation`^{→P.325} with the given TikZ $\langle options \rangle$.

13.5 Templates


N 2020-06-05

`/gtrfanchart template=<name>` (style, no default)

Sets a predefined style *<name>* for a fan chart graph. A template does not provide new functionality, but combines various options for specific fan charts, e.g. used inside this documentation. It serves as a shortcut. If a template is used, it is recommended to apply it at the begin of the option list. Further customization options can be added behind.


13.5.1 Template 'spartan'

```
\begin{autosize tikzpicture} {\linewidth} {7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=spartan,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




13.5.2 Template 'malefemale sober'

```
\begin{autosizepicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=malefemale sober,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizepicture}
```




13.5.3 Template 'malefemale relation'

```
\begin{autosizepicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=malefemale relation,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizepicture}
```




13.5.4 Template 'colorwheel sober'

```
\begin{autosizetikzpicture}\{\linewidth\}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=colorwheel sober,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizetikzpicture}
```




13.5.5 Template 'colorwheel serious'

```
\begin{autosizetikzpicture}\{\linewidth\}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=colorwheel serious,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizetikzpicture}
```




13.5.6 Template 'colorwheel malefemale'

```
\begin{autosize tikzpicture} {\linewidth} {7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
fanchart template=colorwheel malefemale,
fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




13.5.7 Template 'colorwheel rich'

```
\begin{autosize tikzpicture} {\linewidth} {7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
fanchart template=colorwheel rich,
fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




13.5.8 Template 'colorwheel opulent'

```
\begin{autosize tikzpicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
fanchart template=colorwheel opulent,
fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




13.5.9 Template 'wave sober'

```
\begin{autosize tikzpicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
fanchart template=wave sober,
fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




13.5.10 Template 'wave serious'

```
\begin{autosizepicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=wave serious,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizepicture}
```




13.5.11 Template 'wave malefemale'

```
\begin{autosizepicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=wave malefemale,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizepicture}
```




13.5.12 Template 'wave rich'

```
\begin{autosizepicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=wave rich,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizepicture}
```




13.5.13 Template 'wave opulent'

```
\begin{autosizepicture}{\linewidth}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=wave opulent,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizepicture}
```




13.5.14 Template 'radial sober'

```
\begin{autosizetikzpicture}\{\linewidth\}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=radial sober,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizetikzpicture}
```




13.5.15 Template 'radial serious'

```
\begin{autosizetikzpicture}\{\linewidth\}{7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=radial serious,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosizetikzpicture}
```




13.5.16 Template 'radial malefemale'

```
\begin{autosize tikzpicture} {\linewidth} {7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
fanchart template=radial malefemale,
fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```




13.5.17 Template 'radial rich'

```
\begin{autosize tikzpicture} {\linewidth} {7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
fanchart template=radial rich,
fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```



13.5.18 Template 'radial opulent'

```
\begin{autosize tikzpicture} {\linewidth} {7.5cm}
\gtrfanchartinput[ autofill parents male female=3,
  fanchart template=radial opulent,
  fanchart text portrait=inwards ]
{example.neumann.graph}
\end{autosize tikzpicture}
```



13.6 Advanced Customization

This section is an API description for people who want to customize the fan chart diagrams even further. It is not intended for “the normal user”.

The `lib fanchart` library is written mainly in `expl3`, but options are defined with `pgfkeys` from `TikZ`.

The library redefines the drawing capabilities of `genealogytree`, but parsing and boxing the node contents is done by common routines of the package. The node content and settings are predominantly not available for segment drawing inside the library with few exceptions:

- `\gtrDBsex`: set by `/gtr/database/sex` ^{→ P.165}.
- `\gtrDBrelation`: set by `/gtr/database/relation` ^{→ P.167}.
- `\gtrcomplemented`: set as `true` or `false` by `/gtr/autofill parents male female` ^{→ P.133} and friends.

The following options can be used to replace the drawing procedures.

N 2020-06-05 `/gtr/fanchart-segment-definition={⟨code⟩}` (no default)

Used to set up the core segment. This `⟨code⟩` is called after the segment initialization and before the segment is drawn. `/gtr/fanchart segment style` ^{→ P.324} sets the `⟨code⟩` to `\getree_fanchart_set_segment_style:n` ^{→ P.346} `{#1}`.

N 2020-06-05 `/gtr/fanchart-marker-definition={⟨code⟩}` (no default)

Used to set up the marker. This `⟨code⟩` is called after the segment initialization and before the segment is drawn. `/gtr/fanchart marker style` ^{→ P.327} sets the `⟨code⟩` to `\getree_fanchart_set_marker_style:n` ^{→ P.346} `{#1}`.

N 2020-06-05 `/gtr/fanchart-segment-code={⟨code⟩}` (no default)

Used to draw the current segment of the circle. This `⟨code⟩` is called after the code of `/gtr/fanchart-segment-definition` and `/gtr/fanchart-marker-definition`. Initially, this `⟨code⟩` is equal to `\getree_fanchart_draw_segment_standard:` ^{→ P.346}.

N 2020-06-05 `/gtr/fanchart-root-code={⟨code⟩}` (no default)

This `⟨code⟩` is used to draw the root node (center of the fan chart). `/gtr/fanchart root style` ^{→ P.323} sets the `⟨code⟩` to `\getree_fanchart_draw_root_style:n` ^{→ P.346} `{#1}`.

N 2020-06-05 `\l_getree_fanchart_minor_angle_tl` (use read-only)

N 2020-06-05 `\l_getree_fanchart_major_angle_tl` (use read-only)

These token lists contain the values from `/gtr/fanchart minor angle` ^{→ P.314} and `/gtr/fanchart major angle` ^{→ P.314}.

N 2020-06-05 `\l_getree_fanchart_angle_a_tl` (use read-only)

N 2020-06-05 `\l_getree_fanchart_angle_b_tl` (use read-only)

These token lists contain the minor angle and the major angle of the current segment of circle.

N 2020-06-05 `\l_getree_fanchart_radius_a_tl` (use read-only)

N 2020-06-05 `\l_getree_fanchart_radius_b_tl` (use read-only)

These token lists contain the minor radius and the major radius of the current segment of circle.

N 2020-06-05 `\l_getree_fanchart_offset_a_tl` (use read-only)

N 2020-06-05 `\l_getree_fanchart_offset_b_tl` (use read-only)

These token lists contain the inner offset and the outer offset of the current segment of circle.

<code>\l_gettree_fanchart_line_width_tl</code>	(use read-only)	N 2020-06-05
This token list contains the boundary line width of the current segment of circle.		
<code>\l_gettree_fanchart_level_tl</code>	(use read-only)	N 2020-06-05
This token list contains the level number of the current segment of circle.		
<code>\l_gettree_fanchart_ratio_tl</code>	(use read-only)	N 2020-06-18
This token list contains the relative angle of the center of the current segment taken the intervall $[0, 1]$ where 0 means the minor angle and 1 means the major angle. It can be used to compute angle dependent coloring or similar things.		
<code>\l_gettree_fanchart_id_tl</code>	(use read-only)	N 2020-06-18
This token list contains the node id of the current segment of circle. It is empty, if the node has no id.		
<code>\c_gettree_fanchart_maximum_rings_tl</code>	(constant 24)	N 2020-06-05
This constant token list contains the maximum level number, i.e. the maximum number of segment rings.		
<code>\gettree_fanchart_if_complemented_node_p:</code>		N 2020-06-05
<code>\gettree_fanchart_if_complemented_node:TF</code>	$\{\langle true\ code \rangle\}$ $\{\langle false\ code \rangle\}$	N 2020-06-05
Tests, if the current node is a complemented node, and continues expansion based on the result.		
<code>\gettree_fanchart_set_segment_style:n</code>	$\{\langle style \rangle\}$	N 2020-06-05
Sets a TikZ $\langle style \rangle$ for the (core) segment. The $\langle style \rangle$ is used by <code>\gettree_fanchart_draw_segment_standard:.</code>		
<code>\gettree_fanchart_set_marker_style:n</code>	$\{\langle style \rangle\}$	N 2020-06-05
Sets a TikZ $\langle style \rangle$ for the marker. The $\langle style \rangle$ is used by <code>\gettree_fanchart_draw_segment_standard:.</code>		
<code>\gettree_fanchart_set_color_wave:n</code>	$\{\langle name \rangle\}$	N 2020-06-05
Defines the color $\langle name \rangle$ to store the wave spectrum color depending on the angle of the current segment.		
<code>\gettree_fanchart_set_color_colorwheel:n</code>	$\{\langle name \rangle\}$	N 2020-06-05
Defines the color $\langle name \rangle$ to store the color wheel color depending on the angle of the current segment.		
<code>\gettree_fanchart_draw_path:n</code>	$\{\langle options \rangle\}$	N 2020-06-05
Draws the current segment of circle as TikZ <code>path</code> with the given $\langle options \rangle$.		
<code>\gettree_fanchart_draw_path:nnn</code>	$\{\langle radius1 \rangle\}$ $\{\langle radius2 \rangle\}$ $\{\langle options \rangle\}$	N 2020-06-05
Draws the current segment of circle, but with $\langle radius1 \rangle$ and $\langle radius2 \rangle$, as TikZ <code>path</code> with the given $\langle options \rangle$.		
<code>\gettree_fanchart_draw_root_style:n</code>	$\{\langle options \rangle\}$	N 2020-06-05
Draws the root node (center) as TikZ <code>path</code> with the given $\langle options \rangle$.		
<code>\gettree_fanchart_draw_segment_standard:</code>		N 2020-06-05
Draws the full segment (gap, core, marker) according to all settings.		


```

\definecolor{myblue}{rgb}{0.600000, 0.658824, 0.772549}
\definecolor{myred}{rgb}{1.000000, 0.694118, 0.745098}
\definecolor{mygreen}{rgb}{0.752941, 0.917647, 0.823529}


\ExplSyntaxOn

\gtrset{
  mysegment/.style = { fanchart-segment-definition = {
    \tl_set:Nx \l_tmpa_tl { \fp_to_int:n{ min(95,(\l_gettree_fanchart_level_tl-1)*25) } }
    \fp_compare:nTF{ \l_gettree_fanchart_ratio_tl < 0.5 }
    {
      \colorlet{mycolor}{white!\l_tmpa_tl!myred}
    }
    {
      \colorlet{mycolor}{white!\l_tmpa_tl!myblue}
    }
    \getree_fanchart_set_segment_style:n {fill=mycolor}
  }},
}

\ExplSyntaxOff

\begin{autosizetikzpicture}{\linewidth}{9cm}
\gtrfanchartinput[ autofill parents male female=4,
  fanchart text portrait=inwards,
  fanchart root style = {fill=mygreen},
  fanchart boundary color=black!75,
  mysegment,
  empty name text={},
]
{example.neumann.graph}
\end{autosizetikzpicture}

```



The customization example above considers a two colored approach where the colors fade from the center to the rim. The segment color is dependent from the angle ($\l_gettree_fanchart_ratio_tl \rightarrow P.346$) and from the radius ($\l_gettree_fanchart_level_tl \rightarrow P.346$).

14

Auto-Layout Algorithm

14.1 Preliminaries

As discussed before in Chapter 1 on page 9 and Chapter 4 on page 63, *genealogy trees* can be considered as rooted ordered trees of unbounded degree with annotations. Therefore, an auto-layout algorithm for *genealogy trees* should be some extension of a known algorithm for tree layout which considers the family-centric approach.

The basic ideas for aesthetic properties and implementation are taken from Reingold and Tilford [3], Walker [6], and Buchheim, Jünger, and Leipert [1]. To dampen expectations early, the actual implementation is some extended Reingold and Tilford algorithm and does not consider the aesthetic balancing of small subtrees as presented in more recent research. There are multi-fold reasons for this ranging from performance and implementation complexity considerations in pure L^AT_EX to the simply question, if balancing is needed or even obstructive for this special application. We will come back to this later.

14.1.1 Aesthetic Properties

First, let us consider aesthetic properties which are usually desired when drawing trees. The following wording is intended for vertically (mainly top-down) oriented trees:

- (A1) The y coordinate of a node is given by its level.
- (A2) The edges do not cross each other and nodes on the same level have a minimal horizontal distance.
- (A3) Isomorphic subtrees are drawn identically up to translation.
- (A4) The order of the children of a node is displayed in the drawing.
- (A5) The drawing of the reflection of a tree is the reflected drawing of the original tree.

Some of these properties cannot be guaranteed by the implementation and some are even violated deliberately.

14.1.2 Genealogy Trees

In supplement to typical graph theory notions, there is the additional *family* term for *genealogy trees*:


- (G1) A family is an ordered set of parent nodes and child nodes.
- (G2) All parent nodes of a family are connected with edges to all child nodes of the same family.
- (G3) A node is child to zero or none family and is parent to zero or arbitrary many families.

These three properties alone would allow to construct *genealogy graphs* since they do not restrict to a tree-like structure.


A parent node of a family is called a *leaf*, if it is not child to another family. A child node of a family is called a *leaf*, if it is not parent to another family.

For *genealogy trees*, the graph is required to be *connected* and to comply with exactly *one* of the following requirements:

- (G4a) All child nodes of a family are leaf nodes with exception of at most one (*parent tree*).



- (G4b) All parent nodes of a family are leaf nodes with exception of at most one (*child tree*).



Finally, we always consider *rooted* graphs. If (G4a) is fulfilled, there has to be a *root family* where all child nodes of a family are leaf nodes. If (G4b) is fulfilled, there has to be a *root family* where all parent nodes of a family are leaf nodes.

It is quite obvious that there are *genealogy trees* fulfilling (G1)–(G4) which cannot comply with (A2). Edge crossing is quite likely, but should still be minimized. The minimal distance of nodes on the same level may be deliberately different to emphasize different node affiliations.

14.1.3 Graph Grammar

Genealogy trees fulfilling (G1)–(G4) are described by the graph grammar of Chapter 4 on page 63. This given grammar is certainly not without alternative. Also, there are child trees fulfilling (G1)–(G4b) which cannot be represented in this grammar.

- **parent** constructs including **g**, **c**, and **p** represent *parent trees* fulfilling (G1)–(G4a).
- **child** constructs including **g**, **c**, **p**, and **union** represent *child trees* fulfilling (G1)–(G4b).
- **sandclock** constructs are an extension. They are a handy combination of a *parent tree* and a *child tree*.
- Nodes which are parent to one family and child to another family are **g**-nodes.
- The *root node* of a *parent tree* or *child tree* is the **g**-node of the *root family*.

14.2 Requirements


The aesthetic properties (A1)–(A5) are generally desired for the implemented auto-layout algorithm. While (A1), (A3), and (A4)¹ are considered to be fulfilled, (A2) cannot be guaranteed for *child tree*. This was discussed before and can be seen explicitly in Section 14.2.2 on page 352. Property (A5) is loosely considered in the following alignment requirements, but is not covered by special algorithmic efforts. Besides the effects known from the Reingold and Tilford [3] algorithm, there are additional violations of reflections for edge drawing; also see Section 14.2.2 on page 352 for this.

14.2.1 Parent and Child Alignment


The following wording is intended for top-down oriented trees, but applied analogously for other growing directions.

For a family, the parent nodes and the child nodes should be placed centered to each other. This means that the center point of all parents should be vertically in congruence with the center point of all children.


Here, every parent is parent of just one family. If a parent node is parent to more than one family, see Section 14.2.2 on page 352.




The parent nodes (red) are placed centered above the child nodes (blue).




The center points for children and parents are computed as the half way between the center of the leftmost node and the center of the rightmost node.



Even, if a node is member of another family, only the center of the node itself is considered for alignment.



Even, if a node is member of another family, only the center of the node itself is considered for alignment.



Even, if a node is member of another family, only the center of the node itself is considered for alignment.

¹One can argue about fulfillment of (A4). The graph grammar restricts children of **union** constructs to be grouped together while the children of the embedding **child** can be placed freely. The algorithm displays the order of the children as far as it is described by the grammar, but one could construct trees fulfilling (G1)–(G4b) which cannot be described by the grammar.

14.2.2 Patchwork Families

If a parent node is parent to more than one family, this is described by a **child** construct which embeds one or more **union** constructs. The **g**-node of the **child** family is also the implicit **g**-node of all **union** families. In this case, the combination of the **child** family with all directly embedded **union** families is called the *patchwork family* of the **g**-node which is parent to all children of the patchwork family.

The parent and child alignment considered in Section 14.2.1 on page 351 is now done for the whole patchwork family. This means that the center point of all parents should be vertically in congruence with the center point of all children of the patchwork family.

While node placement is a straightforward extension to Section 14.2.1 on page 351, edge placement is more difficult since edge crossing is quite likely. Therefore, the interconnections are to be separated vertically. This does not hinder crosspoints, but reduces the probability for lines lying on other lines.


The fulfillment of this requirement results in a best-effort algorithm. The following still small example gives a highlight on the vast amount of possible edge configurations for complex patchwork families.

Edge Varieties for Families with Unions

Consider a **child** family with three children together with a **union** with two children, e.g.


```
child{
  g-p-c-c-c-
  union{p-c-c-}
}
```

Depending on the order of the nodes, here, there are 24 different edge configurations:



14.2.3 Graph Growing Direction

The wording used in this chapter applies to top-down oriented trees, but the auto-layout algorithm should consider all four standard directions for graph growing.



The graph growing direction can be selected by setting the `/gtr/timeflow→P.80` option appropriately.

14.3 Algorithmic Steps

The following steps use the notations for *child trees* which grow top-down.

14.3.1 Recursive Family and Node Placement

The tree is constructed recursively in a bottom-up flow. The y -coordinate of a family is given by the current level while the x -coordinate is computed as relative *offset* to the enclosing family. This *offset* is initially 0pt.

During processing for a **child** family, every enclosed **child** and **union** is worked on recursively to construct their corresponding subtrees independently. This results in a list of children subtrees where the direct children of the original **child** family are the root **g**-nodes. This list also contains leaf child nodes and all direct leaf child nodes and child subtrees for all enclosed **union** families.

After the construction of this children list with all their subtrees, each leaf or subtree is placed step by step as close as possible to the right of the already placed last leaf or subtree. The placement is stored into the *offset* value of a subtree or directly for a leaf node.

The same procedure applies to the parent nodes of the original **child** family but with reduced complexity since all parents are leaf nodes.

Finally, the center points (*pivot* points) of all placed children and analogously of all placed parents are computed. All parents are shifted to get both points to congruence².


This concludes the computation for the current **child** family.

14.3.2 Contours

The core of the algorithm is to place one subtree (or leaf node) as close as possible to the right of another subtree (or leaf node). This is done following the ideas of Reingold and Tilford [3] by housekeeping contours for subtrees. Every **child** family keeps an anchor to a starting node for its *west contour* and its *east contour*. The *west contour* is the sequence of all leftmost nodes in the whole subtree, while the *east contour* is the sequence of all rightmost nodes in the whole subtree.

Every node itself has a *west contour value* and an *east contour value* describing the relative x -coordinate of the left and right border of this node in relation to its enclosing family.

When a *west contour* is followed starting from its anchor, the *next* node in the *west contour* after the current contour node is the leftmost leaf (patchwork) child or the parent node of the very first (patchwork) child, if the current node is no leaf node. Otherwise, a *thread* is used to note the next node plus a *thread gap* which is saved for housekeeping.




Analogously, when an *east contour* is followed starting from its anchor, the *next* node in the *east contour* after the current contour node is the rightmost leaf (patchwork) child or the parent node of the very last (patchwork) child, if the current node is no leaf node. Otherwise, a *thread* is used to note the next node plus a *thread gap*.

²As described in detail in this document, this algorithm can be adapted with various option settings, e.g. to change the pivot alignment procedure


For direct children or child families, the relative position is known or computed by the family *offset* values and the stored contour values. For nodes on a thread, this cannot be done and, therefore, the *thread gap* is needed.

The `LIB debug` library documented in Chapter 11 on page 249, provides the `\gtrprocessordebug`^{P.252} command which displays the *offset* value and the different contour values. Also, `\gtrdebugdrawcontour`^{P.261} depicts the contours.




14.3.3 Combining Subtrees

The combining or sewing of two adjacent subtrees traverses the east contour of the left subtree and the west contour of the right subtree. The distance comparisons of every two contour nodes on the same level gives the required *offset* value for the right subtree. The combined forest of the two trees inherits the west contour of the left subtree and the east contour of the right subtree. If one of them is shorter than the other, it is prolonged by a *thread* as required.




14.4 Known Problems


As was already mentioned before, the aesthetic property (A5) is not guaranteed by the auto-layout algorithm. The classic example for this is depicted below using the implemented auto-layout algorithm. Note that the small inner subtrees are not evenly spread but are crowded on the left-hand side.




Next, the classic example is translated to *genealogy trees*. The effect is the same but arguable may be seen more negligible or at least acceptable. To avoid this automatically, some technique from [3, 6] would be needed.




Luckily, the algorithm is implemented in \LaTeX with a lot of intervention points using options. If (A5) is really needed for aesthetic reasons, one can simply cheat by adding some `/gtr/distance \rightarrow P.96` options at the crucial small subtrees:



Another known problem is edge crossing which violates (A2), but this is for some patchwork families sheer unavoidable as even the small examples from Section 14.2.2 on page 352 show. Edge crossing can also happen for childless families, if the usual perpendicular edge drawing is used.



To solve the problem manually, a child with `/gtr/phantomP.125` option can be added to the childless family:



See Section 5.14 on page 128 for a package aided insertion of such `phantom` nodes.

15

Example Graph Files

The following example graph files are used for various examples inside this document.

15.1 example.option.graph

File «example.option.graph»

```
parent[id=SmithDoe]{
  g[id=Arth2008,male]{Arthur\\gtrsymBorn\\,2008}
  c[id=Bert2010,female]{Berta\\gtrsymBorn\\,2010}
  c[id=Char2014,male]{Charles\\gtrsymBorn\\,2014}
  parent[id=Smith]{
    g[id=John1980,male]{John Smith\\gtrsymBorn\\,1980}
    p[id=GpSm1949,male]{Grandpa Smith\\gtrsymBorn\\,1949}
    p[id=GmSm1952,female]{Grandma Smith\\gtrsymBorn\\,1952}
  }
  parent[id=Doe]{
    g[id=Jane1982,female]{Jane Doe\\gtrsymBorn\\,1982}
    c[id=Harr1987,male]{Uncle Harry\\gtrsymBorn\\,1987}
    p[id=GpDo1955,male]{Grandpa Doe\\gtrsymBorn\\,1955}
    p[id=GmDo1956,female]{Grandma Doe\\gtrsymBorn\\,1956}
  }
}
```

15.2 example.database.graph

Also see Section 7.2 on page 163.

File «example.database.graph»

```
child[id=SmitBowd1742]{
  g[id=SmitChar1722]{
    male,
    name      = {\pref{Charles} \surn{Smith}},
    birth     = {(caAD)1722}{London},
    baptism   = {1722-04-13}{London},
    death+    = {1764-10-12}{}{killed},
    profession = {Copper smith, soldier},
    comment   = {Invented the square wheel},
  }
  p[id=BowdJane1724]{
    female,
    name      = {\pref{Jane} \surn{Bowden}},
    floruit-  = {1724/1802},
    marriage  = {1742-03-02}{London},
    death-    = {/1815}
  }
  c[id=BowdAbra1740]{
    male,
    name      = {\pref{Abraham} \surn{Bowden}},
    birth+    = {1740-01-04}{London}{out of wedlock},
    death     = {1740-02-23}{London}
  }
  c[id=SmitEliz1744]{
    female,
    name      = {\pref{Elizabeth} \nick{Liz} \surn{Smith}},
    birth     = {1744-02-02}{London},
    floruit   = {1780/1805}{New York},
    death     = {1812-04-12}{Boston},
    comment   = {Had a store in Boston},
  }
  c[id=SmitMich1758]{
    male,
    name      = {\pref{Michael} \surn{Smith}},
    birth+    = {1758-03-01}{}{died},
  }
}
```

15.3 example.formal.graph

File «example.formal.graph»

```
child[id=fam_A]{
  g[id=na1,male]{a_1}
  p[id=na2,female]{a_2}
  child[id=fam_B]{
    p[id=nb1,male]{b_1}
    g[id=na3,female]{a_3}
    c[id=nb2,male]{b_2}
    child[id=fam_E]{
      p[id=ne1,male]{e_1}
      g[id=nb3,female]{b_3}
      c[id=ne2,male]{e_2}
      c[id=ne3,female]{e_3}
    }
  }
}
child[id=fam_C]{
  g[id=na4,male]{a_4}
  p[id=nc1,female]{c_1}
  child[id=fam_F]{
    g[id=nc2,male]{c_2}
    p[id=nf1,female]{f_1}
    c[id=nf2,male]{f_2}
    c[id=nf3,female]{f_3}
    c[id=nf4,male]{f_4}
  }
}
union[id=fam_D]{
  p[id=nd1,female]{d_1}
  child[id=fam_G]{
    p[id=ng1,male]{g_1}
    g[id=nd2,female]{d_2}
    c[id=ng2,male]{g_2}
    c[id=ng3,female]{g_3}
    union[id=fam_H]{
      p[id=nh1,male]{h_1}
      c[id=nh2,male]{h_2}
    }
  }
}
c[id=nd3,male]{d_3}
child[id=fam_I]{
  g[id=nd4,male]{d_4}
  p[id=ni1,female]{i_1}
  c[id=ni2,female]{i_2}
  c[id=ni3,female]{i_3}
  c[id=ni4,female]{i_4}
}
}
}
c[id=na5,female]{a_5}
}
```

15.4 example.neumann.graph

File «example.neumann.graph»

```
% !TeX encoding=UTF-8
parent[id=NeumGras1672]{%
  g[id=NeumBalt1687]{%
    male,
    name={Johann \pref{Balthasar} \surn{Neumann}},
    shortname={J. \pref{Balthasar} \surn{Neumann}},
    sibling,
    birth={1687-01-27}{Eger (Böhmen)},
    death={1753-08-19}{Würzburg (Unterfranken)},
    comment={Baumeister des Barock und des Rokoko},
  }%
parent[id=NeumHoye1631]{%
  g[id=NeumJoha1631]{%
    male,
    name={\pref{Johann} Christoph \surn{Neumann}},
    shortname={\pref{Johann} C. \surn{Neumann}},
    unrelated,
    birth={1631}{Eger (Böhmen)},
    death={1713-08-08}{Eger (Böhmen)},
    comment={Bürger und Tuchmacher in Eger},
  }%
parent[id=NeumKeb11599]{%
  g[id=NeumAndr1605]{%
    male,
    name={\pref{Andreas} \surn{Neumann}},
    shortname={\pref{Andreas} \surn{Neumann}},
    unrelated,
    birth={1605-11-13}{Eger (Böhmen)},
    death={1671-12-09}{Eger (Böhmen)},
    comment={Bürger und Tuchmacher in Eger},
  }%
parent[id=NeumBbbb1580]{%
  g[id=NeumAndr1576]{%
    male,
    name={\pref{Andreas} \surn{Neumann}},
    shortname={\pref{Andreas} \surn{Neumann}},
    unrelated,
    birth={1576-09-23}{Eger (Böhmen)},
    death={{(caAD)1640}{Eger (Böhmen)}},
    comment={Bürger und Tuchmacher in Eger},
  }%
parent[id=NeumBbbb1520]{%
  g[id=NeumGeor1530]{%
    male,
    name={\pref{Georg} \surn{Neumann}},
    shortname={\pref{Georg} \surn{Neumann}},
    unrelated,
    birth={{(caAD)1530}{Eger (Böhmen)}},
    death={{(caAD)1610}{Eger (Böhmen)}},
    comment={Tuchmacher und Ratsherr in Eger},
  }%
p[id=NeumAndr1470]{%
  male,
  name={\pref{Andreas} \surn{Neumann}},
  shortname={\pref{Andreas} \surn{Neumann}},
  unrelated,
  birth={{(caAD)1470}{Höflas bei Eger (Böhmen)}},
  death={{(caAD)1570}{Eger (Böhmen)}},
}%
```

```

}%
p[id=XxxxKath1545]{%
  female,
  name={\pref{Katharina} \surn{?}},
  shortname={\pref{Katharina} \surn{?}},
  unrelated,
  birth={{(caAD)1545}{}},
  death={{(caAD)1620}{Eger (Böhmen)}},
}%
}%
parent[id=KealBbbb1560]{%
  g[id=KexlBarb1570]{%
    female,
    name={\pref{Barbara} \surn{Keßler}},
    shortname={\pref{Barbara} \surn{Keßler}},
    unrelated,
    birth={{(caAD)1570}{Eger (Böhmen)}},
    marriage={{1599-04-12}{Eger (Böhmen)}},
    death={{(caAD)1650}{Eger (Böhmen)}},
    comment={Bürgerstochter aus Eger},
  }%
  p[id=KexlHier1540]{%
    male,
    name={\pref{Hieronimus} \surn{Keßler}},
    shortname={\pref{Hieronimus} \surn{Keßler}},
    unrelated,
    birth={{(caAD)1540}{}},
    death={{(caAD)1590}{Eger (Böhmen)}},
    comment={Gemeinherr in Eger (1579-1584)},
  }%
  p[id=XxxxAgat1550]{%
    female,
    name={\pref{Agathe} \surn{?}},
    shortname={\pref{Agathe} \surn{?}},
    unrelated,
    birth={{(caAD)1550}{}},
    marriage={{(caAD)1560}{}},
    death={{(caAD)1630}{Eger (Böhmen)}},
  }%
}%
}%
parent[id=HoyeBbbb1600]{%
  g[id=HoyeEste1600]{%
    female,
    name={\pref{Ester} \surn{Hoyer}},
    shortname={\pref{Ester} \surn{Hoyer}},
    unrelated,
    birth={{(caAD)1600}{Sebenbach bei Eger (Böhmen)}},
    marriage={{1631-02-11}{Eger (Böhmen)}},
    death={{(caAD)1670}{Eger (Böhmen)}},
    comment={Bauerstochter aus Schönbach},
  }%
  p[id=HoyeLore1560]{%
    male,
    name={\pref{Lorenz} \surn{Hoyer}},
    shortname={\pref{Lorenz} \surn{Hoyer}},
    unrelated,
    birth={{(caAD)1560}{}},
    death={{(caAD)1640}{Sebenbach bei Eger (Böhmen)}},
    comment={Bauer in Schönbach},
  }%
}%
}%
}%

```

```

parent[id=GrasHamm1645]{%
  g[id=GrasRos11651]{%
    female,
    name={\pref{Rosina} \surn{Grassoldt}},
    shortname={\pref{Rosina} \surn{Grassoldt}},
    sibling,
    birth={1651-11-29}{Eger (Böhmen)},
    marriage={1672-08-02}{Eger (Böhmen)},
    death={1699-11-26}{Eger (Böhmen)},
    comment={Tuchmacherstochter aus Eger},
  }%
parent[id=GrasMich1587]{%
  g[id=GrasHier1600]{%
    male,
    name={\pref{Hieronimus} \surn{Grassoldt}},
    shortname={\pref{Hieronimus} \surn{Grassoldt}},
    unrelated,
    birth={{caAD}1600}{Eger (Böhmen)},
    death={{caAD}1690}{Eger (Böhmen)},
    comment={Bürger und Tuchmacher in Eger},
  }%
p[id=GrasLore1550]{%
  male,
  name={\pref{Lorenz} \surn{Grassoldt}},
  shortname={\pref{Lorenz} \surn{Grassoldt}},
  unrelated,
  birth={{caAD}1550}{},
  death={{caAD}1630}{Eger (Böhmen)},
  comment={Bürger und Tuchmacher in Eger},
}%
parent[id=MichBbbb1560]{%
  g[id=MichBarb1571]{%
    female,
    name={\pref{Barbara} \surn{Michel}},
    shortname={\pref{Barbara} \surn{Michel}},
    unrelated,
    birth={1571-11-03}{Eger (Böhmen)},
    marriage={1587-10-25}{Eger (Böhmen)},
    death={{caAD}1630}{Eger (Böhmen)},
  }%
p[id=MichNik11530]{%
  male,
  name={\pref{Niklas} \surn{Michel}},
  shortname={\pref{Niklas} \surn{Michel}},
  unrelated,
  birth={{caAD}1530}{},
  death={{caAD}1601}{Eger (Böhmen)},
  comment={Bürger und Tuchmacher in Eger},
}%
}%
}%
parent[id=HammDiet1611]{%
  g[id=HammMarg1623]{%
    female,
    name={\pref{Margaretha} \surn{Hammerschmid}},
    shortname={\pref{Margaretha} \surn{Hammerschmid}},
    sibling,
    birth={1623-03-08}{Eger (Böhmen)},
    marriage={1645-09-26}{Eger (Böhmen)},
    death={{caAD}1690}{Eger (Böhmen)},
    comment={Tuchmacherstochter aus Eger},
  }%
parent[id=HammBbbb1570]{%

```



```

g[id=HammNiko1570]{%
  male,
  name={\pref{Nikolaus} \surn{Hammerschmid}},
  shortname={\pref{Nikolaus} \surn{Hammerschmid}},
  ancestor,
  birth={(caAD)1570}{Schöba (Böhmen)},
  death={1623}{Eger (Böhmen)},
  comment={Bürger und Tuchmacher zu Eger},
}%
p[id=HammGeor1520]{%
  male,
  name={\pref{Georg} \surn{Hammerschmid}},
  shortname={\pref{Georg} \surn{Hammerschmid}},
  ancestor,
  birth={(caAD)1520}{},
  death={(caAD)1610}{Schöba (Böhmen)},
  comment={zu Schöba},
}%
}%
parent[id=DietTrap1585]{%
  g[id=DietKath1587]{%
    female,
    name={\pref{Katharina} \surn{Diettl}},
    shortname={\pref{Katharina} \surn{Diettl}},
    sibling,
    birth={1587-12-20}{Eger (Böhmen)},
    marriage={1611-01-02}{Eger (Böhmen)},
    death={(caAD)1660}{Eger (Böhmen)},
    comment={Weißgerberstochter aus Eger},
  }%
parent[id=DietBbbb1560]{%
  g[id=DietCasp1550]{%
    male,
    name={\pref{Caspar} \surn{Diettl}},
    shortname={\pref{Caspar} \surn{Diettl}},
    ancestor,
    birth={(caAD)1550}{},
    death={(caAD)1611}{Eger (Böhmen)},
    comment={Weißgerber zu Eger},
  }%
  p[id=DietNikl1515]{%
    male,
    name={\pref{Niklas} \surn{Diettl}},
    shortname={\pref{Niklas} \surn{Diettl}},
    ancestor,
    birth={1515}{},
    death={(caAD)1580}{Eger (Böhmen)},
    comment={Schuster zu Eger},
  }%
}%
parent[id=TrapBbbb1554]{%
  g[id=TrapUrsu1567]{%
    female,
    name={\pref{Ursula} \surn{Trapp}},
    shortname={\pref{Ursula} \surn{Trapp}},
    ancestor,
    birth={1567-06-27}{Eger (Böhmen)},
    marriage={1585-06-16}{Eger (Böhmen)},
    death={(caAD)1597}{Eger (Böhmen)},
    comment={Weißgerberstochter aus Eger},
  }%
  p[id=TrapCasp1520]{%
    male,

```

```

name={\pref{Caspar} \surn{Trapp}},
shortname={\pref{Caspar} \surn{Trapp}},
ancestor,
birth={({caAD}1520){-}},
death={({caAD}1574){Eger (Böhmen)},
comment={Weißgerber zu Eger},
}%
p[id=XxxxAnna1537]{%
female,
name={\pref{Anna} \surn{?}},
shortname={\pref{Anna} \surn{?}},
ancestor,
birth={({caAD}1537){-}},
marriage={({caAD}1554){-}},
death={({caAD}1610){Eger (Böhmen)},
}%
}%
}%
}%
}%
}%

```

16

Stack Macros

The `genealogytree` package provides an elementary stack mechanism which is used internally, but may also be applied elsewhere. This elementary stack stores and retrieves expanded text first-in-last-out (FILO). There are no safe-guarding mechanisms implemented.

16.1 Creating a Stack

`\gtrnewstack{<name>}`

Creates a new empty stack `<name>`.

```
\gtrnewstack{foo}           % new empty stack
Stack size: \gtrstacksize{foo}
```

Stack size: 0

`\gtrstacksize{<name>}`

Returns the current stack size.

```
\gtrnewstack{foo}
Stack size: \gtrstacksize{foo}
\gtrstackpush{foo}{a}\par
Stack size: \gtrstacksize{foo}
```

Stack size: 0

Stack size: 1

16.2 Push to a Stack

`\gtrstackpush{<name>}{<content>}`

Pushes `<content>` to a stack `<name>`. The `<content>` is expanded during pushing.

```
\def\myx{X}
\gtrnewstack{foo}
\gtrstackpush{foo}{\myx}
\gtrstackpop{foo}
```

X

16.3 Pop from a Stack

`\gtrstackpop{<name>}`

Pops content from a stack `<name>`. The last pushed content is popped first.

```
\gtrnewstack{foo}
\gtrstackpush{foo}{This}
\gtrstackpush{foo}{is}
\gtrstackpush{foo}{a}
\gtrstackpush{foo}{hello}
\gtrstackpush{foo}{world}
\gtrstackpop{foo} \gtrstackpop{foo} \gtrstackpop{foo}
\gtrstackpop{foo} \gtrstackpop{foo}
```

world hello a is This

`\gtrstackpopto{<name>}{<macro>}`

Pops content from a stack `<name>` into a `<macro>`.

```
\gtrnewstack{foo}
\gtrstackpush{foo}{My}
\gtrstackpush{foo}{test}
\gtrstackpopto{foo}{\myA}
\gtrstackpopto{foo}{\myB}
'\myA' and '\myB'.
```

'test' and 'My'.

16.4 Peek into a Stack

`\gtrstackpeek{<name>}`

Reads from a stack `<name>` without reducing the stack content.

```
\gtrnewstack{foo}
\gtrstackpush{foo}{First entry}
'\gtrstackpeek{foo}', '\gtrstackpeek{foo}';
\gtrstackpush{foo}{Second entry}
'\gtrstackpeek{foo}', '\gtrstackpeek{foo}';
```

'First entry', 'First entry'; 'Second entry', 'Second entry';

`\gtrstackpeekto{<name>}{<macro>}`

Peeks content from a stack `<name>` into a `<macro>`.

```
\gtrnewstack{foo}
\gtrstackpush{foo}{My}
\gtrstackpush{foo}{test}
\gtrstackpeekto{foo}{\myA}
\gtrstackpeekto{foo}{\myB}
'\myA' and '\myB'.
```

'test' and 'test'.

16.5 Creating Stack Shortcuts

`\gtrmakestack{<name>}`

Creates a new empty stack `<name>` and creates new macros `<name>size`, `<name>push`, `<name>popto`, `<name>pop`, `<name>peekto`, and `<name>peek`. These macros serve as shortcuts to the corresponding stack macros from above.

```
\gtrmakestack{foo}
\foopush{First}
\foopush{Second}
\foopush{Third}
The stack contains \foosize\ entries. The last one is '\foopeek'.
```

```
\foopopto\myA
The stack contains \foosize\ entries after '\myA' was removed.
```

```
The remaining entries are '\foopop' and '\foopop'.
Now, the stack contains \foosize\ entries.
```

```
Never pop an empty stack: \foopop \foosize
```

```
The stack contains 3 entries. The last one is 'Third'.
The stack contains 2 entries after 'Third' was removed.
The remaining entries are 'Second' and 'First'. Now, the stack contains 0 entries.
Never pop an empty stack: -1
```

```
\gtrmakestack{foo}
\foopush{Mary}\foopush{had}\foopush{a}\foopush{little}\foopush{lamb}
```

```
\loop\ifnum\foosize>0
  \foopop,
\repeat
```

```
lamb, little, a, had, Mary,
```


Bibliography

- [1] Christoph Buchheim, Michael Jünger, and Sebastian Leipert. “Improving Walker’s Algorithm to Run in Linear Time”. In: *Graph Drawing*. 10th International Symposium, GD 2002. Volume 2528. Lecture Notes in Computer Science. Springer, Nov. 8, 2002, pages 344–353.
- [2] Uwe Kern and The L^AT_EX Project Team. *Extending L^AT_EX’s color facilities: the xcolor package*. Version 3.02. Comprehensive T_EX Archive Network. Sept. 29, 2024.
<https://ctan.org/pkg/xcolor>.
- [3] Edward M. Reingold and John S. Tilford. “Tidier drawings of trees”. In: *IEEE Transactions on Software Engineering* 7.2 (Mar. 1981), pages 223–228.
- [4] Thomas F. Sturm. *The tcolorbox package*. Version 6.9.0. Comprehensive T_EX Archive Network. Nov. 28, 2025.
<https://ctan.org/pkg/tcolorbox>.
- [5] Till Tantau, Christian Feuersänger, Henri Menke, and The PGF/TikZ Team. *The TikZ and PGF Packages*. Version 3.1.11a. Comprehensive T_EX Archive Network. Aug. 29, 2025.
<https://ctan.org/pkg/pgf>.
- [6] John Q. Walker II. “A Node-positioning Algorithm for General Trees”. In: *Software. Practice and Experience* 20.7 (July 1990), pages 685–705.

Index

- a3paper 5 value, 300, 306
- a4paper 3 value, 298, 306
- a4paper 4 value, 299, 306
- above value, 112, 113
- AD value, 172
- add child key, 221
- add parent key, 222
- adjust node key, 113
- adjust position key, 112
- affected key, 272
- after parser key, 111
- after tree key, 115
- age key, 167
- age code key, 202
- ahnentafel 3 value, 292
- ahnentafel 4 value, 294
- ahnentafel 5 value, 296
- all key, 13
- all value, 188
- all but AD value, 172, 188
- ancestor key, 167
- ancestor value, 167
- anchoring key, 214
- auto value, 321
- autofill parents female male key, 134
- autofill parents female male* key, 134
- autofill parents male female key, 133
- autofill parents male female* key, 133
- autofill parents none key, 134
- autofill parents unspecific key, 132
- autofill parents unspecific* key, 132
- autosizetikzpicture environment, 61
- autosizetikzpicture* environment, 61
- background key, 214
- baptism key, 169, 192
- baptism+ key, 169
- baptism- key, 169
- Baptized key, 245
- BC value, 172
- below value, 112, 113
- birth key, 169, 191
- birth+ key, 169
- birth- key, 169
- Born key, 245
- Bornoutofwedlock key, 245
- both value, 97, 225, 263
- box key, 98
- box clear key, 98
- burial key, 171, 192
- burial+ key, 171
- burial- key, 171
- Buried key, 245
- c grammar, 17, 19, 21, 55, 59, 60, 64, 73, 77, 78, 117, 120, 284, 311, 350
- \c_gettree_fanchart_maximum_rings_tl, 346
- ca value, 172
- caAD value, 172
- caBC value, 172
- calendar print key, 188
- calendar text for key, 188
- carrier key, 272
- catalan value, 247
- center value, 214
- child grammar, 16, 25, 26, 34, 46, 55, 60, 64, 67, 69, 71, 77–80, 87, 89, 105, 106, 108, 128–130, 219, 261, 350–352, 354
- child value, 97, 225
- child distance key, 87
- child distance in child graph key, 87
- child distance in parent graph key, 86
- chinese value, 247
- clockwise value, 321
- code key, 136
- Colors
 - fanchart, 326, 329, 330
 - gtr_Blue_1, 308
 - gtr_Blue_2, 308
 - gtr_Blue_3, 308
 - gtr_Blue_4, 308
 - gtr_Blue_5, 308
 - gtr_Blue_6, 308
 - gtr_Bright_Red, 308
 - gtr_Female_Background, 273, 308
 - gtr_Female_Frame, 273, 308
 - gtr_Male_Background, 273, 308
 - gtr_Male_Frame, 273, 308
 - gtr_Neuter_Background, 273, 308
 - gtr_Neuter_Frame, 273, 308
 - gtr_Peach_Back, 308
 - gtr_Peach_Frame, 308
 - gtr_Yellow_Back, 308
 - gtr_Yellow_Frame, 308
 - gtrfanchartboundary, 322
 - gtrsymbol, 237, 238
- colorwheel malefemale value, 338
- colorwheel opulent value, 339
- colorwheel rich value, 338
- colorwheel serious value, 337
- colorwheel sober value, 337
- Commands
 - \c_gettree_fanchart_maximum_rings_tl, 346

<code>\genealogytree, 55</code>	<code>\gtrifleafparent, 60</code>
<code>\genealogytreeinput, 56</code>	<code>\gtrifmale, 199</code>
<code>\getree_fanchart_draw_path:n, 346</code>	<code>\gtrifnativitydefined, 191</code>
<code>\getree_fanchart_draw_path:nnn, 346</code>	<code>\gtrifnodeid, 59</code>
<code>\getree_fanchart_draw_root_style:n, 346</code>	<code>\gtrifparent, 60</code>
<code>\getree_fanchart_draw_segment_standard:, 346</code>	<code>\gtrifplacedefined, 190</code>
<code>\getree_fanchart_if_complemented_node:TF, 346</code>	<code>\gtrifpnode, 59</code>
<code>\getree_fanchart_if_complemented_node_p:, 346</code>	<code>\gtrifprofessiondefined, 197</code>
<code>\getree_fanchart_set_color_colorwheel:n, 346</code>	<code>\gtrifroot, 60</code>
<code>\getree_fanchart_set_color_wave:n, 346</code>	<code>\gtrifwedlockdefined, 191</code>
<code>\getree_fanchart_set_marker_style:n, 346</code>	<code>\gtrignorenode, 118</code>
<code>\getree_fanchart_set_segment_style:n, 346</code>	<code>\gtrignoresubtree, 118</code>
<code>\getree_set_options_for_family:nn, 104</code>	<code>\gtrincludDBimage, 200</code>
<code>\getree_set_options_for_node:nn, 95</code>	<code>\gtrkeysappto, 58</code>
<code>\getree_set_options_for_subtree:nn, 107</code>	<code>\gtrkeysgappto, 58</code>
<code>\gtrautosizebox, 61</code>	<code>\gtrlanguage, 247</code>
<code>\gtrautosizebox*, 61</code>	<code>\gtrlistseparator, 194</code>
<code>\gtrBoxContent, 154</code>	<code>\gtrloadlanguage, 248</code>
<code>\gtrcomplemented, 345</code>	<code>\gtrmakestack, 369</code>
<code>\gtrDBage, 167</code>	<code>\gtrnewstack, 367</code>
<code>\gtrDBcomment, 165</code>	<code>\gtrNodeBoxOptions, 154</code>
<code>\gtrDBimage, 38, 166</code>	<code>\gtrnodefamily, 59</code>
<code>\gtrDBimageopt, 166</code>	<code>\gtrnodeid, 59</code>
<code>\gtrDBkekule, 167</code>	<code>\gtrnodelevel, 59</code>
<code>\gtrDBname, 165</code>	<code>\gtrNodeMaxHeight, 154</code>
<code>\gtrDBprofession, 166</code>	<code>\gtrNodeMaxWidth, 154</code>
<code>\gtrDBrelation, 167, 345</code>	<code>\gtrNodeMinHeight, 154</code>
<code>\gtrDBrelationship, 167</code>	<code>\gtrNodeMinWidth, 154</code>
<code>\gtrDBsex, 36, 165, 199, 345</code>	<code>\gtrnodenumber, 59</code>
<code>\gtrDBshortname, 165</code>	<code>\gtrnodetype, 59</code>
<code>\gtrDBuuid, 166</code>	<code>\gtrparent1, 309</code>
<code>\gtrdebugdrawcontour, 261</code>	<code>\gtrparent2, 309</code>
<code>\gtrDeclareDatabaseFormat, 182</code>	<code>\gtrparent3, 309</code>
<code>\gtrDrawSymbolicPortrait, 310</code>	<code>\gtrparent4, 310</code>
<code>\gtredgeset, 207</code>	<code>\gtrparent5, 310</code>
<code>\gtrfanchart, 312</code>	<code>\gtrparent6, 310</code>
<code>\gtrfanchartinput, 313</code>	<code>\gtrparent7, 310</code>
<code>\gtrifagedefined, 202</code>	<code>\gtrParseDate, 173</code>
<code>\gtrifchild, 60</code>	<code>\gtrparserdebug, 250</code>
<code>\gtrifcnode, 59</code>	<code>\gtrparserdebuginput, 251</code>
<code>\gtrifcommentdefined, 196</code>	<code>\gtrPrintAge, 202</code>
<code>\gtrifdatedefined, 186</code>	<code>\gtrPrintComment, 196</code>
<code>\gtrifdeceaseddefined, 191</code>	<code>\gtrPrintDatabase, 183</code>
<code>\gtrifeventdefined, 191</code>	<code>\gtrPrintDate, 186</code>
<code>\gtriffemale, 199</code>	<code>\gtrPrintEvent, 191</code>
<code>\gtrifgnode, 59</code>	<code>\gtrPrintEventPrefix, 191</code>
<code>\gtrifimagedefined, 200</code>	<code>\gtrPrintName, 184</code>
<code>\gtrifleaf, 60</code>	<code>\gtrPrintPlace, 190</code>
<code>\gtrifleafchild, 60</code>	<code>\gtrPrintProfession, 197</code>
	<code>\gtrPrintSex, 199</code>
	<code>\gtrprocessordebug, 252</code>
	<code>\gtrprocessordebuginput, 255</code>
	<code>\gtrset, 58</code>
	<code>\gtrsetoptionsforfamily, 104</code>
	<code>\gtrsetoptionsfornode, 95</code>
	<code>\gtrsetoptionsforsubtree, 107</code>
	<code>\gtrstackpeek, 368</code>
	<code>\gtrstackpeekto, 368</code>
	<code>\gtrstackpop, 368</code>

- \gtrstackpop, 368
- \gtrstackpush, 367
- \gtrstacksize, 367
- \gtrsymBaptized, 239
- \gtrSymbolsFullLegend, 243
- \gtrSymbolsLegend, 244
- \gtrSymbolsRecordReset, 243
- \gtrSymbolsSetCreate, 238
- \gtrSymbolsSetCreateSelected, 238
- \gtrSymbolsSetDraw, 238
- \gtrsymBorn, 239
- \gtrsymBornoutofwedlock, 239
- \gtrsymBuried, 241
- \gtrsymDied, 240
- \gtrsymDiedonbirthday, 239
- \gtrsymDivorced, 240
- \gtrsymEngaged, 240
- \gtrsymFemale, 241
- \gtrsymFloruit, 241
- \gtrsymFuneralurn, 241
- \gtrsymKilled, 240
- \gtrsymMale, 241
- \gtrsymMarried, 240
- \gtrsymNeuter, 242
- \gtrsymPartnership, 240
- \gtrsymStillborn, 239
- \gtruselibrary, 13
- \l_gettree_fanchart_angle_a_tl, 345
- \l_gettree_fanchart_angle_b_tl, 345
- \l_gettree_fanchart_id_tl, 346
- \l_gettree_fanchart_level_tl, 346
- \l_gettree_fanchart_line_width_tl, 346
- \l_gettree_fanchart_major_angle_tl, 345
- \l_gettree_fanchart_minor_angle_tl, 345
- \l_gettree_fanchart_offset_a_tl, 345
- \l_gettree_fanchart_offset_b_tl, 345
- \l_gettree_fanchart_radius_a_tl, 345
- \l_gettree_fanchart_radius_b_tl, 345
- \l_gettree_fanchart_ratio_tl, 346
- \nick, 184
- \node, 138, 152
- \pref, 184
- \surn, 184
- \tcbEXTERNALIZE, 49
- \tcbbox, 138, 146, 149
- \tcbboxfit, 138, 139, 161
- comment key, 165
- comment code key, 196
- complemented key, 135
- complemented family key, 135
- complemented phantom key, 135
- content interpreter key, 155
- content interpreter code key, 156
- content interpreter content key, 156
- content interpreter id and content key, 159
- contour key, 263
- counterclockwise value, 321
- cremated key, 192
- cremated value, 171
- custom key, 211
- d M yyyy value, 186
- d mon yyyy value, 186
- d mon.yyyy value, 186
- d month yyyy value, 186
- d-M-yyyy value, 187
- d-m-yyyy value, 187
- d-mon-yyyy value, 187
- d-month-yyyy value, 187
- d.M.yyyy value, 186
- d.m.yyyy value, 186
- d.mon.yyyy value, 186
- d.month yyyy value, 186
- d/m yyyy value, 186
- d/M/yyyy value, 186
- d/m/yyyy value, 186
- d/mon/yyyy value, 186
- d/month/yyyy value, 186
- danish value, 247
- database value, 35, 133, 134, 138, 161, 275, 278, 281, 284, 286, 289, 291, 292, 294, 296, 298–305
- database content interpreter key, 158
- database format key, 174
- database pole value, 275, 277, 278
- database pole reduced value, 277
- database poleportrait value, 278, 280
- database poleportrait reduced value, 280
- database portrait value, 281, 283
- database portrait reduced value, 283
- database relationship value, 291
- database sideways value, 286, 288, 289
- database sideways reduced value, 288
- database sidewaysportrait value, 289, 290
- database sidewaysportrait reduced value, 290
- database traditional value, 284, 285
- database traditional reduced value, 285
- database unknown key key, 168
- date value, 192
- date code key, 188
- date format key, 186
- date range after key, 189
- date range before key, 189
- date range full key, 189
- date range separator key, 189
- dd mm yyyy value, 186
- dd mon yyyy value, 186
- dd mon.yyyy value, 186
- dd-mm-yyyy value, 186
- dd-mon-yyyy value, 187
- dd-month-yyyy value, 187
- dd.mm.yyyy value, 186
- dd.mon.yyyy value, 186
- dd/mm yyyy value, 186
- dd/mm/yyyy value, 186

`dd/mon/yyyy` value, 186
`dd/month/yyyy` value, 186
`ddmonyyyy` value, 187
`death` key, 170, 192
`death+` key, 170
`death-` key, 170
`debug` key, 13
`deceased` key, 272
`deletion content interpreter` key, 157
`descendant` key, 167
`descendant` value, 167
`Died` key, 245
`died` key, 192
`died` value, 169
`Diedonbirthday` key, 245
`directory` value, 274
`disconnect` key, 225
`display 16:10 3` value, 305, 306
`display 16:10 4` value, 305, 306
`display 16:10 5` value, 305, 306
`display 16:9 3` value, 302, 306
`display 16:9 4` value, 303, 306
`display 16:9 5` value, 304, 306
`distance` key, 96
`divorce` key, 170, 192
`divorce+` key, 170
`divorce-` key, 170
`Divorced` key, 245
`down` value, 80, 211, 272, 284, 291
`dutch` value, 247

`east` value, 263
`edges` key, 204
`edges down` key, 233
`edges down by` key, 233
`edges for family` key, 206
`edges for subtree` key, 206
`edges shift` key, 232
`edges up` key, 233
`edges up by` key, 233
`empty` value, 174
`empty name text` key, 185
`Engaged` key, 245
`engagement` key, 170, 192
`engagement+` key, 170
`engagement-` key, 170
`english` value, 244, 247
Environments
 `autosizetikzpicture`, 61
 `autosizetikzpicture*`, 61
 `exgenealogypicture`, 57
 `genealogypicture`, 57
 `gtreventlist`, 194
 `gtrinfolist`, 198
 `gtrprintlist`, 194
 `tcolorbox`, 138, 143
 `tikzpicture`, 55, 57, 312
`error` value, 168
`event code` key, 192
`event format` key, 192

`event text` key, 192
`exgenealogypicture` environment, 57
`extra edges` key, 226
`extra edges for families` key, 227
`extra edges for family` key, 227
`extra edges prepend` key, 228
`extra edges prepend for families` key, 229
`extra edges prepend for family` key, 229

`family` key, 105
`family box` key, 99
`family database` key, 219
`family edges` key, 205
`family extra edges` key, 226
`family extra edges prepend` key, 228
`family id` key, 262
`family label` key, 218
`family number` key, 262
`fanchart` color, 326, 329, 330
`fanchart` key, 13
`fanchart ancestor style` key, 334
`fanchart angles` key, 315
`fanchart boundary color` key, 322
`fanchart boundary width` key, 322
`fanchart bounds border` key, 319
`fanchart complemented marker style` key, 331
`fanchart complemented segment style` key, 331
`fanchart descendant style` key, 334
`fanchart female style` key, 334
`fanchart inner offset` key, 314
`fanchart landscape from level` key, 320
`fanchart major angle` key, 314
`fanchart male style` key, 334
`fanchart marker colorwheel` key, 329
`fanchart marker malefemale` key, 327
`fanchart marker radial` key, 329
`fanchart marker relation` key, 328
`fanchart marker style` key, 327
`fanchart marker style for ids` key, 333
`fanchart marker style for levels` key, 332
`fanchart marker wave` key, 328
`fanchart minor angle` key, 314
`fanchart neuter style` key, 334
`fanchart open down` key, 316
`fanchart open for` key, 318
`fanchart open full` key, 315
`fanchart open left` key, 317
`fanchart open right` key, 317
`fanchart open up` key, 316
`fanchart outer offset` key, 314
`fanchart radii` key, 314
`fanchart reset bounds` key, 319
`fanchart root malefemale` key, 323
`fanchart root style` key, 323
`fanchart segment colorwheel` key, 326
`fanchart segment malefemale` key, 324
`fanchart segment radial` key, 326
`fanchart segment relation` key, 325

fanchart segment style key, 324
 fanchart segment style for ids key, 333
 fanchart segment style for levels key, 332
 fanchart segment wave key, 325
 fanchart sibling style key, 334
 fanchart template key, 335
 fanchart text landscape key, 321
 fanchart text portrait key, 321
 fanchart unrelated style key, 334
 fanchart-marker-definition key, 345
 fanchart-root-code key, 345
 fanchart-segment-code key, 345
 fanchart-segment-definition key, 345
 Female key, 245
 female key, 101, 165
 female value, 165, 199
 fill overzoom DBimage key, 201
 fill zoom DBimage key, 201
 fit value, 138, 139, 270
 fit to family key, 116
 fit to subtree key, 116
 Floruit key, 245
 floruit key, 170, 192
 floruit+ key, 170
 floruit- key, 170
 foreground key, 213
 formal graph value, 269
 french value, 247
 full value, 174, 184
 full marriage above value, 174, 275, 278
 full marriage below value, 174, 298–305
 full no marriage value, 174
 Funeralurn key, 245
 further distance key, 90

 g grammar, 10, 17, 19, 25, 26, 34, 55, 59, 60, 64, 65, 67, 69, 71, 73, 77, 78, 117, 225, 267, 284, 292, 294, 296, 298–305, 350, 352, 354
 genealogypicture environment, 57
 \genealogytree, 55
 genealogytree edges scope key, 207
 genealogytree extra edges scope key, 230
 \genealogytreeinput, 56
 german value, 245, 247
 german-austrian value, 247
 german-german value, 247
 \getree_fanchart_draw_path:n, 346
 \getree_fanchart_draw_path:nnn, 346
 \getree_fanchart_draw_root_style:n, 346
 \getree_fanchart_draw_segment_standard:, 346
 \getree_fanchart_if_complemented_node:TF, 346
 \getree_fanchart_if_complemented_node_p:, 346
 \getree_fanchart_set_color_colorwheel:n, 346
 \getree_fanchart_set_color_wave:n, 346
 \getree_fanchart_set_marker_style:n, 346
 \getree_fanchart_set_segment_style:n, 346

\getree_set_options_for_family:nn, 104
 \getree_set_options_for_node:nn, 95
 \getree_set_options_for_subtree:nn, 107
 GR value, 172
 Grammar
 c, 17, 19, 21, 55, 59, 60, 64, 73, 77, 78, 117, 120, 284, 311, 350
 child, 16, 25, 26, 34, 46, 55, 60, 64, 67, 69, 71, 77–80, 87, 89, 105, 106, 108, 128–130, 219, 261, 350–352, 354
 g, 10, 17, 19, 25, 26, 34, 55, 59, 60, 64, 65, 67, 69, 71, 73, 77, 78, 117, 225, 267, 284, 292, 294, 296, 298–305, 350, 352, 354
 input, 29, 74
 insert, 75
 p, 17, 19, 21, 32, 55, 59, 60, 64, 73, 77, 78, 117, 284, 292, 294, 296, 298–305, 350
 parent, 16, 17, 19, 20, 34, 55, 60, 64, 65, 71, 74, 77–80, 86, 88, 105, 106, 108, 120, 132–134, 219, 292, 294, 296, 298–305, 311, 312, 350
 sandclock, 34, 39, 55, 60, 64, 71, 106, 128, 130, 350
 union, 26, 27, 55, 64, 67, 69, 106, 128, 225, 231, 261, 267, 350–352, 354
 gtr set color colorwheel key, 330
 gtr set color series key, 330
 gtr set color wave key, 330
 gtr_Blue_1 color, 308
 gtr_Blue_2 color, 308
 gtr_Blue_3 color, 308
 gtr_Blue_4 color, 308
 gtr_Blue_5 color, 308
 gtr_Blue_6 color, 308
 gtr_Bright_Red color, 308
 gtr_Female_Background color, 273, 308
 gtr_Female_Frame color, 273, 308
 gtr_Male_Background color, 273, 308
 gtr_Male_Frame color, 273, 308
 gtr_Neuter_Background color, 273, 308
 gtr_Neuter_Frame color, 273, 308
 gtr_Peach_Back color, 308
 gtr_Peach_Frame color, 308
 gtr_Yellow_Back color, 308
 gtr_Yellow_Frame color, 308
 \gtrautosizebox, 61
 \gtrautosizebox*, 61
 \gtrBoxContent, 154
 \gtrcomplemented, 345
 \gtrDBage, 167
 \gtrDBcomment, 165
 \gtrDBimage, 38, 166
 \gtrDBimageopt, 166
 \gtrDBkekule, 167
 \gtrDBname, 165
 \gtrDBprofession, 166
 \gtrDBrelation, 167, 345
 \gtrDBrelationship, 167
 \gtrDBsex, 36, 165, 199, 345

- `\gtrDBshortname`, 165
- `\gtrDBuuid`, 166
- `\gtrdebugdrawcontour`, 261
- `\gtrDeclareDatabaseFormat`, 182
- `\gtrDrawSymbolicPortrait`, 310
- `\gtredgeset`, 207
- `gtreventlist` environment, 194
- `\gtrfanchart`, 312
- `gtrfanchartboundary` color, 322
- `\gtrfanchartinput`, 313
- `\gtrifagedefined`, 202
- `\gtrifchild`, 60
- `\gtrifcnode`, 59
- `\gtrifcommentdefined`, 196
- `\gtrifdatedefined`, 186
- `\gtrifdeceaseddefined`, 191
- `\gtrifeventdefined`, 191
- `\gtriffemale`, 199
- `\gtrifgnode`, 59
- `\gtrifimagedefined`, 200
- `\gtrifleaf`, 60
- `\gtrifleafchild`, 60
- `\gtrifleafparent`, 60
- `\gtrifmale`, 199
- `\gtrifnativitydefined`, 191
- `\gtrifnodeid`, 59
- `\gtrifparent`, 60
- `\gtrifplacedefined`, 190
- `\gtrifpnode`, 59
- `\gtrifprofessiondefined`, 197
- `\gtrifroot`, 60
- `\gtrifwedlockdefined`, 191
- `\gtrignorenode`, 118
- `\gtrignoresubtree`, 118
- `\gtrincludDBImage`, 200
- `gtrinfolist` environment, 198
- `\gtrkeysappto`, 58
- `\gtrkeysgappto`, 58
- `\gtrlanguage`, 247
- `\gtrlistseparator`, 194
- `\gtrloadlanguage`, 248
- `\gtrmakestack`, 369
- `\gtrnewstack`, 367
- `\gtrNodeBoxOptions`, 154
- `gtrNodeDimensions` key, 139, 143, 146, 149, 152
- `gtrNodeDimensionsLandscape` key, 139, 143, 146, 149, 152
- `\gtrnodefamily`, 59
- `\gtrnodeid`, 59
- `\gtrnodelevel`, 59
- `\gtrNodeMaxHeight`, 154
- `\gtrNodeMaxWidth`, 154
- `\gtrNodeMinHeight`, 154
- `\gtrNodeMinWidth`, 154
- `\gtrnodenumber`, 59
- `\gtrnodetype`, 59
- `\gtrparent1`, 309
- `\gtrparent2`, 309
- `\gtrparent3`, 309
- `\gtrparent4`, 310
- `\gtrparent5`, 310
- `\gtrparent6`, 310
- `\gtrparent7`, 310
- `\gtrParseDate`, 173
- `\gtrparserdebug`, 250
- `\gtrparserdebuginput`, 251
- `\gtrPrintAge`, 202
- `\gtrPrintComment`, 196
- `\gtrPrintDatabase`, 183
- `\gtrPrintDate`, 186
- `\gtrPrintEvent`, 191
- `\gtrPrintEventPrefix`, 191
- `gtrprintlist` environment, 194
- `\gtrPrintName`, 184
- `\gtrPrintPlace`, 190
- `\gtrPrintProfession`, 197
- `\gtrPrintSex`, 199
- `\gtrprocessordebug`, 252
- `\gtrprocessordebuginput`, 255
- `\gtrset`, 58
- `\gtrsetoptionsforfamily`, 104
- `\gtrsetoptionsfornode`, 95
- `\gtrsetoptionsforsubtree`, 107
- `\gtrstackpeek`, 368
- `\gtrstackpeekto`, 368
- `\gtrstackpop`, 368
- `\gtrstackpopto`, 368
- `\gtrstackpush`, 367
- `\gtrstacksize`, 367
- `\gtrsymBaptized`, 239
- `gtrsymbol` color, 237, 238
- `\gtrSymbolsFullLegend`, 243
- `\gtrSymbolsLegend`, 244
- `\gtrSymbolsRecordReset`, 243
- `\gtrSymbolsSetCreate`, 238
- `\gtrSymbolsSetCreateSelected`, 238
- `\gtrSymbolsSetDraw`, 238
- `\gtrsymBorn`, 239
- `\gtrsymBornoutofwedlock`, 239
- `\gtrsymBuried`, 241
- `\gtrsymDied`, 240
- `\gtrsymDiedonbirthday`, 239
- `\gtrsymDivorced`, 240
- `\gtrsymEngaged`, 240
- `\gtrsymFemale`, 241
- `\gtrsymFloruit`, 241
- `\gtrsymFuneralurn`, 241
- `\gtrsymKilled`, 240
- `\gtrsymMale`, 241
- `\gtrsymMarried`, 240
- `\gtrsymNeuter`, 242
- `\gtrsymPartnership`, 240
- `\gtrsymStillborn`, 239
- `\gtruselibrary`, 13
- `hide single leg` key, 215
- `id` key, 92, 166
- `id content interpreter` key, 158

- id prefix key, 94
- id suffix key, 94
- if image defined key, 200
- ignore key, 117
- ignore value, 168
- ignore family database key, 219
- ignore level key, 119
- ignore node key, 118
- ignore parent childs key, 120
- ignore subtree key, 118
- image key, 166
- image prefix key, 201
- imageopt key, 166
- info separators key, 198
- input grammar, 29, 74
- insert grammar, 75
- insert after family key, 122
- insert after node key, 121
- insert at begin family key, 123
- insert at end family key, 124
- insert for childless families key, 129
- insert for childless families level
 - limit key, 131
- insert phantom for childless families key, 130
- inwards value, 321
- italian value, 247
- JU value, 172
- kekule key, 167
- Keys
 - /gtr/
 - add child, 221
 - add parent, 222
 - adjust node, 113
 - adjust position, 112
 - affected, 272
 - after parser, 111
 - after tree, 115
 - age code, 202
 - autofill parents female male, 134
 - autofill parents female male*, 134
 - autofill parents male female, 133
 - autofill parents male female*, 133
 - autofill parents none, 134
 - autofill parents unspecific, 132
 - autofill parents unspecific*, 132
 - box, 98
 - box clear, 98
 - calendar print, 188
 - calendar text for, 188
 - carrier, 272
 - child distance, 87
 - child distance in child graph, 87
 - child distance in parent graph, 86
 - code, 136
 - comment code, 196
 - complemented, 135
 - complemented family, 135

- complemented phantom, 135
- content interpreter, 155
- content interpreter code, 156
- content interpreter content, 156
- content interpreter id and content, 159
- database content interpreter, 158
- database format, 174
- database unknown key, 168
- date code, 188
- date format, 186
- date range after, 189
- date range before, 189
- date range full, 189
- date range separator, 189
- deceased, 272
- deletion content interpreter, 157
- disconnect, 225
- distance, 96
- edges, 204
- edges down, 233
- edges down by, 233
- edges for family, 206
- edges for subtree, 206
- edges shift, 232
- edges up, 233
- edges up by, 233
- empty name text, 185
- event code, 192
- event format, 192
- event text, 192
- extra edges, 226
- extra edges for families, 227
- extra edges for family, 227
- extra edges prepend, 228
- extra edges prepend for families, 229
- extra edges prepend for family, 229
- family, 105
- family box, 99
- family database, 219
- family edges, 205
- family extra edges, 226
- family extra edges prepend, 228
- family label, 218
- fanchart ancestor style, 334
- fanchart angles, 315
- fanchart boundary color, 322
- fanchart boundary width, 322
- fanchart bounds border, 319
- fanchart complemented marker style, 331
- fanchart complemented segment style, 331
- fanchart descendant style, 334
- fanchart female style, 334
- fanchart inner offset, 314
- fanchart landscape from level, 320
- fanchart major angle, 314

fanchart male style, 334
 fanchart marker colorwheel, 329
 fanchart marker malefemale, 327
 fanchart marker radial, 329
 fanchart marker relation, 328
 fanchart marker style, 327
 fanchart marker style for ids, 333
 fanchart marker style for levels, 332
 fanchart marker wave, 328
 fanchart minor angle, 314
 fanchart neuter style, 334
 fanchart open down, 316
 fanchart open for, 318
 fanchart open full, 315
 fanchart open left, 317
 fanchart open right, 317
 fanchart open up, 316
 fanchart outer offset, 314
 fanchart radii, 314
 fanchart reset bounds, 319
 fanchart root malefemale, 323
 fanchart root style, 323
 fanchart segment colorwheel, 326
 fanchart segment malefemale, 324
 fanchart segment radial, 326
 fanchart segment relation, 325
 fanchart segment style, 324
 fanchart segment style for ids, 333
 fanchart segment style for levels, 332
 fanchart segment wave, 325
 fanchart sibling style, 334
 fanchart template, 335
 fanchart text landscape, 321
 fanchart text portrait, 321
 fanchart unrelated style, 334
 fanchart-marker-definition, 345
 fanchart-root-code, 345
 fanchart-segment-code, 345
 fanchart-segment-definition, 345
 female, 101
 further distance, 90
 id, 92
 id content interpreter, 158
 id prefix, 94
 id suffix, 94
 ignore, 117
 ignore family database, 219
 ignore level, 119
 ignore node, 118
 ignore parent childs, 120
 ignore subtree, 118
 info separators, 198
 insert after family, 122
 insert after node, 121
 insert at begin family, 123
 insert at end family, 124
 insert for childless families, 129
 insert for childless families
 level limit, 131
 insert phantom for childless families, 130
 keysfrom, 136
 label, 217
 label database options, 219
 label options, 217
 language, 247
 level, 109
 level distance, 83
 level n, 110
 level size, 84
 list separators, 195
 list separators hang, 195
 male, 101
 name, 184
 name code, 185
 name font, 185
 neuter, 101
 nick code, 184
 no content interpreter, 157
 node, 96
 node box, 98
 node processor, 138
 node size, 85
 node size from, 86
 nullify edge level shift, 235
 options for family, 104
 options for node, 95
 options for subtree, 107
 parent distance, 89
 parent distance in child graph, 89
 parent distance in parent graph, 88
 phantom, 125
 phantom*, 127
 pivot, 97
 pivot shift, 106
 place text, 190
 pref code, 184
 proband level, 111
 processing, 138
 profession code, 197
 remove child, 224
 remove parent, 224
 reset, 136
 reset edge level shift, 234
 set position, 111
 show, 265
 show family, 267
 show id, 265
 show level, 266
 show number, 266
 show type, 267
 subtree, 108
 subtree box, 99
 subtree edges, 206
 subtree label, 218
 surn code, 184

- switch edge level shift, 234
- symbols record reset, 243
- tcbset, 115
- template, 269
- template horizontal border, 306
- template vertical border, 306
- tikz, 103
- tikzpicture, 114
- tikzset, 114
- timeflow, 80
- tree offset, 111
- turn, 100
- use family database, 219
- /gtr/database/
 - age, 167
 - ancestor, 167
 - baptism, 169
 - baptism+, 169
 - baptism-, 169
 - birth, 169
 - birth+, 169
 - birth-, 169
 - burial, 171
 - burial+, 171
 - burial-, 171
 - comment, 165
 - death, 170
 - death+, 170
 - death-, 170
 - descendant, 167
 - divorce, 170
 - divorce+, 170
 - divorce-, 170
 - engagement, 170
 - engagement+, 170
 - engagement-, 170
 - female, 165
 - floruit, 170
 - floruit+, 170
 - floruit-, 170
 - id, 166
 - image, 166
 - imageopt, 166
 - kekule, 167
 - male, 165
 - marriage, 170
 - marriage+, 170
 - marriage-, 170
 - name, 165
 - neuter, 165
 - profession, 166
 - relation, 167
 - relationship, 167
 - sex, 165
 - shortname, 165
 - sibling, 167
 - unrelated, 167
 - uuid, 166
 - viewport, 166
- /gtr/debug/
 - contour, 263
 - family id, 262
 - family number, 262
- /gtr/edge/
 - anchoring, 214
 - background, 214
 - custom, 211
 - foreground, 213
 - hide single leg, 215
 - mesh, 210
 - no background, 214
 - no foreground, 213
 - none, 212
 - perpendicular, 208
 - rounded, 208
 - swing, 209
 - xshift, 215
 - yshift, 216
- /gtr/event prefix/
 - baptism, 192
 - birth, 191
 - burial, 192
 - death, 192
 - divorce, 192
 - engagement, 192
 - floruit, 192
 - marriage, 192
- /gtr/event prefix/birth/
 - died, 192
 - out of wedlock, 191
 - stillborn, 192
- /gtr/event prefix/burial/
 - cremated, 192
- /gtr/event prefix/death/
 - killed, 192
- /gtr/event prefix/marriage/
 - other, 192
- /gtr/library/
 - all, 13
 - debug, 13
 - fanchart, 13
 - templates, 13
- /gtr/symlang/
 - Baptized, 245
 - Born, 245
 - Bornoutofwedlock, 245
 - Buried, 245
 - Died, 245
 - Diedonbirthday, 245
 - Divorced, 245
 - Engaged, 245
 - Female, 245
 - Floruit, 245
 - Funeralurn, 245
 - Killed, 245
 - Male, 245
 - Married, 245
 - Neuter, 245

- Partnership, 245
- Stillborn, 245
- /tcb/
 - female, 101
 - gtrNodeDimensions, 139, 143, 146, 149
 - gtrNodeDimensionsLandscape, 139, 143, 146, 149
 - if image defined, 200
 - image prefix, 201
 - male, 101
 - neuter, 101
- /tikz/
 - fill overzoom DBimage, 201
 - fill zoom DBimage, 201
 - fit to family, 116
 - fit to subtree, 116
 - genealogytree edges scope, 207
 - genealogytree extra edges scope, 230
 - gtr set color colorwheel, 330
 - gtr set color series, 330
 - gtr set color wave, 330
 - gtrNodeDimensions, 152
 - gtrNodeDimensionsLandscape, 152
- keysfrom key, 136
- Killed key, 245
- killed key, 192
- killed value, 170
- \l_gettree_fanchart_angle_a_tl, 345
- \l_gettree_fanchart_angle_b_tl, 345
- \l_gettree_fanchart_id_tl, 346
- \l_gettree_fanchart_level_tl, 346
- \l_gettree_fanchart_line_width_tl, 346
- \l_gettree_fanchart_major_angle_tl, 345
- \l_gettree_fanchart_minor_angle_tl, 345
- \l_gettree_fanchart_offset_a_tl, 345
- \l_gettree_fanchart_offset_b_tl, 345
- \l_gettree_fanchart_radius_a_tl, 345
- \l_gettree_fanchart_radius_b_tl, 345
- \l_gettree_fanchart_ratio_tl, 346
- label key, 217
- label database options key, 219
- label options key, 217
- language key, 247
- left value, 80, 100, 112, 113, 286, 289, 292, 294, 296
- letterpaper 3 value, 301, 306
- letterpaper 4 value, 301, 306
- level key, 109
- level distance key, 83
- level n key, 110
- level size key, 84
- list separators key, 195
- list separators hang key, 195
- m-d-yyyy value, 187
- m.d/yyyy value, 187
- m/d/yyyy value, 187
- Male key, 245
- male key, 101, 165
- male value, 165, 199
- malefemale relation value, 336
- malefemale sober value, 336
- marriage key, 170, 192
- marriage value, 174, 219
- marriage+ key, 170
- marriage- key, 170
- Married key, 245
- medical value, 272
- medium value, 174, 286, 289
- medium marriage above value, 174
- medium marriage below value, 174
- medium no marriage value, 174, 291
- mesh key, 210
- mm-dd-yyyy value, 187
- mm.dd/yyyy value, 187
- mm/dd/yyyy value, 187
- mon d yyyy value, 187
- mon.d yyyy value, 187
- month d yyyy value, 187
- name key, 165, 184
- name value, 174
- name code key, 185
- name font key, 185
- Neuter key, 245
- neuter key, 101, 165
- neuter value, 165
- \nick, 184
- nick code key, 184
- no background key, 214
- no content interpreter key, 157
- no foreground key, 213
- \node, 138, 152
- node key, 96
- node box key, 98
- node processor key, 138
- node size key, 85
- node size from key, 86
- none key, 212
- none value, 97, 188, 263
- nullify edge level shift key, 235
- off value, 100
- options for family key, 104
- options for node key, 95
- options for subtree key, 107
- other key, 192
- other value, 170
- out of wedlock key, 191
- out of wedlock value, 169
- outwards value, 321
- p grammar, 17, 19, 21, 32, 55, 59, 60, 64, 73, 77, 78, 117, 284, 292, 294, 296, 298–305, 350
- parent grammar, 16, 17, 19, 20, 34, 55, 60, 64, 65, 71, 74, 77–80, 86, 88, 105, 106, 108, 120, 132–134, 219, 292, 294, 296, 298–305, 311, 312, 350

parent value, 97, 225
 parent distance key, 89
 parent distance in child graph key, 89
 parent distance in parent graph key, 88
 Partnership key, 245
 periphery value, 214
 perpendicular key, 208
 phantom key, 125
 phantom* key, 127
 pivot key, 97
 pivot shift key, 106
 place text key, 190
 portuguese value, 247
 \pref, 184
 pref code key, 184
 prefix date value, 192
 prefix date place value, 192
 proband level key, 111
 processing key, 138
 profession key, 166
 profession code key, 197

 radial malefemale value, 343
 radial opulent value, 344
 radial rich value, 343
 radial serious value, 342
 radial sober value, 342
 relation key, 167
 relationship key, 167
 remove child key, 224
 remove parent key, 224
 reset key, 136
 reset edge level shift key, 234
 right value, 80, 100, 112, 113, 274
 rounded key, 208
 rounded value, 41

 sandclock grammar, 34, 39, 55, 60, 64, 71, 106, 128, 130, 350
 save value, 168
 set position key, 111
 sex key, 165
 short value, 174, 184
 short marriage above value, 174
 short marriage below value, 174
 short no marriage value, 174, 281, 284
 shortname key, 165
 show key, 265
 show family key, 267
 show id key, 265
 show level key, 266
 show number key, 266
 show type key, 267
 sibling key, 167
 sibling value, 167
 signpost value, 270
 spanish value, 247
 spartan value, 335
 Stillborn key, 245
 stillborn key, 192

 stillborn value, 169
 subtree key, 108
 subtree box key, 99
 subtree edges key, 206
 subtree label key, 218
 \surn, 184
 surn code key, 184
 swedish value, 247
 swing key, 209
 switch edge level shift key, 234
 symbol value, 174
 symbol nodes value, 270
 symbols record reset key, 243

 \tcboxEXTERNALIZE, 49
 \tcbox, 138, 146, 149
 tcbox value, 138, 146
 tcbox* value, 138, 149, 269–272, 274
 \tcboxfit, 138, 139, 161
 tcbset key, 115
 tcolorbox environment, 138, 143
 tcolorbox value, 138, 143
 template key, 269
 template horizontal border key, 306
 template vertical border key, 306
 templates key, 13
 tikz key, 103
 tikznode value, 103, 138, 152
 tikzpicture environment, 55, 57, 312
 tikzpicture key, 114
 tikzset key, 114
 timeflow key, 80
 tiny boxes value, 271
 tiny circles value, 271
 tree offset key, 111
 turn key, 100
 typical value, 186

 union grammar, 26, 27, 55, 64, 67, 69, 106, 128, 225, 231, 261, 267, 350–352, 354
 unrelated key, 167
 unrelated value, 167
 up value, 80
 upsidedown value, 100
 use family database key, 219
 uuid key, 166

 Values
 a3paper 5, 300, 306
 a4paper 3, 298, 306
 a4paper 4, 299, 306
 above, 112, 113
 AD, 172
 ahnentafel 3, 292
 ahnentafel 4, 294
 ahnentafel 5, 296
 all, 188
 all but AD, 172, 188
 ancestor, 167
 auto, 321

BC, 172
 below, 112, 113
 both, 97, 225, 263
 ca, 172
 caAD, 172
 caBC, 172
 catalan, 247
 center, 214
 child, 97, 225
 chinese, 247
 clockwise, 321
 colorwheel malefemale, 338
 colorwheel opulent, 339
 colorwheel rich, 338
 colorwheel serious, 337
 colorwheel sober, 337
 counterclockwise, 321
 cremated, 171
 d M yyyy, 186
 d mon yyyy, 186
 d mon.yyyy, 186
 d month yyyy, 186
 d-M-yyyy, 187
 d-m-yyyy, 187
 d-mon-yyyy, 187
 d-month-yyyy, 187
 d.M.yyyy, 186
 d.m.yyyy, 186
 d.mon.yyyy, 186
 d.month yyyy, 186
 d/m yyyy, 186
 d/M/yyyy, 186
 d/m/yyyy, 186
 d/mon/yyyy, 186
 d/month/yyyy, 186
 danish, 247
 database, 35, 133, 134, 138, 161, 275, 278,
 281, 284, 286, 289, 291, 292, 294, 296,
 298–305
 database pole, 275, 277, 278
 database pole reduced, 277
 database poleportrait, 278, 280
 database poleportrait reduced, 280
 database portrait, 281, 283
 database portrait reduced, 283
 database relationship, 291
 database sideways, 286, 288, 289
 database sideways reduced, 288
 database sidewaysportrait, 289, 290
 database sidewaysportrait reduced,
 290
 database traditional, 284, 285
 database traditional reduced, 285
 date, 192
 dd mm yyyy, 186
 dd mon yyyy, 186
 dd mon.yyyy, 186
 dd-mm-yyyy, 186
 dd-mon-yyyy, 187
 dd-month-yyyy, 187
 dd.mm.yyyy, 186
 dd.mon.yyyy, 186
 dd/mm yyyy, 186
 dd/mm/yyyy, 186
 dd/mon/yyyy, 186
 dd/month/yyyy, 186
 ddmonyyyy, 187
 descendant, 167
 died, 169
 directory, 274
 display 16:10 3, 305, 306
 display 16:10 4, 305, 306
 display 16:10 5, 305, 306
 display 16:9 3, 302, 306
 display 16:9 4, 303, 306
 display 16:9 5, 304, 306
 down, 80, 211, 272, 284, 291
 dutch, 247
 east, 263
 empty, 174
 english, 244, 247
 error, 168
 female, 165, 199
 fit, 138, 139, 270
 formal graph, 269
 french, 247
 full, 174, 184
 full marriage above, 174, 275, 278
 full marriage below, 174, 298–305
 full no marriage, 174
 german, 245, 247
 german-austrian, 247
 german-german, 247
 GR, 172
 ignore, 168
 inwards, 321
 italian, 247
 JU, 172
 killed, 170
 left, 80, 100, 112, 113, 286, 289, 292, 294,
 296
 letterpaper 3, 301, 306
 letterpaper 4, 301, 306
 m-d-yyyy, 187
 m.d.yyyy, 187
 m/d/yyyy, 187
 male, 165, 199
 malefemale relation, 336
 malefemale sober, 336
 marriage, 174, 219
 medical, 272
 medium, 174, 286, 289
 medium marriage above, 174
 medium marriage below, 174
 medium no marriage, 174, 291
 mm-dd-yyyy, 187
 mm.dd.yyyy, 187
 mm/dd/yyyy, 187

- mon d yyyy, 187
- mon.d yyyy, 187
- month d yyyy, 187
- name, 174
- neuter, 165
- none, 97, 188, 263
- off, 100
- other, 170
- out of wedlock, 169
- outwards, 321
- parent, 97, 225
- periphery, 214
- portuguese, 247
- prefix date, 192
- prefix date place, 192
- radial malefemale, 343
- radial opulent, 344
- radial rich, 343
- radial serious, 342
- radial sober, 342
- right, 80, 100, 112, 113, 274
- rounded, 41
- save, 168
- short, 174, 184
- short marriage above, 174
- short marriage below, 174
- short no marriage, 174, 281, 284
- sibling, 167
- signpost, 270
- spanish, 247
- spartan, 335
- stillborn, 169
- swedish, 247
- symbol, 174
- symbol nodes, 270
- tcbox, 138, 146
- tcbox*, 138, 149, 269–272, 274
- tcolorbox, 138, 143
- tikznode, 103, 138, 152
- tiny boxes, 271
- tiny circles, 271
- typical, 186
- unrelated, 167
- up, 80
- upsidedown, 100
- warn, 168
- wave malefemale, 340
- wave opulent, 341
- wave rich, 341
- wave serious, 340
- wave sober, 339
- west, 263
- yyyy, 187
- yyyy d/m, 187
- yyyy mm dd, 187
- yyyy mon dd, 187
- yyyy month d, 187
- yyyy-mm-dd, 187
- yyyy-mon-dd, 187
- yyyy-mon-dd, 187
- yyyy.m.d, 187
- yyyy.M.d., 187
- yyyy.m.d., 187
- yyyy.mm.dd, 187
- yyyy.mon.d., 187
- yyyy.month d., 187
- yyyy/m/d, 187
- yyyy/mm/dd, 187
- yyyymmdd, 187
- yyyymondd, 187
- viewport key, 166
- warn value, 168
- wave malefemale value, 340
- wave opulent value, 341
- wave rich value, 341
- wave serious value, 340
- wave sober value, 339
- west value, 263
- xshift key, 215
- yshift key, 216
- yyyy value, 187
- yyyy d/m value, 187
- yyyy mm dd value, 187
- yyyy mon dd value, 187
- yyyy month d value, 187
- yyyy-mm-dd value, 187
- yyyy-mon-d value, 187
- yyyy-mon-dd value, 187
- yyyy.m.d value, 187
- yyyy.M.d. value, 187
- yyyy.m.d. value, 187
- yyyy.mm.dd value, 187
- yyyy.mon.d. value, 187
- yyyy.month d. value, 187
- yyyy/m/d value, 187
- yyyy/mm/dd value, 187
- yyyymmdd value, 187
- yyyymondd value, 187